

ଓଡିଶା ବିଦ୍ୟୁତ ଶକ୍ତି ସଂଚାରଣ ନିଗମ ଲିଡ.
ODISHA POWER TRANSMISSION CORPORATION LIMITED



(A Government of Odisha Undertaking)

CIN: U40102OR2004SGC007553

Office of the Deputy General Manager (Electrical)
E.H.T. (O&M) Division, Laltikra, Bolangir – 767002,

E-Mail: ehtm.div.blm@optcl.co.in .

ANNEXURE – I

TENDER CALL NOTICE-07/2020-21

Sealed Tenders in Double copy of tender papers in single envelope are invited by the undersigned from Electrical contractor having valid HT (Electrical) License with 3 years Civil work experience in any EHV S/S(33Kv & above) & having Valid PAN card, G.S.T certificate for "Repairing of retaining wall inside switch-yard of 132/33kv GSS Bolangir".

SI No	Description of work	Estimate Cost	EMD Cost Rs.	Tender Paper Cost Rs.
1	REPAIRING OF RETAINING WALL INSIDE SWITCH-YARD OF 132/33KV GSS BOLANGIR".	Rs.536498.00	Rs.5365.00 (Refundable)	Rs.4000.00+12%GST=Rs.4480.00(Non Refundable)

The tender document can be made available in the office of the undersigned on payment of requisite amount **Rs.4000.00+12%GST=Rs.4480.00** towards cost of tender document by cash/ Bank draft drawn in favour of DGM, E.H.T. (O&M) Division, OPTCL, Bolangir, payable at Bolangir. The bid should have accompanied with two sets of tender papers & self attested Photocopy of PAN, GST, HT License & EMD in shape of Demand draft amounting **Rs.5365.00** (1% of the estimated cost) in favour of DGM, E.H.T. (O&M) Division, OPTCL, Bolangir, payable at Bolangir. The Tender will be opened in presence of Tenderers or their authorised representatives possessing original authorisation letter. Incomplete Tender and Tender without EMD shall be rejected.


Date of Sale of Tender Paper: From dt.11.01.2021 to dt.28.01.2021 (During Office Hours)

Last Date of receipt of Tender Paper: dt.29.01.2021 up to 01.30 PM.

Date of Opening of Tender Paper: dt.29.01.2021 at 4.00 PM.


If the last date of receipt/opening of Tender falls on a Holiday, then the tender paper will be received/ opened in the next working days.

The undersigned reserves the right to accept or reject any or all tenders without assigning any reason thereof.



Deputy General Manager
EHT (O&M) Division Bolangir.

SCOPE OF WORK:**Name of work:-Repair of Retaining Wall inside 132/33 KV Grid Sub-Station, Laltikira, Bolangir**

Sl	Description of Items.	Quantity	Unit	Rate	Amount
1.	Dismantling brick or stone masonry in lime or cement mortar above 3m. height including stacking the useful materials for reuse and removing the debris within 50m, Lead	9.45	Cum		
2.	Earth Work in excavation in foundation trenches in ordinary soil within 50m, initial lead and 1.5m, initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per direction of the Engineer-in-charge	90.27	Cum		
3.	Filling in Foundation and plinth with sand watered and rammed, including cost of sand, all labours, T&P reqd. etc. complete.	4.59	Cum		
4.	Cement Concrete (1:4:8) with 4cm size hard granite metal including cost of all materials, labours T&P reqd. etc. complete.	3.06	Cum		
5.	Cement concrete (1:1/2:3) with 12mm size broken hard granite chips for R.C.C. works including hoisting and lying including cost of all materials, labours, T&P reqd. etc. complete. (In Foundation & Plinth)	13.39	Cum		
6.	Cement concrete (1:1/2:3) with 12mm size broken hard granite chips for R.C.C. works including hoisting and lying including cost of all materials, labours, T&P reqd. etc. complete. (In Column, wall & Beam)	13.39	Cum		
7.	Supplying, fitting and placing uncoated HYSD bar reinforcement complete as drawing and technical specification, including cost of all materials, labours, T&P required etc. complete.	17.35	Qntl.		
8.	16mm. Thick cement plaster (1:6) over brick or stone masonry, including cost of all materials, labours, T&P required etc. complete.	53.55	Sq.m.		
9.	12mm. Thick cement plaster (1:6) with cement mortar over brick work, including cost of all materials labours, T&P required etc. complete.	53.55	Sq.m.		
10.	Priming 1 coat with any approved Primer, including cost of all materials, labours, T&P required etc. complete. Data for 9.30 Sqm.	107.1	Sq.m.		
11	Supplvina & Painting two Coats of	107 1	Sq m.		


Deputy General Manager
H.T. (O&M) Division
T.C. TD Balangir

	weather coats over wall surfaces, including cost of all materials, labours, T&P required etc. complete.				
12.	Supplying and fixing f Thermo Cool material in Expansion and Contraction Joint, including cost of all materials and labours with T&P as required for the work etc. complete as per the direction of EIC.	4	Rmt		
13.	Cement Concrete with proportion (1:2:4) with using 12mm size hard crusher broken granite chips including cost of all materials and of all labours with T&P as required for the work etc. Complete.	0.32	Cum		
14.	Filling in Foundation and plinth with excavated earth watered and rammed, including cost of sand, all labours, T&P reqd. etc. complete.	90.27	Cum		

 P
20/01/21

**Deputy General Manager
EHT (O&M) Division Bolangir.**