



# ଓଡ଼ିଶା ବିଦ୍ୟୁତ୍ ଶକ୍ତି ସଂଚାରଣ ନିଗମ ଲି.ଓ.

ODISHA POWER TRANSMISSION CORPORATION LIMITED

(A Government of Odisha Undertaking)

Regd. Office: Janpath: Bhubaneswar-751022.

Telephone: (0674) 2540051 (EPABX), Website: www.optcl.co.in

CIN: U4102OR2004SGC007553

OFFICE OF THE DY. GENERAL MANAGER: ELECT.EHT (O & M) DIVISION, MERAMUNDALI  
AT: KANTABANIA (400/220/132/33 KV GRID S/S), P.O: KUSUPANGA-759121, DIST: DHENKANAL (ODISHA)  
Email: [ehm.div.mrm@optcl.co.in](mailto:ehm.div.mrm@optcl.co.in) GSTN: 21AAACO7873L1Z6

NO.EHT (O&M)/MRM/TECH/72

Dt.17.02.2021

## **CORRIGENDUM NO-01 TO TENDER CALL NOTICE NO. 01 / 2020-21**

With reference to this office Tender Call Notice No. 01/2020-21 regarding construction of RCC slab & laying on cable trench inside 400 kV S/Y at 400/220/132 kV Grid S/S, Meramundali under EHT (O&M) Division, Meramundali, the following correction is being made in the UNIT of SL. No. 2 provided in the Price schedule. In place of existing entry please read the Price Schedule as follows,

(SECTION-IV)

### **PRICE SCHEDULE**

<b>Construction of RCC slab &amp; laying on cable trench inside 400 kV S/Y at Grid S/S, Meramundali.</b>					
<b>SL. No</b>	<b>Name of works</b>	<b>Unit</b>	<b>Qty.</b>	<b>Rate (in Rs.)</b>	<b>Amount (in Rs.)</b>
1	Reinforcement :- Supply of all materials , good quality planks ,ballas, shuttering plates for centring, shuttering, supply of good quality 20mm machine broken granite chips , good quality river sand & concreting , curing for cable trench slab as per IS:4156 including cost of taxes royalties lead lift , labour and T & P with cost of cement & without steel . As per above specification and ration of concrete (1:1.5:3) with cost of cement & without steel.	Cum	54.844		
2	Cutting ,bending ,binding placing in position of steel rods for slab concreting including cost of binding wires with supply of all size rods(TATA/RINL/SAIL make)	Qntl	68.471		
3	Rigid smooth centring and shuttering for RCC works including false work and dismantling then after casting etc. Plinth band, foundation and footing, base of column, mass concrete etc.	Sqm	414.38		
				Add GST @ 18%	
				Grand Total	

(Rupees.....) Only

**All other terms & conditions and specification related to the aforesaid Tender Call Notice shall remain same.**

Sd-/

**GENERAL MANAGER (Elect.)**

EHT (O&M), Division, Meramundali

- C.C:**
1. Chief General Manager (O&M), OPTCL, BBSR
  2. Sr. General Manager, (O & M – II), Meramundali
  3. General Manager EHT (O&M), Circle, Chainpal.
  4. Deputy General Manager (F) CIAC, OPTCL, BBSR.