

**ODISHA POWER TRANSMISSION CORPORATION LIMITED**

**NAME OF THE WORK:-Design, Supply and Installation of 2X160MVA Auto Transformer & 2X40 MVA Power Transformer,for 220/132/33 KV Out Door Type GIS Grid Sub-station at ,Kuakhia in Odisha State of India under PACKAGE-3A Under Japan International Cooperation Agency (JICA)'s ODA Loan.**

**Loan Agreement No: [ID-P245] - FB No: [CPC/JICA/ICB/03A/19-20]- Reference Identification No: [OPTCL/JICA/PKG-3A]**

**Schedule No. 1. Plant Supplied from Abroad (Sub-station )**

**NAME OF THE BIDDER**

Sl. No.	DESCRIPTION OF ITEMS(SCHEDULE-2A-SS) SUPPLY OF FOLLOWING EQUIPMENT & MATERIALS (As per Technical Specification)	Code <sup>1</sup>	Unit	NAME OF THE WORK: Construction of 2*160MVA, & 2*40 MVA, 220/132 KV Open GIS & 33KV INDOOR GIS WITH SAS at KUAKHIA, JAJPUR District.	Unit Price <sup>2</sup>		Total Price <sup>2</sup>
					In Foreign Currency	CIP	
1	2	3	4	5	6		
1	2000A, 50kA for 3s, Double Busbar Circuit Breaker (Circuit breaker shall be E2-C2-M2 class as per IEC 62271-100) arrangement. 245kV OUTDOOR GIS EQUIPMENT as per latest IEC standard & type tested equipment as per technical specification, with open future proof & flexible system in line with IEC 61850 & IEC 62271-203.						
1.1	245kV, 2000A, 50kA for 3 sec (Busbar, CB, Disconnecter, Grounding Switch & CT), SF6 gas insulated ICT Feeder Bay Module each comprising of SF6 gas insulated Single Pole Circuit Breaker (1 Set), Single Phase Current Transformer (6 Nos), Motorised Busbar 3 Phase Disconnecter (2 Nos), Motorised Disconnecter (1 No), Motorised safety Grounding switch (3 Nos), Local Control Cubicle, SF6 gas monitoring system for complete bay, SF6 bus duct termination arrangement (3 Nos), PD sensor [adequate number of UHF sensors in the offered GIS equipment(1 no in each gas compartment) for detection of Partial discharge (of 5 pC and above) as per IEC 60270 through Partial Discharge (PD) monitoring system], different gas compartment, O-ring & gaskets, Nuts, Bolts & Washers for Outdoor use, Absorbent, Limit Switch, SF6 Gas, etc. to complete <b>ICT Feeder Bay Module</b> & its earthing arrangement with earthing strips of adequate size (as per IEEE Std 80-2013 to protect operating staff against any hazardous touch voltages and electro-magnetic interferences) as per the technical specification.		Set	2			

1.2	245kV, 2000A, 50kA for 3 sec (Busbar, CB, Disconnecter, Grounding switch, CT & PT), SF6 gas insulated Line Feeder Bay Module each comprising of SF6 gas insulated Single Pole Circuit Breaker (1 Set), Single Phase Current Transformer (6 Nos), Single phase Line Potential Transformer with disconnecting link (4 winding) (3 Nos), Motorised 3 Phase Busbar Disconnecter (2 Nos), Motorised safety Grounding switch (2 Nos), Motorised 3 Phase Disconnecter with high speed fault making Motorised Grounding switch (1 No), Local Control Cubicle, SF6 gas monitoring system for complete bay, SF6 bus duct termination arrangement (3 Nos), PD sensor [adequate number of UHF sensors in the offered GIS equipment(1 no in each gas compartment) for detection of Partial discharge (of 5 pC and above) as per IEC 60270 through Partial Discharge (PD) monitoring system], different gas compartment, O-ring & gaskets, Nuts, Bolts & Washers for Outdoor use, Absorbent, Limit Switch, SF6 Gas, etc. to complete <b>Line Feeder Bay Module</b> & its earthing arrangement with earthing strips of adequate size (as per IEEE Std 80-2013 to protect operating staff against any hazardous touch voltages and electro-magnetic interferences) as per the technical specification.		Set	4			
1.3	245kV, 2000A, 50kA for 3 sec (Busbars, Disconnecter, Grounding switch & bus PT), 1 Phase Isolated Bus-PT Bay Module comprising of SF6 gas insulated metal enclosed busbars each enclosed in bus enclosures running along the length of the switchgear to interconnect each of circuit breaker bay module. Each busbar set shall be complete with Single phase bus Potential Transformer (4 winding) (3 Nos), Motorised 3 Phase Disconnecter (1 No) , Motorised Busbar safety Grounding switch (1 No), Local Control Cubicle, SF6 gas monitoring system PD sensor [adequate number of UHF sensors in the offered GIS equipment(1 no in each gas compartment) for detection of Partial discharge (of 5 pC and above) as per IEC 60270 through Partial Discharge (PD) monitoring system], different gas compartment, O-ring & gaskets, Nuts, Bolts & Washers for Outdoor use, Absorbent, Limit Switch, SF6 Gas, etc. to complete the bus & its earthing arrangement with earthing strips of adequate size (as per IEEE Std 80-2013 to protect operating staff against any hazardous touch voltages and electro-magnetic interferences) as per the technical specification.		Set	1			
1.4	245kV, 2000A, 50kA for 3 sec (CB, Disconnecter, Grounding switch & CT), SF6 gas insulated <b>Bus Coupler Bay Module</b> comprising of SF6 gas insulated Single Pole Circuit Breaker (1 Set), Single Phase Current Transformer (6 Nos), Motorised 3 Phase Disconnecter (2 Nos), Motorised safety Grounding switch (2 Nos), Local Control Cubicle, SF6 gas monitoring system, PD sensor [adequate number of UHF sensors in the offered GIS equipment(1 no in each gas compartment) for detection of Partial discharge (of 5 pC and above) as per IEC 60270 through Partial Discharge (PD) monitoring system], different gas compartment, O-ring & gaskets, Nuts, Bolts & Washers for Outdoor use, Absorbent, Limit Switch, SF6 Gas, etc. to complete Bus Coupler Bay Module & its earthing arrangement with earthing strips of adequate size (as per IEEE Std 80-2013 to protect operating staff against any hazardous touch voltages and electro-magnetic interferences) as per the technical specification.		Set	1			
1.5	245kV, 2000A, 50 kA, 3 sec, single phase, SF6 gas Insulated Bus Duct outside GIS Bay along with associated Support structure arrangement bends, joints,accessories, & its earthing arrangement with earthing strips of adequate size (as per IEEE Std 80-2013 to protect operating staff against any hazardous touch voltages and electro-magnetic interferences) as per the technical specification.		RM	620			

1.6	245kV, 2000A, 50kA SF6/Air BUSHING (Bushing shall be of Polymer / composite insulator type and shall be seamless sheath of a silicone rubber compound. The hollow silicone composite insulators shall comply as per IEC 61462 and IEC 62217. The design of the composite insulators shall be tested and verified according to IEC 61462) FOR CONNECTING GIS TO AIS along with support structure.		No	18			
2	<b>2000A, 40kA for 3s, Double Busbar Circuit Breaker (Circuit breaker shall be E2-C2-M2 class as per IEC 62271-100) arrangement.</b> <b>145kV OUTDOOR GIS EQUIPMENT as per latest IEC standard &amp; type tested equipment as per technical specification, with open future proof &amp; flexible system in line with IEC 61850 &amp; IEC 62271-203.</b>						
2.1	145kV, 2000A, 40kA for 3 sec (Busbars, CB, Disconnecter, Grounding Switch & CT), SF6 gas insulated <b>ICT Feeder Bay Module</b> each comprising of SF6 gas insulated Single Pole Circuit Breaker (1 Set), Single Phase Current Transformer (6 Nos), Motorised Busbar 3 Phase Disconnecter (2 Nos), Motorised Disconnecter (1 No), Motorised safety Grounding switch (3 Nos), Busbars, Local Control Cubicle, SF6 gas monitoring system for complete bay, Cable termination arrangement (3 Nos), PD sensor [adequate number of UHF sensors in the offered GIS equipment(1 no in each gas compartment) for detection of Partial discharge (of 5 pC and above) as per IEC 60270 through Partial Discharge (PD) monitoring system], different gas compartment, O-ring & gaskets, Nuts, Bolts & Washers for Outdoor use, Absorbent, Limit Switch, SF6 Gas, etc. to complete ICT Feeder Bay Module & its earthing arrangement with earthing strips of adequate size (as per IEEE Std 80-2013 to protect operating staff against any hazardous touch voltages and electro-magnetic interferences) as per the technical specification.		Set	2			
2.2	145kV, 2000A, 40kA for 3 sec (Busbars, CB, Disconnecter, Grounding Switch & CT), SF6 gas insulated <b>Transformer Feeder Bay Module</b> each comprising of SF6 gas insulated Single Pole Circuit Breaker (1 Set), Single Phase Current Transformer (6 Nos), Motorised Busbar 3 Phase Disconnecter (2 Nos), Motorised Disconnecter (1 No), Motorised safety Grounding switch (3 Nos), Busbars, Local Control Cubicle, SF6 gas monitoring system for complete bay, SF6 bus duct termination arrangement (3 Nos), PD sensor [adequate number of UHF sensors in the offered GIS equipment(1 no in each gas compartment) for detection of Partial discharge (of 5 pC and above) as per IEC 60270 through Partial Discharge (PD) monitoring system], different gas compartment, O-ring & gaskets, Nuts, Bolts & Washers for Outdoor use, Absorbent, Limit Switch, SF6 Gas, etc. to complete Transformer Feeder Bay Module & its earthing arrangement with earthing strips of adequate size (as per IEEE Std 80-2013 to protect operating staff against any hazardous touch voltages and electro-magnetic interferences) as per the technical specification.		Set	2			

2.3	145kV, 2000A, 40kA for 3 sec (Busbars, CB, Disconnecter, Grounding switch, CT & PT), SF6 gas insulated <b>Line Feeder Bay Module</b> each comprising of SF6 gas insulated Single Pole Circuit Breaker (1 Set), Single Phase Current Transformer (6 Nos), Single phase Line Potential Transformer with disconnecting link (4 winding) (3 Nos), Motorised 3 Phase Busbar Disconnecter (2 Nos), Motorised safety Grounding switch (2 Nos), Motorised 3 Phase Disconnecter with high speed fault making Motorised Grounding switch (1 No), Busbars, Local Control Cubicle, SF6 gas monitoring system for complete bay, SF6 bus duct termination arrangement (3 Nos), PD sensor [adequate number of UHF sensors in the offered GIS equipment(1 no in each gas compartment) for detection of Partial discharge (of 5 pC and above) as per IEC 60270 through Partial Discharge (PD) monitoring system], different gas compartment, O-ring & gaskets, Nuts, Bolts & Washers for Outdoor use, Absorbent, Limit Switch, SF6 Gas, etc. to complete Line Feeder Bay Module & its earthing arrangement with earthing strips of adequate size (as per IEEE Std 80-2013 to protect operating staff against any hazardous touch voltages and electro-magnetic interferences) as per the technical specification.		Set	2			
2.4	145kV, 2000A, 40kA for 3 sec (Busbars, Disconnecter, Grounding switch & bus PT), 1 Phase Isolated Bus-PT Bay Module comprising of SF6 gas insulated metal enclosed busbars each enclosed in bus enclosures running along the length of the switchgear to interconnect each of circuit breaker bay module. Each busbar set shall be complete with Single phase bus Potential Transformer (4 winding) (3 Nos), Motorised 3 Phase Disconnecter (1 No), Motorised Busbar safety Grounding switch (1 No), Busbars, Local Control Cubicle, SF6 gas monitoring system PD sensor [adequate number of UHF sensors in the offered GIS equipment(1 no in each gas compartment) for detection of Partial discharge (of 5 pC and above) as per IEC 60270 through Partial Discharge (PD) monitoring system], different gas compartment, O-ring & gaskets, Nuts, Bolts & Washers for Outdoor use, Absorbent, Limit Switch, SF6 Gas, etc. to complete the bus & its earthing arrangement with earthing strips of adequate size (as per IEEE Std 80-2013 to protect operating staff against any hazardous touch voltages and electro-magnetic interferences) as per the technical specification.		Set	1			
2.5	145kV, 2000A, 40kA for 3 sec (Busbars, CB, Disconnecter, Grounding switch & CT), SF6 gas insulated <b>Bus Coupler Bay Module</b> comprising of SF6 gas insulated Single Pole Circuit Breaker (1 Set), Single Phase Current Transformer (6 Nos), Motorised 3 Phase Disconnecter (2 Nos), Motorised safety Grounding switch (2 Nos), Busbars, Local Control Cubicle, SF6 gas monitoring system, PD sensor [adequate number of UHF sensors in the offered GIS equipment(1 no in each gas compartment) for detection of Partial discharge (of 5 pC and above) as per IEC 60270 through Partial Discharge (PD) monitoring system], different gas compartment, O-ring & gaskets, Nuts, Bolts & Washers for Outdoor use, Absorbent, Limit Switch, SF6 Gas, etc. to complete Bus Coupler Bay Module & its earthing arrangement with earthing strips of adequate size (as per IEEE Std 80-2013 to protect operating staff against any hazardous touch voltages and electro-magnetic interferences) as per the technical specification.		Set	1			
2.6	145kV, 2000A, 40 kA, 3 sec, single or three phase, SF6 gas Insulated Bus Duct outside GIS Bay along with associated Support structure arrangement bends, joints,accessories, & its earthing arrangement with earthing strips of adequate size (as per IEEE Std 80-2013 to protect operating staff against any hazardous touch voltages and electro-magnetic interferences) as per the technical specification.		RM	170 (3P)			
			RM	510 (1P)			

2.7	145kV, 2000A, 40kA SF6/Air BUSHING (Bushing shall be of Polymer / composite insulator type and shall be seamless sheath of a silicone rubber compound. The hollow silicone composite insulators shall comply as per IEC 61462 and IEC 62217. The design of the composite insulators shall be tested and verified according to IEC 61462) for connecting GIS ro AIS along with support structure.		No	12			
2.8	Portable Partial Discharge Monitoring System (PDM): 245kV and 145kV system shall have Portable Partial Discharge Monitoring System (PDM) & shall be capable for measuring PD in charged GIS environment, bandwidth in order of 100MHz–2GHz & provision to select a wide range of intermediate bandwidths and the principle of operation shall be based on UHF principle of detection. The Detection and measurement of PD and bouncing particles having in built large coloured LCD for displaying and storing facility in the instrument for further analysis to locate actual source of PD such as free conducting particles, floating components, voids in spacers, particle on spacer surfaces etc.		SET	1			
2.9	132 KV XLPE Cable 1000 Sq Mm ( 1000 Amps Single Core ) for 132 KV conectivity from GIS equipment to Auto Transformer & Power Transformer		MTR	1200			
2.10	132 KV Cable termination kit outdoor for 132 KV Transformers suitable for 1CX1000 Sqmm copper cable.		Nos	6			
2.11	132KV Cable termination kits (Outdoor GIS side) suitable for 1CX 1000 sq. mm Copper Cable		Nos	6			
2.12	EHV cable accessories like, link box, SVL, bonding cables, earthing cable for 132 kV system as per tech specification.		LOT	1			
3	<b>2000A, 31.5kA for 3s, Double Busbar Circuit Breaker (Circuit breaker shall be E2-C2-M2 class as per IEC 62271-100) arrangement. 36kV INDOOR GIS EQUIPMENT as per latest IEC standard &amp; type tested equipment as per technical specification, with open future proof &amp; flexible system in line with IEC 61850 &amp; IEC 62271-200.</b>						
3.1	36kV, 2000A, 31.5kA for 3 sec (CB, Disconnecter, Grounding Switch & CT), SF6 gas insulated <b>Transformer Bay Module</b> each comprising of SF6 gas insulated Vacuum Circuit Breaker (1 Set), Single Phase Current Transformer (3 Nos), Motorised Busbar 3 Phase Disconnecter (2 Nos), Motorised Disconnecter (1 No), Motorised safety Grounding switch (3 Nos), Busbars rated 2000A, Local Control Panel, SF6 gas monitoring system for complete bay, etc. to complete Transformer Bay Module suitable cable connection as per the technical specification.		Set	2			
3.2	36kV, 1250A, 31.5kA for 3 sec (CB, Disconnecter, Grounding Switch & CT), SF6 gas insulated <b>Outgoing Feeder Bay Module</b> each comprising of SF6 gas insulated Vacuum Circuit Breaker (1 Set), Single Phase Current Transformer (3 Nos), Motorised Busbar 3 Phase Disconnecter (2 Nos), Motorised Disconnecter (1 No), Motorised safety Grounding switch (3 Nos), Busbars rated 2000A, Local Control Panel, SF6 gas monitoring system for complete bay, etc. to complete Outgoing Feeder Bay Module suitable cable connection as per the technical specification.		Set	5			
3.3	36kV, 1250A, 31.5kA for 3 sec (Disconnecter, Grounding switch & bus PT), 1 Phase Isolated Bus-PT Bay Module comprisig of SF6 gas insulated metal enclosed busbars rated 2000A each enclosed in bus enclosures running along the length of the switchgear to interconnect each of circuit breaker bay module. Each busbar set shall be complete with Single phase bus Potential Transformer (4 winding) (3 Nos), Motorised 3 Phase Disconnecter (1 No) , Motorised Busbar safety Grounding switch (1 No), SF6 gas monitoring system for complete bus system, etc. as per the technical specification.		Set	1			

3.4	36kV, 2000A, 31.5kA for 3 sec (Busbars, CB, Disconnecter, Grounding switch & CT), SF6 gas insulated Bus Coupler Bay Module comprising of SF6 gas insulated Vacuum Circuit Breaker (1 Set), Single Phase Current Transformer (6 Nos), Motorised 3 Phase Disconnecter (2 Nos), Motorised safety Grounding switch (2 Nos), Local Control Panel, SF6 gas monitoring system for complete bay, etc. to complete Bus Coupler Bay Module as per the technical specification.	Set	1			
3.5	<b>33KV EHV POWER CABLES, AL CORRUGATED XLPE CABLES</b>					
3.5.1	33KV CABLE 630 SQ. MM (800 AMPS SINGLE CORE) (for 33 KV connectivity from GI equipment to Power Transformer)	Mtes	1200			
3.5.2	33 KV Cable termination kit indoor for 33 KV Transformers suitable for 1CX630 Sqmm copper cable.	No.s	6			
3.5.3	33 KV Cable termination kit outdoor for 33 KV Transformers suitable for 1CX630 Sqmm copper cable.	No.s	6			
3.5.4	33KV CABLE 300 SQ. MM (400 AMPS SINGLE CORE) (for 33 KV connectivity from GI equipment to Station Transformer & outgoing feeders upto DP structure end)	Mtes	2500			
3.5.4	33 KV Cable termination kit indoor for 33 KV suitable for 1CX300 Sqmm copper cable.	No.s	21			
3.5.5	33 KV Cable termination kit outdoor for 33 KV suitable for 1CX300 Sqmm copper cable.	No.s	21			
4	<b>245 KV,2000A,40KA,ISOLATORS</b>					
4.1	245 KV, 2000A, 40KA, Center break ISOLATORS WITH EARTH SWITCH, supporting structure and terminal connectors as per TS.	SET	4			
5	216 KV, METAL OXIDE SURGE ARRESTOR,10 KA, class III	NOS	18			
6	220 KV Bus Post Insulators	NOS	6			
7	<b>145 KV,1250A,31.5KA,ISOLATORS</b>					
7.1	145 KV, 2000A, 40KA, Center break ISOLATORS WITH EARTH SWITCH, supporting structure and terminal connectors as per TS.	NOS	2			
8	120 KV METAL OXIDE SURGE ARRESTOR, 10 KA, Class III	NOS	18			
9	30 KV SURGE ARRESTERS	NOS	27			
10	33 KV Post Insulators	NOS	15			
10.1	<b>BUS BAR &amp; CIRCUIT MATERIALS</b>					
10.1.1	<b>LONG ROD INSULATORS</b>					
10.1.1.1	120 KN INSULATOR FOR 220KV (2 nos. in one set)	SET	12			
10.1.1.2	90 KN INSULATOR	NOS	7			
11	<b>ACSR MOOSE CONDUCTOR</b>	KMS	1.0			
11.1	<b>HARDWARES &amp; FITTINGS/SPACERS/CLAMP &amp; CONNECTORS</b>					
11.2	220 KV Single Suspension(120 KN)H/W fitting for Single Moose ACSR	NOS	12			
11.3	132 KV Single Suspension(90KN) H/W fitting for single Moose ACSR	NOS	6			
11.4	T- clamp for ACSR ZEBRA run to ACSR MOOSE drop	NOS	24			
11.5	T- clamp for ACSR PANTHER run to ACSR MOOSE drop	NOS	12			
11.6	220 KV PI clamp	NOS	6			
11.7	Spacer for Moose ACSR	NOS	10			
11.8	220 KV LA Clamp	NOS	18			
12	<b>132 KV LA Clamp</b>	NOS	18			
12.1	PG Clamp for ACSR Moose	NOS	30			
12.2	33KV LA Clamp	<b>NOS</b>	27			
12.4	<b>EARTH WIRES &amp; IT'S HARDWARES &amp; FITTING</b>					

12.5	Earthing Spikes of 9 mtr long each and Its Fittings in all respect. (220 kv side)		NOS	5			
12.6	Earthing Spikes of 7 mtr long each and Its Fittings in all respect. (132 kv side)		NOS	3			
<b>13</b>	<b>SUBSTATION EARTHING SYSTEMS</b>						
13.1	EARTHING CONDUCTOR FOR BURRIAL : 75X10 mm GI Flat for laying ( <i>spacing maximum 5m both way</i> ) = 8 km APPX		MT	47.192			
13.2	EARTHING CONDUCTOR: 50X6 mm <b>GI Flat</b> for Raiser from the burial earth mat to equipment,structure etc)		MT	3.920			
<b>14</b>	<b>EARTHING DEVICE &amp; ASSOCIATED ACCESSORIES (50 mm heavy duty GI PERFORATED PIPE 3 mtrs long for treated earth pit)</b>		Nos.	50			
14.1	EARTHING DEVICE & ASSOCIATED ACCESSORIES 40mm MS rod 3 mtrs long for non treated earth pit)		Nos.	50			
14.2	G.I Cable Trays including support GI angle suitable for different sections i.e. Section:1-1,2-2,3-3 & 4-4 along with its accessories as per TS.						
14.3	G.I Cable Trays(size: 450x75x2500mm)		MTRS	1000			
14.4	G.I Cable Trays(size: 300x75x2500mm)		MTRS	1000			
<b>15</b>	<b>G.I Cable Trays(size: 150x75x2500mm)</b>		MTRS	1000			
15.1	Support G. I angle 50x50x6 mm for cable tray		MT	4			
15.2	SUB STATION SWITCHYARD BMK,AC CONSOLE & OTHER MARSHALLING BOXES						
15.3	BAY MARSHALLING KIOSK ( <i>02 Nos. in 220 KV Side,01 Nos. in 132 KV Bay Side, 01 Nos. in 33KV Side</i> )		NOS	4			
15.4	SWITCH YARD AC CONSOLE FOR LIGHTING ( <i>01 Nos. in 220 KV bay, 01 No. in 132 kv Bay</i> )		NOS	2			
<b>16</b>	<b>SWITCH YARD RECEPTACLE BOARD FOR TFR OIL FILTERATION (<i>01 No. near each 220/132 Auto Transformers, and 01 no. near power transformer</i> )</b>		NOS	3			
16.1	SWITCH YARD RECEPTACLE BOARD FOR WELDING & OTHER EMERGENCY ( <i>01 No.</i> )		NOS	1			
<b>17</b>	<b>SWITCH YARD STRUCTURES (LATTICE TYPE FOR COLUMN &amp; BEAMS) FOR 220KV, 132KV &amp; 33 KV CLASS INCLUDING FOUNDATION BOLTS &amp; NUTS.</b>						
17.1	<b>DIFFERENT TYPES OF COLUMNS WITH DETAILS</b>						
17.1.1	P1S-220 KV (NOMINAL UNIT WT- 4.5 MT)- <b>5 NOS</b> )		MT	22.500			
17.1.2	T1S 132KV (NOMINAL UNIT WT-1.2MT (3 NOS.)		MT	3.600			
<b>17.2</b>	<b>DIFFERENT TYPE OF BEAMS WITH DETAILS</b>						
17.2.1	Q1-220KV (NOMINAL UNIT WT- 1.5 MT) (4 NOS.)		MT	6.000			
17.2.2	G1 - 132KV (NOMINAL UNIT WT-0.62MT) ( NOS)		MT	1.240			
17.3	<b>TOTAL WEIGHT OF COLUMN &amp; BEAMS</b>		<b>MT</b>	<b>33.340</b>			
<b>17.4</b>	<b>EQUIPMENT SUPPORT STRUCTURES (LATTICE TYPE) FOR ALL 220KV &amp; 132 KV EQUIPMENTS INCLUDING FOUNDATION BOLTS &amp; NUTS</b>						
17.4.1	Surge Arrester-220 KV( 18 Nos.)		MT	5.258			
17.4.2	Surge Arrester-132 KV( 18 Nos.)		MT	3.288			
17.4.3	BPI-220 KV (6Nos.)		MT	1.757			
17.4.4	Cable Termination Port -33 KV (06 Nos)		MT	2.100			
<b>17.6</b>	<b>TOTAL WEIGHT OF EQUIPMENT STRUCTURES</b>		<b>MT</b>	<b>12.403</b>			
<b>18</b>	<b>Total weight of GI Nuts and Bolts for Columns, Beams &amp; Equipment Structures (taking 5% of the weight of Structures of 458.572MT)</b>		<b>MT</b>	<b>2.287</b>			
<b>18.1</b>	<b>GENERAL EQUIPMENT &amp; SUBSTATION ACCESSORIES</b>						

18.1.1	<b>POWER CABLES,1.1KV,XLPE &amp; PVC ARMoured, ALUMINIUM CONDUCTOR (As per Specification)</b>					
18.1.2	XLPE 3.5 CX300 mm <sup>2</sup>		MTR	1000		
18.1.3	XLPE 3.5 CX185 mm <sup>2</sup>		MTR	1000		
18.1.4	XLPE 3.5 CX120 mm <sup>2</sup>		MTR	1000		
18.1.5	PVC 3.5 CX70 mm <sup>2</sup>		MTR	1200		
18.1.6	PVC 3.5 CX35 mm <sup>2</sup>		MTR	3200		
18.1.7	PVC 4 CX 16 mm <sup>2</sup>		MTR	2200		
18.1.8	PVC 4CX 6 mm <sup>2</sup>		MTR	5000		
18.1.9	PVC 2CX 6 mm <sup>2</sup>		MTR	5000		
18.2	<b>CONTROL CABLES,1.1 KV, PVC,STRANDED COPPER(As per specification)</b>					
18.2.1	2 CX 2.5 mm <sup>2</sup>		MTR	8000		
18.2.2	4 CX 2.5 mm <sup>2</sup>		MTR	15000		
18.2.3	5 CX 2.5 mm <sup>2</sup>		MTR	7500		
18.2.4	7CX 2.5 mm <sup>2</sup>		MTR	8500		
18.2.5	10 CX 2.5 mm <sup>2</sup>		MTR	15000		
18.2.6	12 CX 2.5 mm <sup>2</sup>		MTR	14500		
18.2.7	16 CX 2.5 mm <sup>2</sup>		MTR	7000		
18.2.8	19 CX 2.5 mm <sup>2</sup>		MTR	3000		
18.2.9	1CX 120 mm <sup>2</sup> BAT TO BAT CHARGER & CHARGER TO DCDB		MTR	1200		
19	<b>ACCESSORIES FOR PLCC SYSTEM With OPGW cable</b>					
19.1	48 Fibre Optic Approach cable along with HDPE Pipes		KM	0.50		
19.2	Optical line Terminal Equipment(OLTE) -STM4 type SDH equipment with integrated MUX & tributary cards for speech & data ports for interfacing of Speech & data which should be compatible with existing OPTCL system		No	1		
19.3	Digital Teleprotection Equipment and accessories to be suitable for interfacing with SDHMUX		No	1		
19.4	Supply of FODP(Fibre Optic Distribution Panel)48 F: Indoor type,rack mounted with FCPC coupling and pig tails(DWSm Fibre)		No	1		
19.5	48 V, 300 AH, maintenance free VRLA Battery set.		Set	1		
19.6	SMPS based Battery Charger of 75A suitable for 48V VRLA Battery set		No	1		
19.7	2.5 sq. mm muti strand 2 core control cable(power supply,Transducer/MFT PT supply)		Metre	300		
19.8	2.5 sq. mm multi strand 4 core control cable(Transducer/MFT CT supply)		Metre	300		
19.9	1.5 sq. mm multi strand 10 core control cable(Digital Input)		Metre	200		
19.10	10 sq. mm 2 core multi strand control cable(Battery)		Metre	100		
19.11	48V DCDB,		Set	1		
19.12	Earth Flat, Cable Tray, Telephone cable,Foundation rail, Junction Box,.		Set	1		
20	<b>SUPPLY OF POWER TRANSFORMER,STATION TRANSFORMER &amp; OTHER MATERIALS FOR MEETING THE AUXILIARY SUPPLY OF THE SUB-STATION AS PER TECHNICAL SPECIFICATION</b>					
20.1	<b>AUTO TRANSFORMER: 220/132KV,160 MVA (inclusive of all costs towards type test charges, Mandatory spares, Spanners &amp; Special tools, accessories, etc as specified in the Technical specification)</b>		NOS	2		



20.2	<b>POWER TRANSFORMER : 132/33 KV, 40 MVA (inclusive of all costs towards type test charges, Mandatory spares, Spanners &amp; Special tools, accessories, etc as specified in the Technical specification)</b>		NOS	2			
20.3	STATION TRANSFORMER 33KV/0.43 V,500 KVA (Confirming to Energy Efficiency Level 2 -AS PER SPECIFICATION & relevant IS)		NOS	2			
20.4	<p><b>One no. 4 pole structure (HDG Type) alongwith other equipment &amp; materials for two nos station transformers:</b></p> <p>1.4 Pole structure (using 200X100 mm RS Joist)</p> <p>2. Channel &amp; Angle FOR BRACING OF, CHANNEL for the SA &amp; Isolator &amp; HG fuse etc.</p> <p>3. 90 KN Disc/composite long rod Insulators for 33 KV (48 nos./12 sets) for bus, Bus stringing using ACSR moose conductor &amp; tension hardwares,other clamps &amp; connectors etc as per requirement.</p> <p>4. 2sets of 33 KV Isolator (800 AMP) for 33 KV side of station trafo.</p> <p>5. 2sets of 33 KV HG FUSE.</p> <p>6. 100 Sq mm AAAC conductor suitable for connection between HG fuse &amp; station transformer bushing.</p> <p>7. 2 sets of LT OUT DOOR KIOSK MADE OUT OF 3mm CRCA sheet GI MARSHALLING BOX suitable for outdoor mounting. The bus bar suitable for 1000 AMP shall be arranged in the out door kiosk and other Facility like two sets of 400 Amps MCCB for incoming &amp; outgoing with required sizes of terminal studs for power cable termination &amp; any other accessories required.</p> <p>All materials shall be As per relevant latest IS &amp; as per the direction of Engg. in charge</p>		SETS	2			
21	<b>SUBSTATION LIGHTING (AS PER SPECIFICATION AND APPROVED DRAWINGS) (Switch yard and other street area)</b>						
21.1	<b>SUB-STATION SWITCH YARD LIGHTING</b> : IT INCLUDES SUPPLY OF FIXTURES & LAMPS (LED) of reputed make (Philips/CGL/Bajaj/other approved make of OPTCL) with switch gear,GI Conduit etc.(Lighting fixtures are to be fixed rigidly on the Column at a suitable height so that the required lux can be achieved).(150 watt each). (* REMARKS : FOR SUPPLY OF ALL THE CABLES AS INDICATED ARE COVERED IN THE CABLE ITEMS AS INDICATED ABOVE )		SET	60			
21.2	<b>STREET LIGHTING:</b> GI Tubular Pole: (410-SP-24: IS 2713-Part-II-1980 or latest) Length of pole 8.5 mtrs(minimum weight 158 Kgs). & LED light fittings etc. (ALL THE STREET LIGHT POLE SHALL BE OF GI TUBULAR POLE AND PROVISION OF A GI JUNCTION BOX WITH SUITABLE COVERS AT A HEIGHT OF 1 METRE FROM THE GROUND. THE JUNCTION BOX SHALL HAVE PROVISION OF FUSES, BUSES, CONNECTORS FOR CABLE IN AND OUT. ( IT INCLUDES SUPPLY OF LED LIGHTING FIXTURES WITH LAMPS of 100 Watts of reputed make (Philips/CGL/Bajaj/other approved make of OPTCL) & as per technical specification. (* REMARKS : FOR SUPPLY OF ALL THE CABLES AS INDICATED ARE COVERED IN THE CABLE ITEMS AS INDICATED ABOVE )		SET	25			

21.3	<b>OUTDOOR KIOSK (HDG type) FOR STREET LIGHTING PURPOSE</b> HAVING 2 NOS 200 AMP SWITCH FUSE UNITS AND , 6 NOS.OUT LETS OF 32 AMP MCB FOR STREET LIGHTING. (SUITABLE FOR XLPE CABLES(3.5 CORE 120 SQMM) FROM MAIN ACDB FROM CONTROL ROOM TO THE OUT DOOR KIOSK. XLPE CABLE OF 4C X 16 SQMM FROM OUTDOOR KIOSK TO THE STREET LIGHT POLES AND 4CX6 SQMM FROM POLE TO POLE AND 2CX6 SQMM FROM POLE TO LIGHTING FIXTURES. > 1 NO. OUTDOOR KIOSK FOR COLONY SUPPLY PURPOSE HAVING (* REMARKS : FOR SUPPLY OF ALL THE CABLES AS INDICATED ARE COVERED IN THE CABLE ITEMS AS INDICATED ABOVE )		SET	2			
21.4	40 Mtrs heigh Monopole (HDG) Lighting cum Lightning Mast including LED lighting fixtures ( <b>240 watts each minimum 8 Nos.</b> ) with control gear panel etc suitable for wind zone-VI, with all other accessories like motor for hoisting/lowering the lighting platform & other switchgear and lighting control panel including required cable(copper) & other accessories etc.		SET	2			
22	<b>INDOOR LIGHTING (AS PER SPECIFICATION AND APPROVED DRAWINGS ) ( Control room building,Store shed,store room,Security room cum Visitors room and other area)</b>						
22.1	CONTROL ROOM BUILDING INDOOR LIGHTING, IT INCLUDES SUPPLY OF FIXTURES & LAMPS (LED) of reputed make (Philips/CGL/Bajaj/ other approved make of OPTCL) with switch gear,Conduit & other required materials for succesful illumination of the area/rooms.( No. of LED Lighting fixtures are to be calculated based on the illumination design considering the required lux level indicated in the technical spec & fixing of the same rigidly on the suitable height either ceiling & wall as required.)		LOT	1			
22.2	INDOOR LIGHTING OF SECURITY SHED CUM VISITORS ROOM,PUMP HOUSE,STORE SHED,STORE ROOM, FFPH BUILDING: IT INCLUDES SUPPLY OF FIXTURES & LAMPS (LED) of reputed make (Philips/CGL/Bajaj/ other approved make of OPTCL) with switch gear,Conduit & other required materials for succesful illumination of the area/rooms.( No. of LED Lighting fixtures are to be calculated based on the illumination design considering the required lux level indicated in the technical spec & fixing of the same rigidly on the suitable height either ceiling & wall as required.)		LOT	1			
22.3	2 TR CAPACITY SPLIT AIR CONDITIONING UNITS (Dual Inverter, five star type latest model) with copper condensor having remote temperature & operation control facility with required voltage stabiliser. Receptical indoor Control Board having suitable outgoing (one outgoing for one AC & with overload control gear) & wiring materials with 32 amp socket & plug for each unit of AC etc to complete (AS PER SPECIFICATION) FOR CONTROL ROOM, CARRIER ROOM & CONFERENCE ROOM.,OFFICE ROOM etc which includes all type of cables & wires and a main control switch gear kiosk having sufficient outlet for each air conditioner unit.		Nos.	20			

23	<p><b>Supply of Smoke &amp; Heat detection system:</b> Addressable optical Smoke &amp; Heat Multi detector (adequate Nos) for <b>control room building</b> including all accessories, the Main control panel (Microprocessor based 2 loop fire alarm control panel expandable upto 18 loops fully networkable with each loop capable of taking 99 devices, 8 line x 40 character alpha- numeric liquid crystal display .The panel shall be soft addressable type . The panel shall be able to give pin point location of all fire/fault conditions. Further, the panel must be able to automatically switch off respective control switches when ever any alarm is triggered. The panel shall have in built rectifier, Loop cards,provision for external &amp; internal printer(if required), L C D unit to indicate Fire/Fault Signal with address and analog output, built in printer to log all fire or fault events complete in all respects, integral SMF lead acid batteries with sealed cells of 24 V capable of running for a minimum of 8 hours with integral battery charger complete as required and as per specification. The fire alarm panel shall be suitable for software integration with BMS &amp; PA system ,wall mounting loop powered addressable type hooter with all accessories , addressable manual call box made of polycarbonate with plastic break glass front and complete with monitor module MCB, addressable isolator module with required PVC box, fittings and fixtures, wiring with PVC FRLS wire to cover the required for fire &amp; smoke detection etc. (One control room building is to be provided with Heat &amp; smoke detection). Should have facility for integration with SAS.</p>		SET	1			
24	<p><b>FIRE FIGHTING SYSTEM(PORTABLE AND WHEEL MOUNTED SETS FOR CONTROL ROOM,EQUIPMENT LIKE TRANSFORMER AND OTHER AREAS AS PER TECH SPEC(REFER TS-INST TO BIDDER BEFORE DESIGN-SL NO 16-ANNEXURE - I)</b></p>						
24.1	FOAM TYPE-9 LTRS		NOS	5			
24.2	DRY CHEMICAL POWDER(TROLLEY MOUNTED)- 22.5 KGS		NOS	6			
24.3	DRY POWDER TYPE - 5 KGS		NOS	6			
24.4	CO <sub>2</sub> - 4.5 KGS		NOS	6			
24.5	CO <sub>2</sub> - 9 KGS		NOS	6			
24.6	CO <sub>2</sub> (TROLLY MOUNTED)- 22.5 KGS		NOS	4			
24.7	9 litre Water type		Nos.	4			
24.8	50 Litres Mechanical Foam type		Nos.	2			
24.9	FIRE BUCKET (6 NOS IN EACH STAND) WITH STAND		SET	5			

25	<p><b>SUBSTATION AUTOMATION SYSTEM FOR 220/132/33 KV SUBSTATION ON PRP MODE:</b> Design , engineering , drawing, supervision, installation , testing &amp; commissioning of Substation Automation system alongwith Supply of the following 220, 132 and 33 kV level of protection panels consisting of Bay control Units &amp; numerical protection relays and other auxiliary relays suitable for SAS as per technical specification.</p> <p><b>(220KV side:</b> COMPRISING OF 04 Nos. FEEDER BAYS + 02 TRANSFORMER BAYS + 01 Nos BUS COUPLER BAY, <b>132 KV side:</b> COMPRISING OF 02 Nos. FEEDER SAYS + 04 Nos TRANSFORMER BAYS(auto &amp; power trf.) + 01 No. BUS COUPLER BAY) &amp; <b>33 KV side:</b> COMPRISING OF 02 Nos. FEEDER SAYS + 05 Nos TRANSFORMER BAYS + 01 No. BUS COUPLER BAY)</p> <p><b>NOTE:</b> All protective relays &amp; BCU shall be numerical type.</p>					
25.1	Yard AC Kiosk :6000 mm (L)x5000mm (W)x 4500mm (H) with AC, <b>as per the Specification;</b>		Nos.	3		
25.2	Gate way panel for Sub-Station Automation (in PRP as per the specification & indicative drg ) system (for All 220, 132 & 33 KV side bays including the future bays),other accessories (comprising servers, engg. Station, works station (Main & standby), Remote station control, Colour Laser jet Printers & dot matrix printer for local station as per requirement and also for remote station, Ethernet Switches , LIU, Red Box, Multimode glass fibre Double jacket armoured optical cables, special cables like F.O patch cord & armoured FO cables of adequate length etc required for the system in all respect as per latest IEC 61850 standard, Inverters of required capacity & rating (3KVA-Input shall be both A.C & D.C and output shall be A.C) etc as per TS. A Full HD LED screen of 70 inches for display,SAS furnitures of Godrej make & including all type of accessories & as per technical specification.		SET	1		
25.3	<b>BCU for Substation Auxilliary</b> System (Datas for monitoring of Station AC, Station DC, Lighting, Fire fighting, Air conditioning, Diesel generator etc. as per the site requirement)		SET	1		
25.4	GPS System with PTP, IRIG-B, SNTP		SET	1		
25.5	<b>220 KV SIDE PROTECTION &amp; OTHER PANELS</b>					
25.5.1	<b>FEEDER PROTECTION PANEL</b> (MAIN-I , MAIN-II & BACK-UP PROTECTION WITH AUTO RECLOSURE DISTANCE PROTECTION with Bay control unit (BCU) with all other relays & component required for complete prtction,control etc as per TS and also suitable for substation automation system.		NOS	4		
25.5.2	<b>TRANSFORMER PROTECTION PANEL</b> (DIFFERENTIAL I , REF I & BACK-UP PROTECTION & BCU for 220 KV side) & (Bay control unit-BCU andBACK-UP PROTECTION for 132 KV side) CONSIDERING HV & LV side of 220/132 KV, 160 MVA Auto transformer with all other relays & component required for complete prtction,control etc as per TS and also suitable for substation automation system.		NOS	2		

25.5.3	<b>BUS COUPLER PROTECTION PANEL</b> with Bay control unit (BCU) & Back-up protection relay with with all other relays & component required for complete protection, control etc as per TS and also suitable for substation automation system.		NOS	1			
25.5.4	<b>BUS-BAR PROTECTION PANEL</b> ( Provision of bus bar modules for the future bays(two nos) and with all other relays & component required for complete protection etc as per TS and also suitable for substation automation system.		SET	1			
<b>25.6</b>	<b>132 KV SIDE PROTECTION PANELS</b>						
25.6.1	FEEDER PROTECTION PANEL (MAIN-I & BACK-UP PROTECTION DISTANCE PROTECTION with Bay control unit (BCU) for substation automation system.		NOS	2			
25.6.2	TRANSFORMER PROTECTION PANEL (DIFFERENTIAL, REF & BACK-UP ,PROTECTION CONSIDERING HV side for 40 MVA 132/33 KV Power Transformer) with Bay control unit (BCU) for substation automation system.		NOS	2			
25.6.3	BUS COUPLER PROTECTION PANEL with Bay control unit (BCU) for substation automation system.		NOS	1			
<b>25.7</b>	<b>33 KV SIDE PROTECTION PANEL</b>						
25.7.1	FEEDER PROTECTION PANEL with Bay control & protection unit (BCPU) along with additional BACK-UP PROTECTION for substation automation system for 33KV feeders [ 2nos. Feeder bays in one panel].		SET	3			
25.7.2	TRANSFORMER PROTECTION PANEL (REF & BACK-UP ,PROTECTION CONSIDERING LV side for 2x40 MVA 132/33 KV Power Transformer) with Bay control & protection unit (BCPU) for substation automation system. [ 2nos. Transformer bays in one panel].		SET	1			
25.7.3	STATION TRANSFORMER PROTECTION PANEL(2X 33/0.43 KV, 250 KVA) with Bay control & protection unit (BCPU) for substation automation system.		NOS	1			
25.7.4	BUS COUPLER PROTECTION PANEL with Bay control & protection unit (BCPU) for substation automation system.		NOS	1			
<b>26</b>	<b>AC &amp; DC SYSTEM</b>						
<b>26.1</b>	<b>AC SYSTEM</b>						
26.1.1	MAIN ACDB,(HAVING 800A, 50KA, DRAWOUT TYPE ACB WITH 3 O/C,E/F,U/V RELAYING FACILITY INDOOR TYPE AS PER SPECIFICATION.(MAIN DB-1,MAIN DB-2 WITH B/C)		SET	1			
26.1.2	ACDB (HAVING 400A MCCB) AS PER SPECIFICATION (ACDB-1, ACDB-2 WITH B/C)		SET	1			
26.1.3	MAIN LIGHTING DISTRIBUTION BOARD (HAVING 250A MCCB AS INCOMER)AS PER SPECIFICATION (WITH DB-1,DB-2 & B/C)		SET	1			
26.1.4	INDOOR LIGHTING DISTRIBUTION BOARD AS PER SPECIFICATION. (WITH DB-1,DB-2 & B/C)		SET	1			
26.1.5	EMERGENCY LIGHTING DISTRIBUTION BOARD		SET	1			
26.1.6	INDOOR RECEPTACLE BOARD		SET	1			
<b>26.2</b>	<b>DC SYSTEM</b>						

26.2.1	220 V DC BOARD (HAVING 100A DC MCCB AS INCOMER, E/F (EARTH LEAKAGE), UNDER & OVER VOLTAGE AS PER SPECIFICATION (DC DB-1,DC DB-2 & B/C)	SET	2			
26.2.2	220 V DC EMERGENCY DISTRIBUTION BOARD	SET	1			
26.2.3	BATTERY (350 AH PLANTE TYPE) FOR 220 V DC	SET	2			
26.2.4	BATTERY CHARGER FOR 350 AH, 220 V DC (FLOAT & FLOAT CUM BOOST) (including provision of series dropper diodes with heat sinks & other protection facility at the DC Load terminal end in order to feed 220 V to the load).	SET	2			
27	DISTILLED WATER PLANT OF 10 LTR/HR FOR BATTERY BANKS	SET	1			
28	WALKIE TALKIE SET	SET /PAIR	4			
29	PORTABLE ALUMINIUM LADDER EXTENDABLE TYPE OF ADEQUATE HEIGHT TO BE USED FOR MAINTENANCE OF EQUIPMENT INSIDE SWITCH YARD.	NOS	2			
30	PEDESTAL MOUNTED WHEEL FITTED DERRICK FOR LIFTING/ LOWERING OF MATERIALS UP TO 1.5 TON CAPACITY.	SET	1			
31	WATER COOLER WITH WATER PURIFIER SYSTEM	NOS	2			
32	MAINTENANCE TESTING EQUIPMENT (AS PER ANNEXURE - I ,INDICATED IN TS-TIMK-SCHEDULE OF REQUIREMENTS OF MAINTENANCE EQUIPMENT)	LOT	1			
33	OTHER TOOLS AND PLANTS (T&P's) REQUIREMENT (AS PER ANNEXURE - II ,INDICATED IN TS-TIMK-SCHEDULE OF REQUIREMENTS OTHER T&P's)	LOT	1			
34	OFFICE FURNITURE (AS PER ANNEXURE - III ,INDICATED IN TS-TIMK-SCHEDULE OF REQUIREMENTS OFFICE FURNITURE)>PLACING IN CONTROL ROOM,CONFERENCE ROOM,OFFICE ROOMS,LIBRARY,TESTING LAB,etc.	LOT	1			
35	BEST QUALITY & APPROVED MAKE INSULATION MAT TO BE KEPT INFRONT OF ALL PANELS,BOARDS ETC.	NOS	50			
36	250 KVA,415 VOLTS,3 PHASE SIELENT DIESEL GENERATOR FOR EMERGENCY SITUATION	NOS	1			
37	FIRE FIGHTING EQIPMENT: (Main Pump, Jockey Pump, DG Set cum Pump, Control Panel for Fire Fighting System (HIGH PRESSURE : Hydrant and Mulsifire system) to take care of 2 Nos 160 MVA ICT, Power Transformer, switcyard equipment and buildings. HVW system & hydrant sytem, complete with all piping, valves, fittings etc inside pump house for Fire protection sytem of substation) as per the technical spec.	LOT	1			
38	Hydrant sytem, complete U/G piping of different sizes,vaves and accessories etc outside the Pump House for Fire protection sytem of 2 Nos 160 MVA Aoto transformers, Power transformers, switcyard equipment and buildings as per the technical spec.	LOT	1			
39	<b>EQUIPMENT and MATERIALS for GIS</b>					
39.1	<b>ACCESSORIES</b>					
39.1.1	SF6 Gas handling plant of adequate capacity as per the Technical specification	Set	1			
39.1.2	SF6 gas service cart with all accessories as per the Technical specification	Set	1			
39.2	<b>TESTING EQUIPMENT</b>					
39.2.1	GIS testing equipment as per the Technical specification. (ANY SPECIAL TOOLS & TACKLES REQUIRED (except mentioned under item No. 39.3 below) FOR COMPLETE INSTALLATION OF THE 220KV & 132 KV GAS INSULATED SWITCHGEAR (To be supplied on Non Returnable basis and shall not be taken back by the bidder)	Set	1			
39.3	<b>ESSENTIAL TOOLS and SPARES for GIS (SPARES for 245kV GIS)</b>					
39.3.1	Single phase voltage transformer	Set	1			
39.3.2	Single phase set of 5 cores current transformer including enclosure	Set	1			

39.3.3	Enclosure insulators and main circuit of busbar		Set	1			
39.3.4	Tripping and closing coils		Set	3			
39.3.5	SF6 Pressure gauges		Set	2			
39.3.6	SF6 Pressure relief devices		Set	2			
39.3.7	Auxiliary contacts for circuit breaker		Set	1			
39.3.8	Auxiliary contacts for DS and ES		Set	1			
39.3.9	SF6 gas in steel bottle 52kg / bottle		Nos	2			
39.3.10	Spring charge motor for circuit breakers		Unit	1			
39.3.11	Complete drive mechanism for disconnect switches and grounding switches		Unit	1			
39.3.12	Motor for disconnect switches and grounding switches		Unit	1			
39.3.13	Complete drive mechanism for fast acting grounding switches		Unit	1			
39.3.14	Motor for fast acting grounding switches		Unit	1			
39.3.15	Rupture disc for circuit breakers / potential transformer		Nos	1			
39.3.16	Set of spares for local control cabinet including M.C.B., fuses, time relays, auxiliary relays and terminals		Set	1			
39.3.17	Rupture disc for other components		Nos	2			
39.4	<b>SPARES for 145kV GIS</b>						
39.4.1	Single phase voltage transformer		Set	1			
39.4.2	Single phase set of 4 cores current transformer including enclosure		Set	1			
39.4.3	Enclosure insulators and main circuit of busbar		Set	1			
39.4.4	Tripping and closing coils		Set	3			
39.4.5	SF6 Pressure gauges		Set	2			
39.4.6	SF6 Pressure relief devices		Set	2			
39.4.7	Auxiliary contacts for circuit breaker		Set	1			
39.4.8	Auxiliary contacts for DS and ES		Set	1			
39.4.9	Spring charge motor for circuit breakers		Unit	1			
39.4.10	Complete drive mechanism for disconnect switches and grounding switches		Unit	1			
39.4.11	Motor for disconnect switches and grounding switches		Unit	1			
39.4.12	Complete drive mechanism for fast acting grounding switches		Unit	1			
39.4.13	Motor for fast acting grounding switches		Unit	1			
39.4.14	Rupture disc for circuit breakers / potential transformer		Nos	1			
39.4.15	Set of spares for local control cabinet including M.C.B., fuses, time relays, auxiliary relays and terminals		Set	1			
39.4.16	Rupture disc for other components		Nos	2			
39.5	<b>SPECIAL TOOLS</b>						
39.5.1	SF6 gas leak detector as per the Technical specification		Set	1			
39.5.2	SF6 gas analyzer as per the Technical specification		Set	1			
39.5.3	Milli volt drop measurement appilicance		Set	1			
39.5.4	One set of Box Spanner		Set	1			
39.5.5	One set of adjustable Spanner		Set	1			
39.5.6	SF6 gas bottle locking, measuring and filling assembly with all hose		Set	2			
39.5.7	One set of pipe grooving tools for the hydraulic operating mechanism		Set	1			
39.5.8	Infrared camera as per the Technical specification		Set	1			
	<b>TOTAL OF SUBSTATION-SCHEDULE-1 -Plant (to Schedule No. 6 Grand Summary)</b>						

	Name of Bidder: _____  Signature of Bidder: _____
--	---

<sup>1</sup> Bidders shall enter a code representing the country of origin of all imported plant and equipment.

<sup>2</sup> Specify currency in accordance with specifications in Bid Data Sheet under ITB 19.1 in Single-Stage Bid, or ITB 34.1 in Two-Stage Bid. Create and use as many columns for

Item	Description	Code	Country			



ODISHA POWER TRANSMISSION CORPORATION LIMITED					
NAME OF THE WORK:-Design, Supply and Installation of 2X160MVA Auto Transformer & 2X40 MVA Power Transformer,for 220/132/33 KV Out Door Type GIS Grid Sub-station at ,Kuakhia in Odisha State of India under PACKAGE-3A Under Japan International Cooperation Agency (JICA)'s ODA Loan.					
Loan Agreement No: [ID-P245] - FB No: [CPC/JICA/ICB/03A/19-20]- Reference Identification No: [OPTCL/JICA/PKG-3A]					
Schedule No. 2. Plant Supplied from Within the Employer's Country (Sub-station )					
NAME OF THE BIDDER					
Sl. No.	DESCRIPTION OF ITEMS(SCHEDULE-2A-SS) SUPPLY OF FOLLOWING EQUIPMENT & MATERIALS (As per Technical Specification)	Unit	NAME OF THE WORK: Construction of 2*160MVA, & 2*40 MVA, 220/132 KV Open GIS & 33KV INDOOR GIS WITH SAS at KUAKHIA, JAJPUR District.	Unit Price <sup>1</sup>	Total Price <sup>1</sup>
Sl. No.	DESCRIPTION OF ITEMS(SCHEDULE-2A-SS) SUPPLY OF FOLLOWING EQUIPMENT & MATERIALS (As per Technical Specification)				
1	2	3	4	(2)	(1) x (2)
1	2000A, 50kA for 3s, Double Busbar Circuit Breaker (Circuit breaker shall be E2-C2-M2 class as per IEC 62271-100) arrangement. 245kV OUTDOOR GIS EQUIPMENT as per latest IEC standard & type tested equipment as per technical specification, with open future proof & flexible system in line with IEC 61850 & IEC 62271-203.				
1.1	245kV, 2000A, 50kA for 3 sec (Busbar, CB, Disconnecter, Grounding Switch & CT), SF6 gas insulated ICT Feeder Bay Module each comprising of SF6 gas insulated Single Pole Circuit Breaker (1 Set), Single Phase Current Transformer (6 Nos), Motorised Busbar 3 Phase Disconnecter (2 Nos), Motorised Disconnecter (1 No), Motorised safety Grounding switch (3 Nos), Local Control Cubicle, SF6 gas monitoring system for complete bay, SF6 bus duct termination arrangement (3 Nos), PD sensor [adequate number of UHF sensors in the offered GIS equipment(1 no in each gas compartment) for detection of Partial discharge (of 5 pC and above) as per IEC 60270 through Partial Discharge (PD) monitoring system], different gas compartment, O-ring & gaskets, Nuts, Bolts & Washers for Outdoor use, Absorbent, Limit Switch, SF6 Gas, etc. to complete <b>ICT Feeder Bay Module</b> & its earthing arrangement with earthing strips of adequate size (as per IEEE Std 80-2013 to protect operating staff against any hazardous touch voltages and electromagnetic interferences) as per the technical specification.	Set	2		

1.2	<p>245kV, 2000A, 50kA for 3 sec (Busbar, CB, Disconnecter, Grounding switch, CT &amp; PT), SF6 gas insulated Line Feeder Bay Module each comprising of SF6 gas insulated Single Pole Circuit Breaker (1 Set), Single Phase Current Transformer (6 Nos), Single phase Line Potential Transformer with disconnecting link (4 winding) (3 Nos), Motorised 3 Phase Busbar Disconnecter (2 Nos), Motorised safety Grounding switch (2 Nos), Motorised 3 Phase Disconnecter with high speed fault making Motorised Grounding switch (1 No), Local Control Cubicle, SF6 gas monitoring system for complete bay, SF6 bus duct termination arrangement (3 Nos), PD sensor [adequate number of UHF sensors in the offered GIS equipment(1 no in each gas compartment) for detection of Partial discharge (of 5 pC and above) as per IEC 60270 through Partial Discharge (PD) monitoring system], different gas compartment, O-ring &amp; gaskets, Nuts, Bolts &amp; Washers for Outdoor use, Absorbent, Limit Switch, SF6 Gas, etc. to complete <b>Line Feeder Bay Module</b> &amp; its earthing arrangement with earthing strips of adequate size (as per IEEE Std 80-2013 to protect operating staff against any hazardous touch voltages and electro-magnetic interferences) as per the technical specification.</p>	Set	4		
1.3	<p>245kV, 2000A, 50kA for 3 sec (Busbars, Disconnecter, Grounding switch &amp; bus PT), 1 Phase Isolated Bus-PT Bay Module comprising of SF6 gas insulated metal enclosed busbars each enclosed in bus enclosures running along the length of the switchgear to interconnect each of circuit breaker bay module. Each busbar set shall be complete with Single phase bus Potential Transformer (4 winding) (3 Nos), Motorised 3 Phase Disconnecter (1 No) , Motorised Busbar safety Grounding switch (1 No), Local Control Cubicle, SF6 gas monitoring system PD sensor [adequate number of UHF sensors in the offered GIS equipment(1 no in each gas compartment) for detection of Partial discharge (of 5 pC and above) as per IEC 60270 through Partial Discharge (PD) monitoring system], different gas compartment, O-ring &amp; gaskets, Nuts, Bolts &amp; Washers for Outdoor use, Absorbent, Limit Switch, SF6 Gas, etc. to complete the bus &amp; its earthing arrangement with earthing strips of adequate size (as per IEEE Std 80-2013 to protect operating staff against any hazardous touch voltages and electro-magnetic interferences) as per the technical specification.</p>	Set	1		

1.4	245kV, 2000A, 50kA for 3 sec (CB, Disconnecter, Grounding switch & CT), SF6 gas insulated <b>Bus Coupler Bay Module</b> comprising of SF6 gas insulated Single Pole Circuit Breaker (1 Set), Single Phase Current Transformer (6 Nos), Motorised 3 Phase Disconnecter (2 Nos), Motorised safety Grounding switch (2 Nos), Local Control Cubicle, SF6 gas monitoring system, PD sensor [adequate number of UHF sensors in the offered GIS equipment(1 no in each gas compartment) for detection of Partial discharge (of 5 pC and above) as per IEC 60270 through Partial Discharge (PD) monitoring system], different gas compartment, O-ring & gaskets, Nuts, Bolts & Washers for Outdoor use, Absorbent, Limit Switch, SF6 Gas, etc. to complete Bus Coupler Bay Module & its earthing arrangement with earthing strips of adequate size (as per IEEE Std 80-2013 to protect operating staff against any hazardous touch voltages and electro-magnetic interferences) as per the technical specification.	Set	1		
1.5	245kV, 2000A, 50 kA, 3 sec, single phase, SF6 gas Insulated Bus Duct outside GIS Bay along with associated Support structure arrangement bends, joints, accessories, & its earthing arrangement with earthing strips of adequate size (as per IEEE Std 80-2013 to protect operating staff against any hazardous touch voltages and electro-magnetic interferences) as per the technical specification.	RM	620		
1.6	245kV, 2000A, 50kA SF6/Air BUSHING (Bushing shall be of Polymer / composite insulator type and shall be seamless sheath of a silicone rubber compound. The hollow silicone composite insulators shall comply as per IEC 61462 and IEC 62217. The design of the composite insulators shall be tested and verified according to IEC 61462) FOR CONNECTING GIS TO AIS along with support structure.	No	18		
2	<b>2000A, 40kA for 3s, Double Busbar Circuit Breaker (Circuit breaker shall be E2-C2-M2 class as per IEC 62271-100) arrangement.</b> <b>145kV OUTDOOR GIS EQUIPMENT as per latest IEC standard &amp; type tested equipment as per technical specification, with open future proof &amp; flexible system in line with IEC 61850 &amp; IEC 62271-203.</b>				

2.1	<p>145kV, 2000A, 40kA for 3 sec (Busbars, CB, Disconnecter, Grounding Switch &amp; CT), SF6 gas insulated <b>ICT Feeder Bay Module</b> each comprising of SF6 gas insulated Single Pole Circuit Breaker (1 Set), Single Phase Current Transformer (6 Nos), Motorised Busbar 3 Phase Disconnecter (2 Nos), Motorised Disconnecter (1 No), Motorised safety Grounding switch (3 Nos), Busbars, Local Control Cubicle, SF6 gas monitoring system for complete bay, Cable termination arrangement (3 Nos), PD sensor [adequate number of UHF sensors in the offered GIS equipment(1 no in each gas compartment) for detection of Partial discharge (of 5 pC and above) as per IEC 60270 through Partial Discharge (PD) monitoring system], different gas compartment, O-ring &amp; gaskets, Nuts, Bolts &amp; Washers for Outdoor use, Absorbent, Limit Switch, SF6 Gas, etc. to complete ICT Feeder Bay Module &amp; its earthing arrangement with earthing strips of adequate size (as per IEEE Std 80-2013 to protect operating staff against any hazardous touch voltages and electro-magnetic interferences) as per the technical specification.</p>	Set	2		
2.2	<p>145kV, 2000A, 40kA for 3 sec (Busbars, CB, Disconnecter, Grounding Switch &amp; CT), SF6 gas insulated <b>Transformer Feeder Bay Module</b> each comprising of SF6 gas insulated Single Pole Circuit Breaker (1 Set), Single Phase Current Transformer (6 Nos), Motorised Busbar 3 Phase Disconnecter (2 Nos), Motorised Disconnecter (1 No), Motorised safety Grounding switch (3 Nos), Busbars, Local Control Cubicle, SF6 gas monitoring system for complete bay, SF6 bus duct termination arrangement (3 Nos), PD sensor [adequate number of UHF sensors in the offered GIS equipment(1 no in each gas compartment) for detection of Partial discharge (of 5 pC and above) as per IEC 60270 through Partial Discharge (PD) monitoring system], different gas compartment, O-ring &amp; gaskets, Nuts, Bolts &amp; Washers for Outdoor use, Absorbent, Limit Switch, SF6 Gas, etc. to complete Transformer Feeder Bay Module &amp; its earthing arrangement with earthing strips of adequate size (as per IEEE Std 80-2013 to protect operating staff against any hazardous touch voltages and electro-magnetic interferences) as per the technical specification.</p>	Set	2		

2.3	<p>145kV, 2000A, 40kA for 3 sec (Busbars, CB, Disconnector, Grounding switch, CT &amp; PT), SF6 gas insulated <b>Line Feeder Bay Module</b> each comprising of SF6 gas insulated Single Pole Circuit Breaker (1 Set), Single Phase Current Transformer (6 Nos), Single phase Line Potential Transformer with disconnecting link (4 winding) (3 Nos), Motorised 3 Phase Busbar Disconnector (2 Nos), Motorised safety Grounding switch (2 Nos), Motorised 3 Phase Disconnector with high speed fault making Motorised Grounding switch (1 No), Busbars, Local Control Cubicle, SF6 gas monitoring system for complete bay, SF6 bus duct termination arrangement (3 Nos), PD sensor [adequate number of UHF sensors in the offered GIS equipment(1 no in each gas compartment) for detection of Partial discharge (of 5 pC and above) as per IEC 60270 through Partial Discharge (PD) monitoring system], different gas compartment, O-ring &amp; gaskets, Nuts, Bolts &amp; Washers for Outdoor use, Absorbent, Limit Switch, SF6 Gas, etc. to complete Line Feeder Bay Module &amp; its earthing arrangement with earthing strips of adequate size (as per IEEE Std 80-2013 to protect operating staff against any hazardous touch voltages and electro-magnetic interferences) as per the technical specification.</p>	Set	2		
2.4	<p>145kV, 2000A, 40kA for 3 sec (Busbars, Disconnector, Grounding switch &amp; bus PT), 1 Phase Isolated Bus-PT Bay Module comprising of SF6 gas insulated metal enclosed busbars each enclosed in bus enclosures running along the length of the switchgear to interconnect each of circuit breaker bay module. Each busbar set shall be complete with Single phase bus Potential Transformer (4 winding) (3 Nos), Motorised 3 Phase Disconnector (1 No), Motorised Busbar safety Grounding switch (1 No), Busbars, Local Control Cubicle, SF6 gas monitoring system PD sensor [adequate number of UHF sensors in the offered GIS equipment(1 no in each gas compartment) for detection of Partial discharge (of 5 pC and above) as per IEC 60270 through Partial Discharge (PD) monitoring system], different gas compartment, O-ring &amp; gaskets, Nuts, Bolts &amp; Washers for Outdoor use, Absorbent, Limit Switch, SF6 Gas, etc. to complete the bus &amp; its earthing arrangement with earthing strips of adequate size (as per IEEE Std 80-2013 to protect operating staff against any hazardous touch voltages and electro-magnetic interferences) as per the technical specification.</p>	Set	1		

2.5	145kV, 2000A, 40kA for 3 sec (Busbars, CB, Disconnecter, Grounding switch & CT), SF6 gas insulated <b>Bus Coupler Bay Module</b> comprising of SF6 gas insulated Single Pole Circuit Breaker (1 Set), Single Phase Current Transformer (6 Nos), Motorised 3 Phase Disconnecter (2 Nos), Motorised safety Grounding switch (2 Nos), Busbars, Local Control Cubicle, SF6 gas monitoring system, PD sensor [adequate number of UHF sensors in the offered GIS equipment(1 no in each gas compartment) for detection of Partial discharge (of 5 pC and above) as per IEC 60270 through Partial Discharge (PD) monitoring system], different gas compartment, O-ring & gaskets, Nuts, Bolts & Washers for Outdoor use, Absorbent, Limit Switch, SF6 Gas, etc. to complete Bus Coupler Bay Module & its earthing arrangement with earthing strips of adequate size (as per IEEE Std 80-2013 to protect operating staff against any hazardous touch voltages and electro-magnetic interferences) as per the technical specification.	Set	1		
2.6	145kV, 2000A, 40 kA, 3 sec, single or three phase, SF6 gas Insulated Bus Duct outside GIS Bay along with associated Support structure arrangement bends, joints,accessories, & its earthing arrangement with earthing strips of adequate size (as per IEEE Std 80-2013 to protect operating staff against any hazardous touch voltages and electro-magnetic interferences) as per the technical specification. (In the case of 3 phase busduct, the upper row shall be used. In the case of 1 phase busduct, the lower row shall be used.)	RM	170 (3P)		
		RM	510 (1P)		
2.7	145kV, 2000A, 40kA SF6/Air BUSHING (Bushing shall be of Polymer / composite insulator type and shall be seamless sheath of a silicone rubber compound. The hollow silicone composite insulators shall comply as per IEC 61462 and IEC 62217. The design of the composite insulators shall be tested and verified according to IEC 61462) for connecting GIS ro AIS along with support structure.	No	12		
2.8	Portable Partial Discharge Monitoring System (PDM): 245kV and 145kV system shall have Portable Partial Discharge Monitoring System (PDM) & shall be capable for measuring PD in charged GIS environment, bandwidth in order of 100MHz–2GHz & provision to select a wide range of intermediate bandwidths and the principle of operation shall be based on UHF principle of detection. The Detection and measurement of PD and bouncing particles having in built large coloured LCD for displaying and storing facility in the instrument for further analysis to locate actual source of PD such as free conducting particles, floating components, voids in spacers, particle on spacer surfaces etc.	SET	1		

2.9	132 KV XLPE Cable 1000 Sq Mm ( 1000 Amps Single Core ) for 132 KV connectivity from GIS equipment to Auto Transformer & Power Transformer	MTR	1200		
2.10	132 KV Cable termination kit outdoor for 132 KV Transformers suitable for 1CX1000 Sqmm copper cable.	Nos	6		
2.11	132KV Cable termination kits (Outdoor GIS side) suitable for 1CX 1000 sq. mm Copper Cable	Nos	6		
2.12	EHV cable accessories like, link box, SVL, bonding cables, earthing cable for 132 kV system as per tech specification.	LOT	1		
3	<b>2000A, 31.5kA for 3s, Double Busbar Circuit Breaker (Circuit breaker shall be E2-C2-M2 class as per IEC 62271-100) arrangement. 36kV INDOOR GIS EQUIPMENT as per latest IEC standard &amp; type tested equipment as per technical specification, with open future proof &amp; flexible system in line with IEC 61850 &amp; IEC 62271-200.</b>				
3.1	36kV, 2000A, 31.5kA for 3 sec (CB, Disconnecter, Grounding Switch & CT), SF6 gas insulated <b>Transformer Bay Module</b> each comprising of SF6 gas insulated Vacuum Circuit Breaker (1 Set), Single Phase Current Transformer (3 Nos), Motorised Busbar 3 Phase Disconnecter (2 Nos), Motorised Disconnecter (1 No), Motorised safety Grounding switch (3 Nos), Busbars rated 2000A, Local Control Panel, SF6 gas monitoring system for complete bay, etc. to complete Transformer Bay Module suitable cable connection as per the technical specification.	Set	2		
3.2	36kV, 1250A, 31.5kA for 3 sec (CB, Disconnecter, Grounding Switch & CT), SF6 gas insulated Outgoing Feeder Bay Module each comprising of SF6 gas insulated Vacuum Circuit Breaker (1 Set), Single Phase Current Transformer (3 Nos), Motorised Busbar 3 Phase Disconnecter (2 Nos), Motorised Disconnecter (1 No), Motorised safety Grounding switch (3 Nos), Busbars rated 2000A, Local Control Panel, SF6 gas monitoring system for complete bay, etc. to complete Outgoing Feeder Bay Module suitable cable connection as per the technical specification.	Set	5		
3.3	36kV, 1250A, 31.5kA for 3 sec (Disconnecter, Grounding switch & bus PT), 1 Phase Isolated Bus-PT Bay Module comprising of SF6 gas insulated metal enclosed busbars rated 2000A each enclosed in bus enclosures running along the length of the switchgear to interconnect each of circuit breaker bay module. Each busbar set shall be complete with Single phase bus Potential Transformer (4 winding) (3 Nos), Motorised 3 Phase Disconnecter (1 No) , Motorised Busbar safety Grounding switch (1 No), SF6 gas monitoring system for complete bus system, etc. as per the technical specification.	Set	1		

3.4	36kV, 2000A, 31.5kA for 3 sec (Busbars, CB, Disconnecter, Grounding switch & CT), SF6 gas insulated Bus Coupler Bay Module comprising of SF6 gas insulated Vacuum Circuit Breaker (1 Set), Single Phase Current Transformer (6 Nos), Motorised 3 Phase Disconnecter (2 Nos), Motorised safety Grounding switch (2 Nos), Local Control Panel, SF6 gas monitoring system for complete bay, etc. to complete Bus Coupler Bay Module as per the technical specification.	Set	1		
3.5	<b>33KV EHV POWER CABLES, AL CORRUGATED XLPE CABLES</b>				
3.5.1	33KV CABLE 630 SQ. MM (800 AMPS SINGLE CORE) (for 33 KV connectivity from GI equipment to Power Transformer)	Mtes	1200		
3.5.2	33 KV Cable termination kit indoor for 33 KV Transformers suitable for 1CX630 Sqmm copper cable.	No.s	6		
3.5.3	33 KV Cable termination kit outdoor for 33 KV Transformers suitable for 1CX630 Sqmm copper cable.	No.s	6		
3.5.4	33KV CABLE 300 SQ. MM (400 AMPS SINGLE CORE) (for 33 KV connectivity from GI equipment to Station Transformer & outgoing feeders upto DP structure end)	Mtes	2500		
3.5.4	33 KV Cable termination kit indoor for 33 KV suitable for 1CX300 Sqmm copper cable.	No.s	21		
3.5.5	33 KV Cable termination kit outdoor for 33 KV suitable for 1CX300 Sqmm copper cable.	No.s	21		
4	<b>245 KV,2000A,40KA,ISOLATORS</b>				
4.1	245 KV, 2000A, 40KA, Center break ISOLATORS WITH EARTH SWITCH, supporting structure and terminal connectors as per TS.	SET	4		
5	216 KV, METAL OXIDE SURGE ARRESTOR,10 KA, class III	NOS	18		
6	220 KV Bus Post Insulators	NOS	6		
7	<b>145 KV,1250A,31.5KA,ISOLATORS</b>				
7.1	145 KV, 2000A, 40KA, Center break ISOLATORS WITH EARTH SWITCH, supporting structure and terminal connectors as per TS.	NOS	2		
8	120 KV METAL OXIDE SURGE ARRESTOR, 10 KA, Class III	NOS	18		
9	30 KV SURGE ARRESTERS	NOS	27		
10	33 KV Post Insulators	NOS	15		
10.1	<b>BUS BAR &amp; CIRCUIT MATERIALS</b>				
10.1.1	LONG ROD INSULATORS				
10.1.1.1	120 KN INSULATOR FOR 220KV (2 nos. in one set)	SET	12		
10.1.1.2	90 KN INSULATOR	NOS	7		
11	<b>ACSR MOOSE CONDUCTOR</b>	KMS	1.0		
11.1	<b>HARDWARES &amp; FITTINGS/SPACERS/CLAMP &amp; CONNECTORS</b>				
11.2	220 KV Single Suspension(120 KN)H/W fitting for Single Moose ACSR	NOS	12		
11.3	132 KV Single Suspension(90KN) H/W fitting for single Moose ACSR	NOS	6		
11.4	T- clamp for ACSR ZEBRA run to ACSR MOOSE drop	NOS	24		
11.5	T- clamp for ACSR PANTHER run to ACSR MOOSE drop	NOS	12		



11.6	220 KV PI clamp	NOS	6		
11.7	Spacer for Moose ACSR	NOS	10		
11.8	220 KV LA Clamp	NOS	18		
<b>12</b>	<b>132 KV LA Clamp</b>	NOS	18		
12.1	PG Clamp for ACSR Moose	NOS	30		
12.2	33KV LA Clamp	<b>NOS</b>	27		
12.4	<b>EARTH WIRES &amp; IT'S HARDWARES &amp; FITTING</b>				
12.5	Earthing Spikes of 9 mtr long each and Its Fittings in all respect. (220 kv side)	NOS	5		
12.6	Earthing Spikes of 7 mtr long each and Its Fittings in all respect. (132 kv side)	NOS	3		
<b>13</b>	<b>SUBSTATION EARTHING SYSTEMS</b>				
13.1	EARTHING CONDUCTOR FOR BURRIAL : 75X10 mm GI Flat for laying ( <i>spacing maximum 5m both way</i> ) = 8 km APPX	MT	47.192		
13.2	EARTHING CONDUCTOR: 50X6 mm <b>GI Flat</b> for Raiser from the burial earth mat to equipment,structure etc)	MT	3.920		
<b>14</b>	<b>EARTHING DEVICE &amp; ASSOCIATED ACCESSORIES (50 mm heavy duty GI PERFORATED PIPE 3 mtrs long for treated earth pit)</b>	Nos.	50		
14.1	EARTHING DEVICE & ASSOCIATED ACCESSORIES 40mm MS rod 3 mtrs long for non treated earth pit)	Nos.	50		
14.2	G.I Cable Trays including support GI angle suitable for different sections i.e. Section:1-1,2-2,3-3 & 4-4 along with its accessories as per TS.				
14.3	G.I Cable Trays(size: 450x75x2500mm)	MTRS	1000		
14.4	G.I Cable Trays(size: 300x75x2500mm)	MTRS	1000		
<b>15</b>	<b>G.I Cable Trays(size: 150x75x2500mm)</b>	MTRS	1000		
15.1	Support G. I angle 50x50x6 mm for cable tray	MT	4		
15.2	SUB STATION SWITCHYARD BMK,AC CONSOLE & OTHER MARSHALLING BOXES				
15.3	BAY MARSHALLING KIOSK ( <i>02 Nos. in 220 KV Side,01 Nos. in 132 KV Bay Side, 01 Nos. in 33KV Side</i> )	NOS	4		
15.4	SWITCH YARD AC CONSOLE FOR LIGHTING ( <i>01 Nos. in 220 KV bay, 01 No. in 132 kv Bay</i> )	NOS	2		
<b>16</b>	<b>SWITCH YARD RECEPTACLE BOARD FOR TFR OIL FILTERATION (01 No. near each 220/132 Auto Transformers, and 01 no. near power transformer )</b>	NOS	3		
16.1	SWITCH YARD RECEPTACLE BOARD FOR WELDING & OTHER EMERGENCY ( <i>01 No.</i> )	NOS	1		
<b>17</b>	<b>SWITCH YARD STRUCTURES (LATTICE TYPE FOR COLUMN &amp; BEAMS) FOR 220KV, 132KV &amp; 33 KV CLASS INCLUDING FOUNDATION BOLTS &amp; NUTS.</b>				
17.1	<b>DIFFERENT TYPES OF COLUMNS WITH DETAILS</b>				
17.1.1	P1S-220 KV (NOMINAL UNIT WT- 4.5 MT)- <b>5 NOS</b>	MT	22.500		

17.1.2	T1S 132KV (NOMINAL UNIT WT-1.2MT (3 NOS.))	MT	3.600		
<b>17.2</b>	<b>DIFFERENT TYPE OF BEAMS WITH DETAILS</b>				
17.2.1	Q1-220KV (NOMINAL UNIT WT- 1.5 MT) (4 NOS.)	MT	6.000		
17.2.2	G1 - 132KV (NOMINAL UNIT WT-0.62MT) ( NOS)	MT	1.240		
<b>17.3</b>	<b>TOTAL WEIGHT OF COLUMN &amp; BEAMS</b>	<b>MT</b>	<b>33.340</b>		
<b>17.4</b>	<b>EQUIPMENT SUPPORT STRUCTURES (LATTICE TYPE) FOR ALL 220KV &amp; 132 KV EQUIPMENTS INCLUDING FOUNDATION BOLTS &amp; NUTS</b>				
17.4.1	Surge Arrester-220 KV( 18 Nos.)	MT	5.258		
17.4.2	Surge Arrester-132 KV( 18 Nos.)	MT	3.288		
17.4.3	BPI-220 KV (6Nos.)	MT	1.757		
17.4.4	Cable Termination Port -33 KV (06 Nos)	MT	2.100		
<b>17.6</b>	<b>TOTAL WEIGHT OF EQUIPMENT STRUCTURES</b>	<b>MT</b>	<b>12.403</b>		
<b>18</b>	<b>Total weight of GI Nuts and Bolts for Columns, Beams &amp; Equipment Structures (taking 5% of the weight of Structures of 458.572MT)</b>	<b>MT</b>	<b>2.287</b>		
<b>18.1</b>	<b>GENERAL EQUIPMENT &amp; SUBSTATION ACCESSORIES</b>				
<b>18.1.1</b>	<b>POWER CABLES,1.1KV,XLPE &amp; PVC ARMOURED, ALUMINIUM CONDUCTOR (As per Specification)</b>				
18.1.2	XLPE 3.5 CX300 mm <sup>2</sup>	MTR	1000		
18.1.3	XLPE 3.5 CX185 mm <sup>2</sup>	MTR	1000		
18.1.4	XLPE 3.5 CX120 mm <sup>2</sup>	MTR	1000		
18.1.5	PVC 3.5 CX70 mm <sup>2</sup>	MTR	1200		
18.1.6	PVC 3.5 CX35 mm <sup>2</sup>	MTR	3200		
18.1.7	PVC 4 CX 16 mm <sup>2</sup>	MTR	2200		
18.1.8	PVC 4CX 6 mm <sup>2</sup>	MTR	5000		
18.1.9	PVC 2CX 6 mm <sup>2</sup>	MTR	5000		
<b>18.2</b>	<b>CONTROL CABLES,1.1 KV, PVC,STRANDED COPPER(As per specification)</b>				
18.2.1	2 CX 2.5 mm <sup>2</sup>	MTR	8000		
18.2.2	4 CX 2.5 mm <sup>2</sup>	MTR	15000		
18.2.3	5 CX 2.5 mm <sup>2</sup>	MTR	7500		
18.2.4	7CX 2.5 mm <sup>2</sup>	MTR	8500		
18.2.5	10 CX 2.5 mm <sup>2</sup>	MTR	15000		
18.2.6	12 CX 2.5 mm <sup>2</sup>	MTR	14500		
18.2.7	16 CX 2.5 mm <sup>2</sup>	MTR	7000		
18.2.8	19 CX 2.5 mm <sup>2</sup>	MTR	3000		
18.2.9	1CX 120 mm <sup>2</sup> BAT TO BAT CHARGER & CHARGER TO DCDB	MTR	1200		
<b>19</b>	<b>ACCESSORIES FOR PLCC SYSTEM With OPGW cable</b>				
19.1	48 Fibre Optic Approach cable along with HDPE Pipes	KM	0.50		

19.2	Optical line Terminal Equipment(OLTE) -STM4 type SDH equipment with integrated MUX & tributary cards for speech & data ports for interfacing of Speech & data which should be compatible with existing OPTCL system	No	1		
19.3	Digital Teleprotection Equipment and accessories to be suitable for interfacing with SDHMUX	No	1		
19.4	Supply of FODP(Fibre Optic Distribution Panel)48 F: Indoor type,rack mounted with FCPC coupling and pig tails(DWSm Fibre)	No	1		
19.5	48 V, 300 AH, maintenance free VRLA Battery set.	Set	1		
19.6	SMPS based Battery Charger of 75A suitable for 48V VRLA Battery set	No	1		
19.7	2.5 sq. mm multi strand 2 core control cable(power supply,Transducer/MFT PT supply)	Metre	300		
19.8	2.5 sq. mm multi strand 4 core control cable(Transducer/MFT CT supply)	Metre	300		
19.9	1.5 sq. mm multi strand 10 core control cable(Digital Input)	Metre	200		
19.10	10 sq. mm 2 core multi strand control cable(Battery)	Metre	100		
19.11	48V DCDB,	Set	1		
19.12	Earth Flat, Cable Tray, Telephone cable,Foundation rail, Junction Box,.	Set	1		
20	<b>SUPPLY OF POWER TRANSFORMER,STATION TRANSFORMER &amp; OTHER MATERIALS FOR MEETING THE AUXILIARY SUPPLY OF THE SUB-STATION AS PER TECHNICAL SPECIFICATION</b>				
20.1	<b>AUTO TRANSFORMER: 220/132KV,160 MVA (inclusive of all costs towards type test charges, Mandatory spares, Spanners &amp; Special tools, accessories, etc as specified in the Technical specification)</b>	NOS	2		
20.2	<b>POWER TRANSFORMER : 132/33 KV, 40 MVA (inclusive of all costs towards type test charges, Mandatory spares, Spanners &amp; Special tools, accessories, etc as specified in the Technical specification)</b>	NOS	2		
20.3	STATION TRANSFORMER 33KV/0.43 V,500 KVA (Confirming to Energy Efficiency Level 2 -AS PER SPECIFICATION & relevant IS)	NOS	2		

20.4	<p><b>One no. 4 pole structure (HDG Type) alongwith other equipment &amp; materials for two nos station transformers:</b></p> <p>1.4 Pole structure (using 200X100 mm RS Joist)</p> <p>2. Channel &amp; Angle FOR BRACING OF, CHANNEL for the SA &amp; Isolator &amp; HG fuse etc.</p> <p>3. 90 KN Disc/composite long rod Insulators for 33 KV (48 nos./12 sets) for bus, Bus stringing using ACSR moose conductor &amp; tension hardwares,other clamps &amp; connectors etc as per requirement.</p> <p>4. 2sets of 33 KV Isolator (800 AMP) for 33 KV side of station trafo.</p> <p>5. 2sets of 33 KV HG FUSE.</p> <p>6. 100 Sq mm AAAC conductor suitable for connection between HG fuse &amp; station transformer bushing.</p> <p>7. 2 sets of LT OUT DOOR KIOSK MADE OUT OF 3mm CRCA sheet GI MARSHALLING BOX suitable for outdoor mounting. The bus bar suitable for 1000 AMP shall be arranged in the out door kiosk and other Facility like two sets of 400 Amps MCCB for incoming &amp; outgoing with required sizes of terminal studs for power cable termination &amp; any other accessories required.</p> <p>All materials shall be As per relevant latest IS &amp; as per the direction of Engg. in charge</p>	SETS	2		
21	<p><b>SUBSTATION LIGHTING (AS PER SPECIFICATION AND APPROVED DRAWINGS) (Switch yard and other street area)</b></p>				
21.1	<p><b>SUB-STATION SWITCH YARD LIGHTING : IT INCLUDES SUPPLY OF FIXTURES &amp; LAMPS (LED) of reputed make (Philips/CGL/Bajaj/other approved make of OPTCL) with switch gear,GI Conduit etc.(Lighting fixtures are to be fixed rigidly on the Column at a suitable height so that the required lux can be achieved).(150 watt each). (* REMARKS : FOR SUPPLY OF ALL THE CABLES AS INDICATED ARE COVERED IN THE CABLE ITEMS AS INDICATED ABOVE )</b></p>	SET	60		

21.2	<p><b>STREET LIGHTING:</b> GI Tubular Pole: (410-SP-24: IS 2713-Part-II-1980 or latest) Length of pole 8.5 mtrs(minimum weight 158 Kgs). &amp; LED light fittings etc.</p> <p>(ALL THE STREET LIGHT POLE SHALL BE OF GI TUBULAR POLE AND PROVISION OF A GI JUNCTION BOX WITH SUITABLE COVERS AT A HEIGHT OF 1 METRE FROM THE GROUND. THE JUNCTION BOX SHALL HAVE PROVISION OF FUSES, BUSES, CONNECTORS FOR CABLE IN AND OUT. ( IT INCLUDES SUPPLY OF LED LIGHTING FIXTURES WITH LAMPS of 100 Watts of reputed make (Philips/CGL/Bajaj/other approved make of OPTCL) &amp; as per technical specification. (* REMARKS : FOR SUPPLY OF ALL THE CABLES AS INDICATED ARE COVERED IN THE CABLE ITEMS AS INDICATED ABOVE )</p>	SET	25		
21.3	<p><b>OUTDOOR KIOSK (HDG type) FOR STREET LIGHTING PURPOSE</b> HAVING 2 NOS 200 AMP SWITCH FUSE UNITS AND , 6 NOS.OUT LETS OF 32 AMP MCB FOR STREET LIGHTING. (SUITABLE FOR XLPE CABLES(3.5 CORE 120 SQMM) FROM MAIN ACDB FROM CONTROL ROOM TO THE OUT DOOR KIOSK. XLPE CABLE OF 4C X 16 SQMM FROM OUTDOOR KIOSK TO THE STREET LIGHT POLES AND 4CX6 SQMM FROM POLE TO POLE AND 2CX6 SQMM FROM POLE TO LIGHTING FIXTURES. &gt; 1 NO. OUTDOOR KIOSK FOR COLONY SUPPLY PURPOSE HAVING (* REMARKS : FOR SUPPLY OF ALL THE CABLES AS INDICATED ARE COVERED IN THE CABLE ITEMS AS INDICATED ABOVE )</p>	SET	2		
21.4	<p>40 Mtrs heigh Monopole (HDG) Lighting cum Lightning Mast including LED lighting fixtures (<b>240 watts each minimum 8 Nos.</b>) with control gear panel etc suitable for wind zone-VI, with all other accessories like motor for hoisting/lowering the lighting platform &amp; other switchgear and lighting control panel including required cable(copper) &amp; other accessories etc.</p>	SET	2		
22	<p><b>INDOOR LIGHTING (AS PER SPECIFICATION AND APPROVED DRAWINGS ) ( Control room building,Store shed,store room,Security room cum Visitors room and other area)</b></p>				

22.1	CONTROL ROOM BUILDING INDOOR LIGHTING, IT INCLUDES SUPPLY OF FIXTURES & LAMPS (LED) of reputed make (Philips/CGL/Bajaj/ other approved make of OPTCL) with switch gear,Conduit & other required materials for succesful illumination of the area/rooms.( No. of LED Lighting fixtures are to be calculated based on the illumination design considering the required lux level indicated in the technical spec & fixing of the same rigidly on the suitable height either ceiling & wall as required.)	LOT	1		
22.2	INDOOR LIGHTING OF SECURITY SHED CUM VISITORS ROOM,PUMP HOUSE,STORE SHED,STORE ROOM, FFPH BUILDING: IT INCLUDES SUPPLY OF FIXTURES & LAMPS (LED) of reputed make (Philips/CGL/Bajaj/ other approved make of OPTCL) with switch gear,Conduit & other required materials for succesful illumination of the area/rooms.( No. of LED Lighting fixtures are to be calculated based on the illumination design considering the required lux level indicated in the technical spec & fixing of the same rigidly on the suitable height either ceiling & wall as required.)	LOT	1		
22.3	2 TR CAPACITY SPLIT AIR CONDITIONING UNITS (Dual Inverter, five star type latest model) with copper condensor having remote temperature & operation control facility with required voltage stabiliser. Receptical indoor Control Board having suitable outgoing (one outgoing for one AC & with overload control gear) & wiring materials with 32 amp socket & plug for each unit of AC etc to complete (AS PER SPECIFICATION) FOR CONTROL ROOM, CARRIER ROOM & CONFERENCE ROOM.,OFFICE ROOM etc which includes all type of cables & wires and a main control switch gear kiosk having sufficient outlet for each air conditioner unit.	Nos.	20		

23	<p><b>Supply of Smoke &amp; Heat detection system:</b> Addressable optical Smoke &amp; Heat Multi detector (adequate Nos) for <b>control room building</b> including all accessories, the Main control panel (Microprocessor based 2 loop fire alarm control panel expandable upto 18 loops fully networkable with each loop capable of taking 99 devices, 8 line x 40 character alpha- numeric liquid crystal display .The panel shall be soft addressable type . The panel shall be able to give pin point location of all fire/fault conditions. Further, the panel must be able to automatically switch off respective control switches when ever any alarm is triggered. The panel shall have in built rectifier, Loop cards,provision for external &amp; internal printer(if required), L C D unit to indicate Fire/Fault Signal with address and analog output, built in printer to log all fire or fault events complete in all respects, integral SMF lead acid batteries with sealed cells of 24 V capable of running for a minimum of 8 hours with integral battery charger complete as required and as per specification. The fire alarm panel shall be suitable for software integration with BMS &amp; PA system ,wall mounting loop powered addressable type hooter with all accessories , addressable manual call box made of polycarbonate with plastic break glass front and complete with monitor module MCB, addressable isolator module with required PVC box, fittings and fixtures, wiring with PVC FRLS wire to cover the required for fire &amp; smoke detection etc. (One control room building is to be provided with Heat &amp; smoke detection). Should have facility for integration with SAS.</p>	SET	1		
24	<p><b>FIRE FIGHTING SYSTEM(PORTABLE AND WHEEL MOUNTED SETS FOR CONTROL ROOM,EQUIPMENT LIKE TRANSFORMER AND OTHER AREAS AS PER TECH SPEC(REFER TS-INST TO BIDDER BEFORE DESIGN-SL NO 16-ANNEXURE - I)</b></p>				
24.1	FOAM TYPE-9 LTRS	NOS	5		
24.2	DRY CHEMICAL POWDER(TROLLEY MOUNTED)- 22.5 KGS	NOS	6		
24.3	DRY POWDER TYPE - 5 KGS	NOS	6		
24.4	CO <sub>2</sub> - 4.5 KGS	NOS	6		
24.5	CO <sub>2</sub> - 9 KGS	NOS	6		
24.6	CO <sub>2</sub> (TROLLY MOUNTED)- 22.5 KGS	NOS	4		
24.7	9 litre Water type	Nos.	4		
24.8	50 Litres Mechanical Foam type	Nos.	2		

24.9	FIRE BUCKET (6 NOS IN EACH STAND) WITH STAND	SET	5		
25	<p><b>SUBSTATION AUTOMATION SYSTEM FOR 220/132/33 KV SUBSTATION ON PRP MODE:</b> Design , engineering , drawing, supervision, installation , testing &amp; commissioning of Substation Automation system alongwith Supply of the following 220, 132 and 33 kV level of protection panels consisting of Bay control Units &amp; numerical protection relays and other auxiliary relays suitable for SAS as per technical specification.</p> <p><b>(220KV side:</b> COMPRISING OF 04 Nos. FEEDER BAYS + 02 TRANSFORMER BAYS + 01 Nos BUS COUPLER BAY, <b>132 KV side:</b> COMPRISING OF 02 Nos. FEEDER SAYS + 04 Nos TRANSFORMER BAYS(auto &amp; power trf.) + 01 No. BUS COUPLER BAY) &amp; <b>33 KV side:</b> COMPRISING OF 02 Nos. FEEDER SAYS + 05 Nos TRANSFORMER BAYS + 01 No. BUS COUPLER BAY)</p> <p><b>NOTE:</b> All protective relays &amp; BCU shall be numerical type.</p>				
25.1	Yard AC Kiosk :6000 mm (L)x5000mm (W)x 4500mm (H) with AC, <b>as per the Specification;</b>	Nos.	3		
25.2	Gate way panel for Sub-Station Automation (in PRP as per the specification & indicative drg ) system (for All 220, 132 & 33 KV side bays including the future bays),other accessories (comprising servers, engg. Station, works station (Main & standby), Remote station control, Colour Laser jet Printers & dot matrix printer for local station as per requirement and also for remote station, Ethernet Switches , LIU, Red Box, Multimode glass fibre Double jacket armoured optical cables, special cables like F.O patch cord & armoured FO cables of adequate length etc required for the system in all respect as per latest IEC 61850 standard, Inverters of required capacity & rating (3KVA-Input shall be both A.C & D.C and output shall be A.C) etc as per TS. A Full HD LED screen of 70 inches for display,SAS furnitures of Godrej make & including all type of accessories & as per technical specification.	SET	1		
25.3	<b>BCU for Substation Auxilliary System</b> (Datas for monitoring of Station AC, Station DC, Lighting, Fire fighting, Air conditioning, Diesel generator etc. as per the site requirement)	SET	1		
25.4	GPS System with PTP, IRIG-B, SNTTP	SET	1		
25.5	<b>220 KV SIDE PROTECTION &amp; OTHER PANELS</b>				



25.5.1	<b>FEEDER PROTECTION PANEL</b> (MAIN-I , MAIN-II & BACK-UP PROTECTION WITH AUTO RECLOSURE DISTANCE PROTECTION with Bay control unit (BCU) with all other relays & component required for complete protection,control etc as per TS and also suitable for substation automation system.	NOS	4		
25.5.2	<b>TRANSFORMER PROTECTION PANEL</b> (DIFFERENTIAL I , REF I & BACK-UP PROTECTION & BCU for 220 KV side) & (Bay control unit-BCU and BACK-UP PROTECTION for 132 KV side) CONSIDERING HV & LV side of 220/132 KV, 160 MVA Auto transformer with all other relays & component required for complete protection,control etc as per TS and also suitable for substation automation system.	NOS	2		
25.5.3	<b>BUS COUPLER PROTECTION PANEL</b> with Bay control unit (BCU) & Back-up protection relay with with all other relays & component required for complete protection,control etc as per TS and also suitable for substation automation system.	NOS	1		
25.5.4	<b>BUS-BAR PROTECTION PANEL</b> ( Provision of bus bar modules for the future bays(two nos) and with with all other relays & component required for complete protection etc as per TS and also suitable for substation automation system.	SET	1		
<b>25.6</b>	<b>132 KV SIDE PROTECTION PANELS</b>				
25.6.1	FEEDER PROTECTION PANEL (MAIN-I & BACK-UP PROTECTION DISTANCE PROTECTION with Bay control unit (BCU) for substation automation system.	NOS	2		
25.6.2	TRANSFORMER PROTECTION PANEL (DIFFERENTIAL,REF & BACK-UP ,PROTECTION CONSIDERING HV side for 40 MVA 132/33 KV Power Transformer) with Bay control unit (BCU) for substation automation system.	NOS	2		
25.6.3	BUS COUPLER PROTECTION PANEL with Bay control unit (BCU) for substation automation system.	NOS	1		
<b>25.7</b>	<b>33 KV SIDE PROTECTION PANEL</b>				
25.7.1	FEEDER PROTECTION PANEL with Bay control & protection unit (BCPU) along with additional BACK-UP PROTECTION for substation automation system for 33KV feeders [ 2nos. Feeder bays in one panel].	SET	3		

25.7.2	TRANSFORMER PROTECTION PANEL (REF & BACK-UP ,PROTECTION CONSIDERING LV side for 2x40 MVA 132/33 KV Power Transformer) with Bay control & ptection unit (BCPU) for substation automation system. [ 2nos. Transformer bays in one panel].	SET	1		
25.7.3	STATION TRANSFORMER PROTECTION PANEL(2X 33/0.43 KV, 250 KVA) with Bay control & protection unit (BCPU) for substation automation system.	NOS	1		
25.7.4	BUS COUPLER PROTECTION PANEL with Bay control & protection unit (BCPU) for substation automation system.	NOS	1		
26	<b>AC &amp; DC SYSTEM</b>				
26.1	<b>AC SYSTEM</b>				
26.1.1	MAIN ACDB,(HAVING 800A, 50KA, DRAWOUT TYPE ACB WITH 3 O/C,E/F,U/V RELAYING FACILITY INDOOR TYPE AS PER SPECIFICATION.(MAIN DB-1,MAIN DB-2 WITH B/C)	SET	1		
26.1.2	ACDB (HAVING 400A MCCB) AS PER SPECIFICATION (ACDB-1, ACDB-2 WITH B/C)	SET	1		
26.1.3	MAIN LIGHTING DISTRIBUTION BOARD (HAVING 250A MCCB AS INCOMER)AS PER SPECIFICATION (WITH DB-1,DB-2 & B/C)	SET	1		
26.1.4	INDOOR LIGHTING DISTRIBUTION BOARD AS PER SPECIFICATION. (WITH DB-1,DB-2 & B/C)	SET	1		
26.1.5	EMERGENCY LIGHTING DISTRIBUTION BOARD	SET	1		
26.1.6	INDOOR RECEPTACLE BOARD	SET	1		
26.2	<b>DC SYSTEM</b>				
26.2.1	220 V DC BOARD (HAVING 100A DC MCCB AS INCOMER, E/F (EARTH LEAKAGE), UNDER & OVER VOLTAGE AS PER SPECIFICATION (DC DB-1,DC DB-2 & B/C)	SET	2		
26.2.2	220 V DC EMERGENCY DISTRIBUTION BOARD	SET	1		
26.2.3	BATTERY (350 AH PLANTE TYPE) FOR 220 V DC	SET	2		
26.2.4	BATTERY CHARGER FOR 350 AH, 220 V DC (FLOAT & FLOAT CUM BOOST) (including provision of series dropper diodes with heat sinks & other protection facility at the DC Load terminal end in order to feed 220 V to the load).	SET	2		
27	DISTILLED WATER PLANT OF 10 LTR/HR FOR BATTERY BANKS	SET	1		
28	WALKIE TALKIE SET	SET /PAIR	4		
29	PORTABLE ALUMINIUM LADDER EXTENDABLE TYPE OF ADEQUATE HEIGHT TO BE USED FOR MAINTENANCE OF EQUIPMENT INSIDE SWITCH YARD.	NOS	2		

30	PEDESTAL MOUNTED WHEEL FITTED DERRICK FOR LIFTING/ LOWERING OF MATERIALS UP TO 1.5 TON CAPACITY.	SET	1		
31	WATER COOLER WITH WATER PURIFIER SYSTEM	NOS	2		
32	MAINTENANCE TESTING EQUIPMENT (AS PER <b>ANNEXURE - I</b> ,INDICATED IN TS-TIMK-SCHEDULE OF REQUIREMENTS OF MAINTENANCE EQUIPMENT)	LOT	1		
33	OTHER TOOLS AND PLANTS (T&P's) REQUIREMENT (AS PER <b>ANNEXURE - II</b> ,INDICATED IN TS-TIMK-SCHEDULE OF REQUI-REMENTS OTHER T&P's)	LOT	1		
34	OFFICE FURNITURE (AS PER <b>ANNEXURE - III</b> ,INDICATED IN TS-TIMK-SCHEDULE OF REQUIREMENTS OFFICE FURNITURE)>PLACING IN CONTROL ROOM,CONFERENCE ROOM,OFFICE ROOMS,LIBRARY,TESTING LAB,etc.	LOT	1		
35	BEST QUALITY & APPROVED MAKE INSULATION MAT TO BE KEPT INFRONT OF ALL PANELS,BOARDS ETC.	NOS	50		
36	250 KVA,415 VOLTS,3 PHASE SIELENT DIESEL GENERATOR FOR EMERGENCY SITUATION	NOS	1		
37	FIRE FIGHTING EQIPMENT: (Main Pump, Jockey Pump, DG Set cum Pump, Control Panel for Fire Fighting System (HIGH PRESSURE : Hydrant and Mulsifire system) to take care of 2 Nos 160 MVA ICT, Power Transformer, switcyard equipment and buildings. HVW system & hydrant sytsem, complete with all piping, valves, fittings etc inside pump house for Fire protection sytem of substation) as per the technical spec.	LOT	1		
38	Hydrant sytsem, complete U/G piping of different sizes,vaves and accessories etc outside the Pump House for Fire protection sytem of 2 Nos 160 MVA Aoto transformers, Power transformers, switcyard equipment and buildings as per the technical spec.	LOT	1		
39	<b>EQUIPMENT and MATERIALS for GIS</b>				
39.1	<b>ACCESSORIES</b>				
39.1.1	SF6 Gas handling plant of adequate capacity as per the Technical specification	Set	1		
39.1.2	SF6 gas service cart with all accessories as per the Technical specification	Set	1		
39.2	<b>TESTING EQUIPMENT</b>				
39.2.1	GIS testing equipment as per the Technical specification. (ANY SPECIAL TOOLS & TACKLES REQUIRED (except mentioned under item No. 39.3 below) FOR COMPLETE INSTALLATION OF THE 220KV & 132 KV GAS INSULATED SWITCHGEAR (To be supplied on Non Returnable basis and shall not be taken back by the bidder)	Set	1		
39.3	<b>ESSENTIAL TOOLS and SPARES for GIS (SPARES for 245kV GIS)</b>				
39.3.1	Single phase voltage transformer	Set	1		
39.3.2	Single phase set of 5 cores current transformer including enclosure	Set	1		

39.3.3	Enclosure insulators and main circuit of busbar	Set	1		
39.3.4	Tripping and closing coils	Set	3		
39.3.5	SF6 Pressure gauges	Set	2		
39.3.6	SF6 Pressure relief devices	Set	2		
39.3.7	Auxiliary contacts for circuit breaker	Set	1		
39.3.8	Auxiliary contacts for DS and ES	Set	1		
39.3.9	SF6 gas in steel bottle 52kg / bottle	Nos	2		
39.3.10	Spring charge motor for circuit breakers	Unit	1		
39.3.11	Complete drive mechanism for disconnect switches and grounding switches	Unit	1		
39.3.12	Motor for disconnect switches and grounding switches	Unit	1		
39.3.13	Complete drive mechanism for fast acting grounding switches	Unit	1		
39.3.14	Motor for fast acting grounding switches	Unit	1		
39.3.15	Rupture disc for circuit breakers / potential transformer	Nos	1		
39.3.16	Set of spares for local control cabinet including M.C.B., fuses, time relays, auxiliary relays and terminals	Set	1		
39.3.17	Rupture disc for other components	Nos	2		
39.4	<b>SPARES for 145kV GIS</b>				
39.4.1	Single phase voltage transformer	Set	1		
39.4.2	Single phase set of 4 cores current transformer including enclosure	Set	1		
39.4.3	Enclosure insulators and main circuit of busbar	Set	1		
39.4.4	Tripping and closing coils	Set	3		
39.4.5	SF6 Pressure gauges	Set	2		
39.4.6	SF6 Pressure relief devices	Set	2		
39.4.7	Auxiliary contacts for circuit breaker	Set	1		
39.4.8	Auxiliary contacts for DS and ES	Set	1		
39.4.9	Spring charge motor for circuit breakers	Unit	1		
39.4.10	Complete drive mechanism for disconnect switches and grounding switches	Unit	1		
39.4.11	Motor for disconnect switches and grounding switches	Unit	1		
39.4.12	Complete drive mechanism for fast acting grounding switches	Unit	1		
39.4.13	Motor for fast acting grounding switches	Unit	1		
39.4.14	Rupture disc for circuit breakers / potential transformer	Nos	1		
39.4.15	Set of spares for local control cabinet including M.C.B., fuses, time relays, auxiliary relays and terminals	Set	1		
39.4.16	Rupture disc for other components	Nos	2		
39.5	<b>SPECIAL TOOLS</b>				
39.5.1	SF6 gas leak detector as per the Technical specification	Set	1		
39.5.2	SF6 gas analyzer as per the Technical specification	Set	1		
39.5.3	Milli volt drop measurement appliance	Set	1		
39.5.4	One set of Box Spanner	Set	1		
39.5.5	One set of adjustable Spanner	Set	1		
39.5.6	SF6 gas bottle locking, measuring and filling assembly with all hose	Set	2		
39.5.7	One set of pipe grooving tools for the hydraulic operating mechanism	Set	1		

39.5.8	Infrared camera as per the Technical specification	Set	1		
	<b>TOTAL OF SUBSTATION-SCHEDULE-2-Plant (to Schedule No. 6 Grand Summary)</b>				
			Name of Bidder: _____		
			Signature of Bidder: _____		

<sup>1</sup> Prices of Items quoted in Schedule No.1 shall not be quoted again in Schedule No. 2 and shall have a remark against the said row "Quoted in Schedule No

**ODISHA POWER TRANSMISSION CORPORATION LIMITED**

**NAME OF THE WORK:-Design, Supply and Installation of 2X160MVA Auto Transformer & 2X40 MVA Power Transformer,for 220/132/33 KV Out Door Type GIS Grid Sub-station at ,Kuakhia in Odisha State of India under PACKAGE-3A Under Japan International Cooperation Agency (JICA)'s ODA Loan.**

**Loan Agreement No: [ID-P245] - FB No: [CPC/JICA/ICB/03A/19-20]- Reference Identification No: [OPTCL/JICA/PKG-3A]**

**Schedule No. 4. Installation and Other Services (Sub-station )**

**NAME OF THE BIDDER**

SL. NO.	ERECTION,TESTING & COMMISSIONING OF FOLLOWING EQUIPMENT/MATERIALS ALONG WITH CIVIL & ELECTRICAL WORKS (As per Technical Specification)	UNIT	Quantity for: NAME OF THE WORK: Construction of 2*160MVA, & 2*40 MVA, 220/132 KV Open GIS & 33KV INDOOR GIS WITH SAS at KUAKHIA, JAIPUR District.	Unit Price <sup>1</sup>		Total Price <sup>1</sup>	
				Foreign Currency Portion	Local Currency Portion	Foreign Currency Portion	Local Currency Portion
			1	2	3	(1x2)	(1x3)
PART-A	CIVIL WORKS						
1	Foundations : Design, engineering, supply of all labour, material (Cement-OPC-43 Grade, coarse and fine aggregates(Sand and Metal Chips) etc) for construction of RCC ( 1:1.5:3) & PCC (1:3:6), RCC footings of any depth, pedestal and piling as per requirement including soil investigation, excavation,concreting, shuttering, grouting, underpinning and back filling of foundations etc complete for the following switch yard gantry/ portal structures and equipment support & others as per the technical specification and approved drawings.(RCC RATIO 1:1.5:3). This also includes excavation in all types of soil or rocks,back filling,and disposal of excess earth as per the direction of Engineer In charge.						
1.1	EXCAVATION FOR PREPARATION OF FOUNDATION WORK FOR THE SWITCHYARD COLUMN,EQUIPMENT etc.:This also includes excavation in all types of soil or rocks,back filling,and disposal of excess earth as per the direction of Engineer In charge.						
1.1.1	Normal Soil(SOFT/LOOSE)	Cum	2000				
1.1.2	Hard Soil	Cum	2000				
1.1.3	Soft Rock	Cum	100				
1.1.4	Hard Rock required blasting	Cum	1				

1.2	Design, Engineering, Providing and laying of plain cement concrete (PCC 1:3:6) of grade M10 with approved quality coarse aggregates (Nominal size 12mm to 20mm) , fine aggregates, cement in column and equipment foundation as blind layer inclusive of labour charges for concrete mixing & curing. This includes supply of all labourers, T&P and dewatering wherever required as per Technical specification and instruction of Engineer In charge.	Cum	150				
1.3	<b>Open Cast Foundations</b>						
1.3.1	Open cast foundation for the above column/equipment/marshalling box foundations 1:1.5:3 (Grade M-20), and placing in position of steel rods of different size as per design in the foundation pit as required for the above foundations) and including supply of Labour all materials like ,Cement, coarse and fine aggregates,shuttering,proper curing of the foundations/concrete and T&P in line with the Specification and as per direction of Engineer in Charge.	Cum	200				
1.3.2	Supply of Steel of different size (as per design) with cutting, bending, binding in position of M.S.Rod for reinforcement of foundation concrete of Piles(Under reem Pile) including supply of binding wire (With supply of steel rod ( TATA/RINL/SAIL make)	MT.	5				
1.4	<b>PILE FOUNDATION (UNDER-REAM PILE) BORING &amp; CONCRETE WORKS</b>						
1.4.1	Boring for under ream cast-in-Situ piling, with Manual Auger method or by using Motor driven Machinery,including supply of Bentonite required for stabilization bore of required diameter bore holes & approximate length of the bore is 10 Mtrs. with under reamed piles.						
1.4.1.1	375MM DIA	Mtrs	500				
14.2	Supply of all materials like cement, , all coarse aggregates, fine aggregates and making <b>Under-reamed pile</b> foundations (after pile boring as per required depth, basing on design) as per requirement, including supply of all equipment with labours, proper curing of the foundations and T&P as per specification in the concrete ratio <b>1:1.5:3</b> (Grade <b>M-20</b> ) and disposal of excess earth as per the direction of Engineer In Charge.	CUM	150				
14.3	Supply of Steel of different size (as per design) with cutting, bending, binding in position of M.S.Rod for reinforcement of foundation concrete of Piles(Under reem Pile) including supply of binding wire (With supply of steel rod FE:500 or above ( TATA/RINL/SAIL make)	MT	15				
1.5	<b>PILE RISER,CAPPING,PEDESTAL &amp; TIE-BEAM CONCRETE WORKS</b>						

1.5.1	Pile riser (if required),capping, tie beams etc, required for foundation of columns, equipment etc. including supply of cement, different gradient for concrete ratio 1:1.5:3 (Grade M-20.) including curing minimum for 15 days continuous in all type of soils and back filling etc.and disposal of excess earth as per the direction of Engineer In charge.	CUM	500				
1.5.2	Supply of Steel of different size (as per design ) with cutting, bending, binding in position of M.S.Rod for reinforcement of foundation concret of Pile Risers including supply of binding wire (With supply of steel rod FE:500 or above ( TATA/RINL/SAIL make)	MT	35				
16	<p>Cable Trenches: Design, engineering, and construction of RCC cable trenches and all associated works for cable trench and cable trench crossings as per technical specifications and approved drawings and as per direction of the Engineer in Charge.</p> <p>(1) This also includes excavation in all types of soil or rocks,back filling,and disposal of excess earth as per the direction of Engineer In charge.</p> <p>(2) Design, Engineering, Providing and laying of plain cement concrete (PCC 1:3:6) of grade M10 with approved quality coarse aggregates (Nominal size 12mm to 20mm) , fine aggregates, cement in cable trench as blind layer inclusive of labour charges for concrete mixing &amp; curing. This includes supply of all labourers, T&amp;P and dewatering wherever required as per Technical specification and instruction of Engineer In charge.</p> <p>(3) Open cast foundation for the cable trench with RCC: 1:1.5:3 (Grade M-20 Nominal mixing),including supply of Labour all materials like MS Rod,Cement, coarse and fine aggregates,shuttering,cutting,bending,binding of M.S.Rod including supply of binding wire proper curing of the foundations/concrete and T&amp;P in line with the Specification and as per direction of Engineer in Charge.</p> <p>(4) Fly ash Brickwork with fly ash Fly ash Brick ,plastering (!:6 Ratio) &amp; curing, wherever required including the supply of labour,material, cement, etc.</p> <p>(5) Fabrication &amp; Fixing of MS Angle(G.I) for cable tray support (as per specification). The cable tray support frame shall be pre fabricated GI angle as per requirement and to be welded with the plate fixed on the trench wall for better rigidity. The plate (6mm) fixed on the wall are also to be welded with the MS rods provided for the trench wall before concreting.</p> <p>(6) Precast of RCC covers (1:1.5:3) and its fixing on the cable trench as per spec and instruction of Engg. In Charge.</p> <p>(7) CABLE TRENCHES INSIDE THE CONTROL ROOM SHALL BE COVERED WITH M.S CHEQUERED PLATE(Duly painted as per instruction of Engg in charge) INCLUDING STANDARD SUPPORT STAND {HD Galvanised (M.S JOIST ,CHANNEL,ANGLE)}.</p>						
16.1	Cable trench with covers						
16.1.1	Section 1-1	Mtrs	200				
16.1.2	Section 2- 2	Mtrs	500				
16.1.3	Section 3-3	Mtrs	400				
16.1.4	Section 4-4	Mtrs	100				
16.2	Rain water harvesting system as per Technical specification and approval of drawing and as per the direction of the Engineer in charge.	LOT	1				



16.3	Cable trench crossing:Design,engineering,construction including supply of labour,materials,cement,reinforcement steel,formwork etc,and all associated works for construction of trench crossing as per technical specification and approved drawing.						
16.3.1	Road crossing for						
16.3.1.1	Section 1-1	Lot	1				
16.3.1.2	Section 2- 2	Lot	1				
16.3.1.3	Section 3-3	Lot	1				
17	<p><b>CONTROL ROOM BUILDING WITH RAMP:</b> Design, engineering and construction of switch yard buildings including the cost of all type of materials, supply of labour, cement, reinforcement- steel, form work and excavation as per the approved drawing and technical specification. <b>The column foundations shall be either shallow/open cast type or pile type foundation as per the site requirement</b> (The RCC structure frame should be in the ratio 1:1.5:3).This also includes excavation in all types of soil or rocks,back filling,and disposal of excess earth as per the direction of Engineer In charge. As per approved drawings and specification. This work including anti-termites treatment, plinth protection, DPC, peripheral drains, water supply, plumbing, sanitation, fire-fighting, electrification etc (one Double storied building having the GF: Store room,Bat room,Maint room, ACDB &amp; DCDB Room, Toilets &amp; stair case &amp; etc, FF : SAS room, conference room,Office room,Transit rest room,toilets,pantry etc).</p> <p>Control Room Building Size: <b>25 mtrs X 15 Mtrs</b></p> <p>The contractor shall finalize the dimensions of the hall &amp; rooms according to the equipment offered by them providing enough space &amp; access for erection, operation and maintenance &amp; future expansion.</p>						
17.1	Boring for under ream cast-in-Situ piling, with Manual Auger method or by using Motor driven Machinery, including supply of Bentonite required for stabilization bore of required diameter bore holes applicable for under ream piles. Design, engineering, supply of all materials like cement, steel ((FE500 and above grade- TATA/ RINL/ Sail Make), all coarse aggregates, fine aggregates and making Under-reamed pile foundations ( pile boring as per required depth, basing on design) as per requirement.	Lot	1				
17.2	RCC work(excluding piling foundation works) including MS rods(FE500 and above grade) (including excavation, PCC, Shuttering, etc. for column ,Beams and roofs etc) as per technical spec & approved drawings.	Lot	1				

17.3	Fly ash brick masonry work in cement sand mortar 1: 6 with Fly ash bricks of class designation 75 as per technical spec & approved drawings.	Lot	1				
17.4	Flooring with double charged vitrified tiles with dado in all the rooms,Bath and toilets shall be provided with anti skid ceramic tiles(wall of the same also to be provided with ceramic tiles),Acid proof industrial tiles to be provided on the floor and wall of the battery room as per technical spec & approved drawings.	Lot	1				
17.5	External and internal wall painting with primer coat as per technical spec mentioned in the civil section. External: One coat weather coat primer + two coats of weather coat colour paint. Internal: Two coats wall putty+solvent thinable white primer of one coat+two coats colour paint. Battery Room:The left over portion of walls and ceiling of Battery room shall be acid proof paints as per specification & approved drawings.	Lot	1				
17.6	External and internal wall (External (18mm thk ) and internal (12 mm thk) wall and ceiling plastering as per technical spec mentioned in the civil section) and Building internal & external & ceiling paintings as per technical spec mentioned in the civil section. The ceiling of Battery room shall be acid proof paints as per specification & approved drawings.	Lot	1				
17.7	Provision of ceiling in the control room area as per specification mentioned in the civil section & approved drawings.	Lot	1				
17.8	Doors and windows shall be of sliding type with locking facility and shall be of aluminium with glaze of 6mm & windows shall have aluminium grills. Windows shall be provided with vertical window blinder to protect from the sun ray. As per technical spec & approved drawing.	Lot	1				

17.9	Provision of PHD and other fittings of reputed make for the control room building (in Toilets, wash room, overhead water tank of adequate capacity etc) of reputed make, provision of rain water discharge pipes at different locations and etc as per requirement and approved drawing. There shall be septic tank and soak pit of required capacity including complete sewage system as per approved drawing & technical specification & as per instruction of Engg- in-Charge. It includes supply of all types of materials of reputed make, labour etc to complete the work. Toilets for Gents & Ladies to be provided including all good quality reputed fittings as per technical specification. The toilets & wash room shall have antiskid floor tiles & wall tiles of ceramic upto height of 8 feet. Provision of rain water discharge pipes at different locations and two nos of over head water tank of 2000 ltrs capacity etc as per requirement and approved drawing. All bath room & toilet shall have water & termite proof doors and provision of sliding louvers with exhaust fan.	Lot	1				
17.10	Internal concealed wiring (including supply of flexible copper FRP 1.1 KV PVC wire, conduits & its accessories, modular type switches & switch board, Junction boxes with required MCB & Earth leakage detector switchgear etc), fixing of lighting fixtures & switchgear, ceiling fans of 1400 sweep and regulators (including supply), exhaust fan (including supply), Erection of all Lighting FIXTURES & LAMPS (LED), D.C emergency lighting (including supply), as per approved drawing and direction of Engineer In charge.	Lot	1				
17.11	Supply, fitting and fixing of stainless steel pf 304 grade in hand railing using 50mm dia of 2mm thick circular pipe with balustrade of size 32mmx32mmx32mm @0.90mtr C/C and stainless square pipe bracing of size 32mmx32mmx32mm in three rows in staircase as per approved design and specification, buffing, polishing etc with cost, conveyance, taxes of all materials, labour, T&P etc required for the complete in all respect	Lot	1				
17.12	Installation of smoke and heat detection system of the building.	Lot	1				
18	<b>Boundary wall</b> : Soil investigation, Design, engineering, procurement of material like cement, steel, bricks, 'Y' post with barbed wire and concertina coil fencing 600mm Dia 10 gauge with Razer edges including other materials and labour including all associated works for construction of boundary-wall along the property line of the sub-station as per technical specification and instruction of the Engineer in Charge. (the size of the bricks shall be 250mm having 1st class Fly-ash brick having compressive strength with 75kg/cm <sup>2</sup> ). This also includes excavation in all types of soil or rocks, backfilling, and disposal of excess earth as per the direction of Engineer In charge. (**APPROXIMATE LENGTH OF THE BOUNDARY WALL) and approved drawing.						

18.1	Appox length of the Boundary wall rested on pile foundation:. size of the pile shall be 375mm dia & depth of 5000mm minimum at an interval of 3000mm having 300x300 Grade beam on the pile & Brick works rested on RCC Beam and RCC Columns as per TS	R. Mtrs.	650				
19	Roads: Design, construction of roads and walkways/ shoulders within sub-station(Switch yard area,colony area,approach road,control room building area, main gate to the switch yard gate etc) as per specification, layout and approved drawings complete. This also includes excavation in all types of soil or rocks,back filling,and disposal of excess earth as per the direction of Engineer In charge. Provision of drains on both the side of the roads for easy discharge of rain water.						
19.1	7 mtrs concrete road with shoulder at both the side as per technical specification indicated in the civil section(from the switch yard main gate to power transformer,approach road & infront of GIS cum control room building & Shall have drain on both side of the road.	Mtrs	400				
19.2	4 mtrs concrete road with shoulder at both the side & shall have drain on both side of the road as per technical specification indicated in the civil section( Periphery roads outside switch yard fencing and colony roads)	Mtrs	300				
20	Drainage system:Collection of rainfall data, Design, construction of storm water drainage scheme (RCC type), road-culverts,Shall have drain on both side of the road and drains crossing cable trenches etc. as per specification and approved drawing. This also includes excavation in all types of soil or rocks,back filling,and disposal of excess earth as per the direction of Engineer In charge. All the switch yard bays , roads water drainage shall be connected to the main surface drain. As per approved drawing and specification.						
20.1	Storm water drain	Mtrs.	700				
20.2	Road-culverts, drain crossings	Lots	1				
20.3	Cable trench crossing	Lots	1				

21	Design, engineering, supply of labour, material, equipments and construction of Auto-transformer/Power Transformer foundation including piling, all associated works, rail tracks, jacking pads, anchor block RCC and PCC, miscellaneous structural steel including oil collection pits, MS grating(if required), gravel filling, and other items etc. not mentioned herein, but specifically required for the completion of the work as per technical specification and approved drawing and this foundation should be connected with Main concrete road of the switch-yard . (Rate shall be inclusive of cement, reinforcement steel, angles, RS joists, Channels , Rails , flats and form work etc.)(all cement concrete shall have RCC ratio 1:1.5:3).This also includes excavation in all types of soil or rocks, backfilling, and disposal of excess earth as per the direction of Engineer In charge.						
21.1	160 MVA, 220/132 KV Auto transformer: Overall dimension of Transformer with Radiator. Total weight of Transformer as mentioned in Technical specification(Considering approximate foundation value)	Nos	2				
21.2	40 MVA, 132/33kV Power Transformer (Overall dimension of transformer(approx) Length:7200 mm X Width 6000 mm X Height 6200 mm) Total weight with oil and tank: 97.5 MT (approx) <b>As Per Technical Specification</b>	Nos	2				
21.3	Fire wall: Design, engineering, procurement of labour, material including all associated works for construction of fire-walls as per technical specification and approved drawings(column shall be RCC ratio 1:1.5:3 and the walls are of fire resistant bricks).This also includes excavation in all types of soil or rocks, backfilling, and disposal of excess earth as per the direction of Engineer In charge. As per approved drawing and specification. Painting of the walls as per direction of the Site In charge	Nos	2				
21.4	NCT FOUNDATION: Design, engineering, procurement of labour, material including all associated works for construction of foundation NCT(also refer clause 1,1.1,&1.2) near Transformers and as per approved drawing and requirement and also as per the instruction of Engineer in charge. This also includes excavation in all types of soil or rocks, backfilling, and disposal of excess earth as per the direction of Engineer In charge.	Nos	4				
21.5	STATION TRANSFORMER: Design, engineering, procurement of labour, material including all associated works for construction of Transformer foundation, Four Pole structure and Koisk etc. for station transformers 33/0.43 KV, 500 KVA as per approved drawing and specification.	Nos	2				

21.6	OIL SUMP PIT:Oil collection (from transformers)sump pit with provision of pump(5 HP, with auto level control , including cabling, fixing of control gear )as per CIGRE. As per spec and approved drawing. >Oil capacity of each AUTO in ltrs appox. a) 160 MVA, 220/132 KV: 70000 ltrs.	Nos	1				
21.8	OIL SUMP PIT:Oil collection (from transformers)sump pit with provision of pump(5 HP, with auto level control , including cabling, fixing of control gear )as per CIGRE. As per spec and approved drawing. >Oil capacity of each Power Transformer in ltrs appox. a) 40 MVA, 132/33 KV, 27000 Ltrs	Nos	2				
22	PCC before site surfacing :Providing and supplying all labour, material, equipments etc. required for proper leveling of earth after erection of structures and equipments and proper compaction by using roller of adequate capacity(minimum 3 Ton capacity) with water sprinkling of switch yard area. After proper leveling of the switch yard area (after anti-weed treatment), spreading of plain cement concrete with mixing ratio 1:3:6 (M10) and maintaining proper sloping for easy discharge of storm water having concrete thickness of 75 mm. including rolling , dressing, compacting,the area. This also includes excavation in all types of soil or rocks,back-filling,and disposal of excess earth as per the direction of Engineer in charge and approved drawing. (Switch yard area)	CUM	2640				
23	Metal Spreading: Providing supplying and laying two layers of machine crushed metals (gravel) fill, the first layer after compaction shall make minimum 50 mm thickness coarse/ layer of 20 mm nominal size consolidated/ compacted and (by using roller as specified in the specification).A final layer of 50 mm thickness of machine crushed 20 mm nominal size of metals(gravel) above the first layer of 50 mm thickness and as per the technical specification and instruction of Engineer in charge above the PCC(1:3:6). The total compacted thickness of the metals(20 mm Nominal) 100mm above the PCC.	CUM	2640				
24	CONTOUR SURVEY,AND LEVELING, BACK FILLING						
24.1	Contour survey of the entire sub-station area including Supply of all labour & T&P by contractor.	SQM	25000				
24.2	Soil investigation : Supply of labour,T&Pand other necessary arrangements for Soil investigation/testing of the Switchyard,control Room, Quarters area etc.as per the site requirement,Technical specification & instruction of Engineer-in-Charge.	PER POINT	10				
24.3	Cutting, Filling and Leveling of Sub-station area including supply of labour and T&P						

25	LEVELLING OF S/S AREA:Providing, neatly dressing up and leveling of substation area including switch yard area to a required level as decided by the Engineer in Charge, the work includes removal, clearing of the entire area from vegetation, trees, bushes, uprooting of plants and disposal of surplus earth and unusable material from the site by means of any mechanical transport, if required as per direction of the Project In charge, with all labours, tools, tackles and plants complete as per approved drawing and specification. This also includes excavation in all type of soils or rocks, back filling and disposal of excess earth or rocks to make the area to a level for construction as per scope and as per approved drawing and specification.						
25.1	Cutting of earth & filling of the said earth as per the direction of Engineer in Charge.	Cum	2000				
25.2	Filling with borrowed earth beyond 30 mtrs & up to 100mtrs lead as per the direction of Engineer in Charge.	Cum	10000				
25.3	Filling with borrowed earth beyond 100 mtrs lead as per the direction of Engineer in Charge.	Cum	30000				
26	PROVISION OF GARDEN:Provision of gardens in front of the control room building,GIS buildings & other areas where can be provided as per the site Engineer's instruction, including supply of decorative plants,garden grass,flowering plants,soil treatment and its plantation including materials,labour and T&P. As per the instruction of Engineer in Charge . Provision of water tap with water sprinkler arrangement including water pipe laying with control at different location. Supply of All materials. Both side of the RCC roads shall be provided with decorative plants as per the instruction of the Site Engineer.	LOT	1				
27	STONE PITCHING & TOE WALL:Stone pitching including making of toe walls both at top and bottom, including surface drain both at top and bottom and partition wall in every 10 mtrs by using boulders and RR masonry walls respectively. This also includes excavation in all types of soil or rocks,back filling,and disposal of excess earth and supply of materials and labour as per the direction of Engineer In charge and as per approved drawing and specification.						
27.1	Excavation in Soft & Loose Soil	Cum	200				
27.2	P.C.C (1:3:6): Lean Concrete Grade M-10	Cum	22				
27.3	RR Masonry (1:5)	Cum	225				
27.4	P.C.C (1:2:4): Lean Concrete Grade M-15	Cum	2				

28	SWITCH YARD FENCING: Providing and fixing of G.I Goat mesh (2.5 mm dia)( in a GI angle 50X50X6 mm frame having 50X6 mm GI flat bracing corner to corner) fencing( the posts and links shall be of HD Galvanized ) in switch yard and other areas of the substation with a total fence height complete as per specification and approved drawings, and as required under the safety regulation of local, state and central government bodies and as per instruction of the Engineer-in-Charge.(The PCC work for grouting the post shall be 1:2:4 and a continuous Fly ash Brick masonry work with ratio 1:5 and cement pointing of the joints, for the fencing up to a height from the finished ground level) .This also includes excavation in all types of soil or rocks, back filling,and disposal of excess earth as per the direction of Engineer In charge. The earthing of the fencing as per specification.	Mtr	500				
28.9	Any other civil work to be included in the schedule by the Bidder if required essential for successful completion of project, including supply of labour, material, cement reinforcement steel, form work etc. Bidder shall also quote the unit rate for the following items of works.(Rate shall be inclusive of supply of labour, material, cement, reinforcement steel, form work etc. )						
29.1	Excavation:This also includes excavation in all types of soil or rocks,back filling,and disposal of excess earth as per the direction of Engineer In charge.	Cu.m.	1				
29.2	Fly ash Brick masonry work using fly ash Fly ash Brick in cement sand mortar 1: 5 with Fly ash Bricks of class designation 75.	Cu.m.	1				
29.3	12 mm thick plaster in cement sand mortar ( 1: 5 ).	Sq.m.	1				
30	MAIN GATE & SWITCH YARD GATES:Design, engineering, procurement of labour, material including all associated works for construction and fixing of of a main gate and one no. switch yard gates with men gates as per specification and approved drawing. This also includes excavation in all types of soil or rocks,back filling,and disposal of excess earth as per the direction of Engineer In charge. Provision of gate lights (Post top lantern type) on each pillar of the gate. It includes supply & fixing of light fixtures including LED Gate lamp, LV XLPE cables, switchgear etc required to complete works as per specification and approved drawings.(* REMARKS : FOR SUPPLY OF ALL THE CABLES AS INDICATED ARE COVERED IN THE supply)}						
30.1	MAIN GATE	NOS	2				
30.2	WICKET GATE NEAR MAIN GATE	NOS	1				
30.3	SWITCH YARD GATE(ON BOTH SIDES OF 7MTRS. CONCRETE ROAD OF SWITCHYARD)	NOS	2				
30.4	WICKET GATE NEAR SWITCHYARD	NOS	1				



31	<p>FIRE FIGHTING &amp; DG BUILDING:(one building).Design, engineering and construction of buildings including the piling where required, the cost of material, supply of labour, cement, reinforcement- steel, form work and excavation as per the approved drawing and technical specification ( The RCC structure frame should be in the ratio 1:1.5:3).This also includes excavation in all types of soil or rocks,backfilling,and disposal of excess earth as per the direction of Engineer In charge.As per approved drawings and specification.</p> <p>Area of the Fire Fighting &amp; DG Room with portico at front side, stair case to the top of the building ,.The details of of building construction shall be as per the Tech spec.</p>						
31.1	RCC volume including MS rods(including column ,Beams and roofs etc) as per technical spec & approved drawings.	Lot	1				
31.2	Brick masonry work in cement sand mortar 1: 6 with bricks of class designation 75kg/mm2 as per technical spec & approved drawings.	Lot	1				
31.3	Concrete Flooring to be provided on the floor I of the DG cum Fire Fighting room as per technical spec & approved drawings.	Lot	1				
31.4	External and internal wall painting with primer coat as per technical spec mentioned in the civil section. External: One coat weather coat primer + two coats of weather coat colour paint. Internal: Two coats wall putty+solvent thinable white primer of one coat+two coats colour paint. Refer the specification.	Lot	1				
31.5	Doors and windows shall be of sliding type with locking facility and shall be of aluminium with glaze of 6mm & windows shall have aluminium grills. As per technical spec & approved drawing.	Lot	1				
31.6	Provision of PHD and other fittings of reputed make having ISI mark ,provision of rain water discharge pipes at different locations and etc as per requirement and approved drawing & technical specification & as per instruction of Engg- in-Charge. It includes supply of all types of materials of reputed make, labour etc to complete the work.	Lot	1				
31.7	Internal concealed wiring,fixing of lighting fixtures(LED) ,fans and regulators(Electronic regulator) ,exhaust fan,D.C emergency lighting INCLUDING SUPPLY OF ALL ITEMS as per spec & approved drawing.	Lot	1				
31.8	Provision of smoke and fire detection system of the building.	Lot	1				
31.9	Provision of Water Tank for fire fighting below ground.	Lot	1				

32	<p>SECURITY SHED &amp; CUM VISITOR ROOM: Design, engineering, procurement of labour, material including all associated works for construction of Security shed near main gate, watch tower shed at the corners of switch yard as per the approved drawing and instruction of Engineer in charge. This also includes excavation in all types of soil or rocks or pile boring, back filling, and disposal of excess earth as per the direction of Engineer In charge. Internal electrification including supply of lighting fixtures, fan with regulators and provision of incoming AC supply from the main ACDB/outdoor kiosks installed for street light or colony quarters. Also includes painting of the building (in side and out side) as per recommended for colony building in the specification. <b>Including Latrin &amp; Bath Provision</b> (* REMARKS : FOR SUPPLY OF ALL THE CABLES AS INDICATED ARE COVERED IN THE supply))</p>						
32.1	<p>SECURITY SHED: The size of the security shed shall be 3.5 mtrs X 6.5 mtrs and height of 3.5 mtrs RCC roof, Fly ash Brick masonry works, plastering and painting and fixing of MS doors and windows. Internal concealed wiring (including supply of flexible copper FRP 1.1 KV PVC wire, conduits &amp; its accessories, modular type switches &amp; switch board, Junction boxes with required MCB &amp; Earth leakage detector switchgear etc), fixing of lighting fixtures &amp; switchgear, ceiling fans of 1400 sweep and regulators (including supply) and provision of incoming AC supply from the main ACDB/outdoor kiosks installed for street light or colony quarters. Also includes painting of the building (in side and out side) as per recommended for colony building in the specification. <b>Including Latrin &amp; Bath Provision</b>(* REMARKS : FOR SUPPLY OF ALL THE CABLES AS INDICATED ARE COVERED IN THE supply))</p>	Nos	1				

32.2	<p>BORE WELL &amp; PUMP HOUSE:Design, engineering, procurement of labour, material including all associated works for construction of two nos. bore wells for control room building including switch yard and colony quarters as per specification and approved drawing and instruction of Engineer in charge. This includes supply and fixing and commissioning of two nos 5 HP submersible water pump with starter and other protection. Construction of two nos pump house at ideal location for fixing of the electrical starter units. The pump house be of RCC roof and having walls of Fly ash Brick masonry and plastering and painting of external &amp; internal walls with MS door having locking arrangement &amp; window. Internal concealed wiring (including supply of flexible copper FRP 1.1 KV PVC wire,conduits &amp; its accessories,modular type switches &amp; switch board. The size of the room shall be 2.5mtrsX2.5 mtrs having height of 3 mtrs. as per approved drawing and specification. There shall be approach road to the pump house. This includes supply of materials,labours and T&amp;P &amp; excavation of all type of soils including rock and disposal of excess materials as per instruction of Engineer In charge Supply &amp; laying of LV XLPE 3.5CX 35 sq mm cable from ACDB to pump house, control gear &amp; earthing of the system etc to complete the scheme as per approved drawing &amp; instruction of Engineer-in charge.</p>	LOT	2				
33	<p>COLOUR CODING, BAY MARKING Etc:Design, engineering, procurement of labour, material including all associated works for the followings. This should be as per direction of site In charge. a)Color coding (red, Yellow &amp; Blue) for equipments, Bus gantry &amp; column of entire switch yard. Good quality weather proof sticker may be used for identification. b)Each bay should be identified with the help of bay marker sign board, suitably grouted. MS sign board with stand to be installed. Proper painting and lettering to be done of the entire switch yard area.</p>	Lot	1				

34	<p>STORE SHED:Design, engineering, procurement of labour, material including all associated works for construction of store shed as per specification and approved drawing. This also includes excavation in all types of soil or rocks or pile boring,back filling,and disposal of excess earth as per the specification,approved drawing and direction of Engineer In charge. One no store shed of floor size 10X10 mtr having Fly ash Brick walls and plastering with RCC roof. The flooring shall be of 75 mm thickness PCC (mix ratio1:2:4) over RR masonry works (as per standard practice of flooring). Provision of adequate nos of MS racks (proper paintings also to be done as per the direction of site in charge) for keeping the spare materials. The height of the shed shall be 4mtrs above the plinth. Internal concealed wiring (including supply of flexible copper FRP 1.1 KV PVC wire,conduits &amp; its accessories,modular type switches &amp; switch board,Junction boxes with required MCB &amp; Earth leakage detector switcghear etc),fixing of lighting fixtures &amp; switchgear ,ceiling fans of 1400 sweep and regulators( including supply) and provision of incoming AC supply from the main ACDB/outdoor kiosks installed for street light or colony quarters. Also includes painting of the building (in side and out side) as per recommended for colony building in the specification. (* REMARKS : FOR SUPPLY OF ALL THE CABLES AS INDICATED ARE COVERED IN THE supply}}</p>	Lot	1				
35	<p>PLATFORM FOR STORING EQUIMENTS:Design, engineering, procurement of labour, material including all associated works for construction of a platform for storing of bushings,Instrument transformers etc, as per specification and approved drawing.This also includes excavation in all types of soil or rocks,backfilling,and disposal of excess earth as per the specification,approved drawing and direction of Engineer In charge. One no platform outside the store shed RR masonry (compacted) with PCC at the top for storing the transformer bushings, Instrument transformers, transformer oil drums etc. The floor size of the platform shall be 15mtrX10 mtr with Galvanised Corrugated Sheet (Tata Make) top cover and associated MS supporting structure duly painted.</p>	NOS	1				

36	PROVISION OF PLANTATIONS:Provision of plantation of 100 nos fruit bearing plants and 100 nos decorative plants at different locations, a garden in front of the control room including supply of plants,soil treatment and its plantation including materials,labour and T&P. As per the instruction of Engineer in Charge and specification.	Lot	1				
37	Anti-Weed Treatment						
37.1	Supply of labour,T&P,Chemicals and other necessary arrangements for anti-weed treat of the switch-yard areas,controlroom etc. as per the instruction of Engineer-in-Charge.The chemical to be sprayed as per the standard practice adopted for antiweed treatment of sub-station area & as per the technical specification.	Sq Mtrs	24000				
38	VEHICLE PARKING SHED: The size of the parking area shall be 15mtrs X 15 mtrs, out of the entire area there shall be provision of shed for 5 mtrs X 15 mtrs and rest of the area shall be without shed. 100 mm thick PCC(1:2:4) flooring after the preparing the foundation base & Roof of the parking place shall be RCC & Parking shed shall be as per TS-E6-Civil & as per the direction of Engineer in Charge.	Lot	1				
39	Construction of township/colony (residential quarters) for staff and employees of the employer. Layout, design, survey, levelling, site dressing and clearing of the area, soil investigation, excavation, PCC, RCC, Fly ash Brick work, plastering ,flooring(flooring shall be with vitrified tiles of reputed make with a dado of minimum6 inches),fixing of doors windows and window grills, including all labour, T&P, material like cement ,sand aggregate, Fly ash Bricks, reinforcements etc with all bought items required for completion of the quarters as per approved construction drawings with all facilities for supply of drinking water. The outer paint shall be applied with weather coat synthetic enamel paint as per the standard practice of application and the inner paint shall be applied with distemper of approved quality as per the instruction and approval of the same by OPTCL. This also includes excavation in all types of soil or rocks or pile boring,back filling,and disposal of excess earth as per the direction of Engineer In charge. Internal electrical wiring with fixing of light fixtures and fans with electronic regulators and exhaust fans as per technical specification and approved drawing. Construction of over head RCC tank(1000 ltrs capacity one for each quarters), sewerage disposal and connection with main sewerage/ septic tank and soak pit, storm water and surface drainage, culverts, roads, with suitable radius on the curves and its connection with main road the substation, street lighting, internal lighting, internal plumbing and sanitation including internal/external finishing of quarters etc. required for completion of the town ship. (RCC column structure frame and the Fly ash Bricks to be used shall be fly ash Fly ash Brick, all the door and window frame & panels shall be aluminium with adequate size as indicated in the TS and also as per the National Building Code adopted.						

39.1	<b>"D" type Quarter As per technical specification: 1 no quarter on ground floor &amp; 1 no quarter on First floor ,the size of each quarter plinth area shall be 120 Sq Mtrs(appox)</b>						
39.1.1	"D" type Quarter As per technical specification: 1 no quarter on ground floor & the size of quarter plinth area shall be 120 Sq Mtrs(appox)	SQ.MTRS	120				
39.1.2	"D" type Quarter As per technical specification: 1 no quarter on First floor & the size of quarter plinth area shall be 120 Sq Mtrs(appox)	SQ.MTRS	120				
39.2	<b>"E" type Quarter As per technical specification (one no. two storied flat. Each flat shall be with 2 nos quarters on ground floor &amp; 2 Nos quarters on 1st floor).(There shall be 4 Nos quarters to be accommodated in one flat as E1,E2,E3 &amp; E4)</b>						
39.2.1	"E" type Quarter As per technical specification: 2 nos quarters on ground floor (Each quarter size plinth area shall be 73 Sq Mtrs(appox)	SQ.MTRS	146				
39.2.3	"E" type Quarter As per technical specification: 2 nos quarters on first floor(Each quarter size plinth area shall be 73 Sq Mtrs(appox)	SQ.MTRS	146				
	<b>TOTAL OF CIVIL WORKS (PART-A)</b>						
<b>PART B</b>	<b>ELECTRICAL WORKS</b>						
<b>1</b>	<b>2000A, 50kA for 3s, Double Busbar Circuit Breaker (Circuit breaker shall be E2-C2-M2 class as per IEC 62271-100) arrangement. 245kV OUTDOOR GIS EQUIPMENT as per latest IEC standard &amp; type tested equipment as per technical specification, with open future proof &amp; flexible system in line with IEC 61850 &amp; IEC 62271-203.</b>						
<b>1.1</b>	245kV, 2000A, 50kA for 3 sec (Busbar, CB, Disconnecter, Grounding Switch & CT), SF6 gas insulated ICT Feeder Bay Module each comprising of SF6 gas insulated Single Pole Circuit Breaker (1 Set), Single Phase Current Transformer (6 Nos), Motorised Busbar 3 Phase Disconnecter (2 Nos), Motorised Disconnecter (1 No), Motorised safety Grounding switch (3 Nos), Local Control Cubicle, SF6 gas monitoring system for complete bay, SF6 bus duct termination arrangement (3 Nos), PD sensor [adequate number of UHF sensors in the offered GIS equipment(1 no in each gas compartment) for detection of Partial discharge (of 5 pC and above) as per IEC 60270 through Partial Discharge (PD) monitoring system], different gas compartment, O-ring & gaskets, Nuts, Bolts & Washers for Outdoor use, Absorbent, Limit Switch, SF6 Gas, etc. to complete <b>ICT Feeder Bay Module</b> & its earthing arrangement with earthing strips of adequate size (as per IEEE Std 80-2013 to protect operating staff against any hazardous touch voltages and electro-magnetic interferences) as per the technical specification.	<b>Set</b>	<b>2</b>				

1.2	<p>245kV, 2000A, 50kA for 3 sec (Busbar, CB, Disconnector, Grounding switch, CT &amp; PT), SF6 gas insulated Line Feeder Bay Module each comprising of SF6 gas insulated Single Pole Circuit Breaker (1 Set), Single Phase Current Transformer (6 Nos), Single phase Line Potential Transformer with disconnecting link (4 winding) (3 Nos), Motorised 3 Phase Busbar Disconnector (2 Nos), Motorised safety Grounding switch (2 Nos), Motorised 3 Phase Disconnector with high speed fault making Motorised Grounding switch (1 No), Local Control Cubicle, SF6 gas monitoring system for complete bay, SF6 bus duct termination arrangement (3 Nos), PD sensor [adequate number of UHF sensors in the offered GIS equipment(1 no in each gas compartment) for detection of Partial discharge (of 5 pC and above) as per IEC 60270 through Partial Discharge (PD) monitoring system], different gas compartment, O-ring &amp; gaskets, Nuts, Bolts &amp; Washers for Outdoor use, Absorbent, Limit Switch, SF6 Gas, etc. to complete <b>Line Feeder Bay Module</b> &amp; its earthing arrangement with earthing strips of adequate size (as per IEEE Std 80-2013 to protect operating staff against any hazardous touch voltages and electro-magnetic interferences) as per the technical specification.</p>	Set	4				
1.3	<p>245kV, 2000A, 50kA for 3 sec (Busbars, Disconnector, Grounding switch &amp; bus PT), 1 Phase Isolated Bus-PT Bay Module comprising of SF6 gas insulated metal enclosed busbars each enclosed in bus enclosures running along the length of the switchgear to interconnect each of circuit breaker bay module. Each busbar set shall be complete with Single phase bus Potential Transformer (4 winding) (3 Nos), Motorised 3 Phase Disconnector (1 No) , Motorised Busbar safety Grounding switch (1 No), Local Control Cubicle, SF6 gas monitoring system PD sensor [adequate number of UHF sensors in the offered GIS equipment(1 no in each gas compartment) for detection of Partial discharge (of 5 pC and above) as per IEC 60270 through Partial Discharge (PD) monitoring system], different gas compartment, O-ring &amp; gaskets, Nuts, Bolts &amp; Washers for Outdoor use, Absorbent, Limit Switch, SF6 Gas, etc. to complete the bus &amp; its earthing arrangement with earthing strips of adequate size (as per IEEE Std 80-2013 to protect operating staff against any hazardous touch voltages and electro-magnetic interferences) as per the technical specification.</p>	Set	1				

1.4	245kV, 2000A, 50kA for 3 sec (CB, Disconnecter, Grounding switch & CT), SF6 gas insulated <b>Bus Coupler Bay Module</b> comprising of SF6 gas insulated Single Pole Circuit Breaker (1 Set), Single Phase Current Transformer (6 Nos), Motorised 3 Phase Disconnecter (2 Nos), Motorised safety Grounding switch (2 Nos), Local Control Cubicle, SF6 gas monitoring system, PD sensor [adequate number of UHF sensors in the offered GIS equipment(1 no in each gas compartment) for detection of Partial discharge (of 5 pC and above) as per IEC 60270 through Partial Discharge (PD) monitoring system], different gas compartment, O-ring & gaskets, Nuts, Bolts & Washers for Outdoor use, Absorbent, Limit Switch, SF6 Gas, etc. to complete Bus Coupler Bay Module & its earthing arrangement with earthing strips of adequate size (as per IEEE Std 80-2013 to protect operating staff against any hazardous touch voltages and electro-magnetic interferences) as per the technical specification.	Set	1				
1.5	245kV, 2000A, 50 kA, 3 sec, single phase, SF6 gas Insulated Bus Duct outside GIS Bay along with associated Support structure arrangement bends, joints, accessories, & its earthing arrangement with earthing strips of adequate size (as per IEEE Std 80-2013 to protect operating staff against any hazardous touch voltages and electro-magnetic interferences) as per the technical specification.	RM	620				
1.6	245kV, 2000A, 50kA SF6/Air BUSHING (Bushing shall be of Polymer / composite insulator type and shall be seamless sheath of a silicone rubber compound. The hollow silicone composite insulators shall comply as per IEC 61462 and IEC 62217. The design of the composite insulators shall be tested and verified according to IEC 61462) FOR CONNECTING GIS TO AIS along with support structure.	No	18				
2	<b>2000A, 40kA for 3s, Double Busbar Circuit Breaker (Circuit breaker shall be E2-C2-M2 class as per IEC 62271-100) arrangement.</b> <b>145kV OUTDOOR GIS EQUIPMENT as per latest IEC standard &amp; type tested equipment as per technical specification, with open future proof &amp; flexible system in line with IEC 61850 &amp; IEC 62271-203.</b>						



2.1	<p>145kV, 2000A, 40kA for 3 sec (Busbars, CB, Disconnecter, Grounding Switch &amp; CT), SF6 gas insulated <b>ICT Feeder Bay Module</b> each comprising of SF6 gas insulated Single Pole Circuit Breaker (1 Set), Single Phase Current Transformer (6 Nos), Motorised Busbar 3 Phase Disconnecter (2 Nos), Motorised Disconnecter (1 No), Motorised safety Grounding switch (3 Nos), Busbars, Local Control Cubicle, SF6 gas monitoring system for complete bay, Cable termination arrangement (3 Nos), PD sensor [adequate number of UHF sensors in the offered GIS equipment(1 no in each gas compartment) for detection of Partial discharge (of 5 pC and above) as per IEC 60270 through Partial Discharge (PD) monitoring system], different gas compartment, O-ring &amp; gaskets, Nuts, Bolts &amp; Washers for Outdoor use, Absorbent, Limit Switch, SF6 Gas, etc. to complete ICT Feeder Bay Module &amp; its earthing arrangement with earthing strips of adequate size (as per IEEE Std 80-2013 to protect operating staff against any hazardous touch voltages and electro-magnetic interferences) as per the technical specification.</p>	Set	2				
2.2	<p>145kV, 2000A, 40kA for 3 sec (Busbars, CB, Disconnecter, Grounding Switch &amp; CT), SF6 gas insulated <b>Transformer Feeder Bay Module</b> each comprising of SF6 gas insulated Single Pole Circuit Breaker (1 Set), Single Phase Current Transformer (6 Nos), Motorised Busbar 3 Phase Disconnecter (2 Nos), Motorised Disconnecter (1 No), Motorised safety Grounding switch (3 Nos), Busbars, Local Control Cubicle, SF6 gas monitoring system for complete bay, SF6 bus duct termination arrangement (3 Nos), PD sensor [adequate number of UHF sensors in the offered GIS equipment(1 no in each gas compartment) for detection of Partial discharge (of 5 pC and above) as per IEC 60270 through Partial Discharge (PD) monitoring system], different gas compartment, O-ring &amp; gaskets, Nuts, Bolts &amp; Washers for Outdoor use, Absorbent, Limit Switch, SF6 Gas, etc. to complete Transformer Feeder Bay Module &amp; its earthing arrangement with earthing strips of adequate size (as per IEEE Std 80-2013 to protect operating staff against any hazardous touch voltages and electro-magnetic interferences) as per the technical specification.</p>	Set	2				

2.3	<p>145kV, 2000A, 40kA for 3 sec (Busbars, CB, Disconnector, Grounding switch, CT &amp; PT), SF6 gas insulated <b>Line Feeder Bay Module</b> each comprising of SF6 gas insulated Single Pole Circuit Breaker (1 Set), Single Phase Current Transformer (6 Nos), Single phase Line Potential Transformer with disconnecting link (4 winding) (3 Nos), Motorised 3 Phase Busbar Disconnector (2 Nos), Motorised safety Grounding switch (2 Nos), Motorised 3 Phase Disconnector with high speed fault making Motorised Grounding switch (1 No), Busbars, Local Control Cubicle, SF6 gas monitoring system for complete bay, SF6 bus duct termination arrangement (3 Nos), PD sensor [adequate number of UHF sensors in the offered GIS equipment(1 no in each gas compartment) for detection of Partial discharge (of 5 pC and above) as per IEC 60270 through Partial Discharge (PD) monitoring system], different gas compartment, O-ring &amp; gaskets, Nuts, Bolts &amp; Washers for Outdoor use, Absorbent, Limit Switch, SF6 Gas, etc. to complete Line Feeder Bay Module &amp; its earthing arrangement with earthing strips of adequate size (as per IEEE Std 80-2013 to protect operating staff against any hazardous touch voltages and electro-magnetic interferences) as per the technical specification.</p>	Set	2				
2.4	<p>145kV, 2000A, 40kA for 3 sec (Busbars, Disconnector, Grounding switch &amp; bus PT), 1 Phase Isolated Bus-PT Bay Module comprising of SF6 gas insulated metal enclosed busbars each enclosed in bus enclosures running along the length of the switchgear to interconnect each of circuit breaker bay module. Each busbar set shall be complete with Single phase bus Potential Transformer (4 winding) (3 Nos), Motorised 3 Phase Disconnector (1 No), Motorised Busbar safety Grounding switch (1 No), Busbars, Local Control Cubicle, SF6 gas monitoring system PD sensor [adequate number of UHF sensors in the offered GIS equipment(1 no in each gas compartment) for detection of Partial discharge (of 5 pC and above) as per IEC 60270 through Partial Discharge (PD) monitoring system], different gas compartment, O-ring &amp; gaskets, Nuts, Bolts &amp; Washers for Outdoor use, Absorbent, Limit Switch, SF6 Gas, etc. to complete the bus &amp; its earthing arrangement with earthing strips of adequate size (as per IEEE Std 80-2013 to protect operating staff against any hazardous touch voltages and electro-magnetic interferences) as per the technical specification.</p>	Set	1				

2.5	145kV, 2000A, 40kA for 3 sec (Busbars, CB, Disconnecter, Grounding switch & CT), SF6 gas insulated <b>Bus Coupler Bay Module</b> comprising of SF6 gas insulated Single Pole Circuit Breaker (1 Set), Single Phase Current Transformer (6 Nos), Motorised 3 Phase Disconnecter (2 Nos), Motorised safety Grounding switch (2 Nos), Busbars, Local Control Cubicle, SF6 gas monitoring system, PD sensor [adequate number of UHF sensors in the offered GIS equipment(1 no in each gas compartment) for detection of Partial discharge (of 5 pC and above) as per IEC 60270 through Partial Discharge (PD) monitoring system], different gas compartment, O-ring & gaskets, Nuts, Bolts & Washers for Outdoor use, Absorbent, Limit Switch, SF6 Gas, etc. to complete Bus Coupler Bay Module & its earthing arrangement with earthing strips of adequate size (as per IEEE Std 80-2013 to protect operating staff against any hazardous touch voltages and electro-magnetic interferences) as per the technical specification.	Set	1				
2.6	145kV, 2000A, 40 kA, 3 sec, single or three phase, SF6 gas Insulated Bus Duct outside GIS Bay along with associated Support structure arrangement bends, joints, accessories, & its earthing arrangement with earthing strips of adequate size (as per IEEE Std 80-2013 to protect operating staff against any hazardous touch voltages and electro-magnetic interferences) as per the technical specification. (In the case of 3 phase busduct, the upper column shall be used. In the case of 1 phase busduct, the lower column shall be used.)	RM	170				
2.7	145kV, 2000A, 40kA SF6/Air BUSHING (Bushing shall be of Polymer / composite insulator type and shall be seamless sheath of a silicone rubber compound. The hollow silicone composite insulators shall comply as per IEC 61462 and IEC 62217. The design of the composite insulators shall be tested and verified according to IEC 61462) for connecting GIS to AIS along with support structure.	No	12				
2.8	Portable Partial Discharge Monitoring System (PDM): 245kV and 145kV system shall have Portable Partial Discharge Monitoring System (PDM) & shall be capable for measuring PD in charged GIS environment, bandwidth in order of 100MHz–2GHz & provision to select a wide range of intermediate bandwidths and the principle of operation shall be based on UHF principle of detection. The Detection and measurement of PD and bouncing particles having in built large coloured LCD for displaying and storing facility in the instrument for further analysis to locate actual source of PD such as free conducting particles, floating components, voids in spacers, particle on spacer surfaces etc.	SET	1				
2.9	132 KV XLPE Cable 1000 Sq Mm ( 1000 Amps Single Core ) for 132 KV connectivity from GIS equipment to Auto Transformer & Power Transformer	MTR	1200				
2.10	132 KV Cable termination kit outdoor for 132 KV Transformers suitable for 1CX1000 Sqmm copper cable.	Nos	6				
2.11	132KV Cable termination kits (Outdoor GIS side) suitable for 1CX <b>1000 sq. mm</b> Copper Cable	Nos	6				

<b>3</b>	<b>2000A, 31.5kA for 3s, Double Busbar Circuit Breaker (Circuit breaker shall be E2-C2-M2 class as per IEC 62271-100) arrangement. 36kV INDOOR GIS EQUIPMENT as per latest IEC standard &amp; type tested equipment as per technical specification, with open future proof &amp; flexible system in line with IEC 61850 &amp; IEC 62271-200.</b>						
<b>3.1</b>	36kV, 2000A, 31.5kA for 3 sec (CB, Disconnecter, Grounding Switch & CT), SF6 gas insulated <b>Transformer Bay Module</b> each comprising of SF6 gas insulated Vacuum Circuit Breaker (1 Set), Single Phase Current Transformer (3 Nos), Motorised Busbar 3 Phase Disconnecter (2 Nos), Motorised Disconnecter (1 No), Motorised safety Grounding switch (3 Nos), Busbars rated 2000A, Local Control Panel, SF6 gas monitoring system for complete bay, etc. to complete Transformer Bay Module suitable cable connection as per the technical specification.	Set	<b>2</b>				
<b>3.2</b>	36kV, 1250A, 31.5kA for 3 sec (CB, Disconnecter, Grounding Switch & CT), SF6 gas insulated Outgoing Feeder Bay Module each comprising of SF6 gas insulated Vacuum Circuit Breaker (1 Set), Single Phase Current Transformer (3 Nos), Motorised Busbar 3 Phase Disconnecter (2 Nos), Motorised Disconnecter (1 No), Motorised safety Grounding switch (3 Nos), Busbars rated 2000A, Local Control Panel, SF6 gas monitoring system for complete bay, etc. to complete Outgoing Feeder Bay Module suitable cable connection as per the technical specification.	Set	<b>5</b>				
<b>3.3</b>	36kV, 1250A, 31.5kA for 3 sec (Disconnecter, Grounding switch & bus PT), 1 Phase Isolated Bus-PT Bay Module comprising of SF6 gas insulated metal enclosed busbars rated 2000A each enclosed in bus enclosures running along the length of the switchgear to interconnect each of circuit breaker bay module. Each busbar set shall be complete with Single phase bus Potential Transformer (4 winding) (3 Nos), Motorised 3 Phase Disconnecter (1 No) , Motorised Busbar safety Grounding switch (1 No), SF6 gas monitoring system for complete bus system, etc. as per the technical specification.	Set	<b>1</b>				
<b>3.4</b>	36kV, 2000A, 31.5kA for 3 sec (Busbars, CB, Disconnecter, Grounding switch & CT), SF6 gas insulated Bus Coupler Bay Module comprising of SF6 gas insulated Vacuum Circuit Breaker (1 Set), Single Phase Current Transformer (6 Nos), Motorised 3 Phase Disconnecter (2 Nos), Motorised safety Grounding switch (2 Nos), Local Control Panel, SF6 gas monitoring system for complete bay, etc. to complete Bus Coupler Bay Module as per the technical specification.	Set	<b>1</b>				
<b>3.5</b>	<b>33KV EHV POWER CABLES, AL CORRUGATED XLPE CABLES</b>						
<b>3.5.1</b>	33KV CABLE 630 SQ. MM (800 AMPS SINGLE CORE) (for 33 KV connectivity from GI equipment to Power Transformer)	Mtes	<b>1200</b>				
<b>3.5.2</b>	33 KV Cable termination kit indoor for 33 KV Transformers suitable for 1CX630 Sqmm copper cable.	No.s	<b>6</b>				
<b>3.5.3</b>	33 KV Cable termination kit outdoor for 33 KV Transformers suitable for 1CX630 Sqmm copper cable.	No.s	<b>6</b>				

3.5.4	33KV CABLE 300 SQ. MM (400 AMPS SINGLE CORE) (for 33 KV connectivity from GI equipment to Station Transformer & outgoing feeders upto DP structure end)	Mtes	2500				
3.5.4	33 KV Cable termination kit indoor for 33 KV suitable for 1CX300 Sqmm copper cable.	No.s	21				
3.5.5	33 KV Cable termination kit outdoor for 33 KV suitable for 1CX300 Sqmm copper cable.	No.s	21				
3.5.6	All types of HARDWARES & FITTINGS/SPACERS/CLAMPS & CONNECTORS FOR 220KV SIDE OF THE GIS S/S.	LOT	1				
3.5.7	All types of HARDWARES & FITTINGS/SPACERS/CLAMPS & CONNECTORS FOR 132 & 33 KV SIDE OF THE GIS S/S.	LOT	1				
4	<b>220 KV, 132 KV, 33 KV Equipments Required for line incoming &amp; OUTGOING</b>						
4.1	245 KV, 2000A, 40KA, ISOLATORS WITH SINGLE EARTH SWITCH	NOS	4				
4.2	245KV 1 phase Solid core bus post insulator (AIS) as per technical specification.	NOS	6				
5	216KV metal oxide surge arrester, 10KA Long duration discharge class III , 10 KJ/KV at 216KV as per technical specification.	NOS	18				
6	145 KV ,1250A, 31.5 KA S/I WITH SINGLE EARTH SWITCH	NOS	2				
7	120 KV METAL OXIDE SURGE ARRESTOR, 10 KA, Class III	NOS	18				
8	30 KV, METAL OXIDE SURGE ARRESTOR, 10kA, Long duration discharge class III (AIS) as per technical specification.	NOS	27				
8	36 KV Bus Post Insulator as per technical specification	NOS	15				
9	<b>BUS BAR &amp; CIRCUIT MATERIALS</b>						
9.1	BUS STRINGING, JUMPERING						
10	<b>Bus stringing ACSR Moose Single</b>	Mtrs	500				
11	<b>Jumpering to Equipments</b>	Mtrs	1000				

12	SUBSTATION EARTHING SYSTEMS: Substation earth mat Design, engineering, supply(except the GI Flats, only erection) inclusive of corrosion protection measures if any,laying of earth mat conductors of Hot dip galvanised flats of size 75X10 mm to the approval of Engineer in charge, excavation, welding/jointing of ground conductors along with risers (a) upto Finished level from the mat size 75X10 mm & b) from the finished ground level to the top of the structure and equipment shall be with 50X6 mm GI Flats, with back filling and good compaction,grounding driven rods(40 mm MS solid rod for untreated earth pit ,perforated 50 mm Heavy duty GI pipes for treated earth pits (with details of treatment as per IS). The spacing between the earth conductor not more than 5 mtrs(both way) and to be buried at depth of 700mm from the finished ground level. For provision of treated earth pit and untreated earth pit, refer the specification for designing. Provision of water taps inside the switch yard areas and peripheral treated and un-treated earth pit are required to be provided for watering the treated earth pits. The no. of treated and un treated earth pits are to be done as per the practice and as indicated in the drawing for different equipments. This is as per approved drawing and specification.						
12.1	EARTHING CONDUCTOR FOR BURRIAL : 75X10 mm GI Flat for laying (spacing maximum 5m both way) = 8 km APPX	Mtrs	8000				
12.2	EARTHING CONDUCTOR: 50X6mm GI (HDG) Flat for Raiser for console box,LT panels,DC panels,Marshalling boxes,equipments Structures etc)	Mtrs	15700				
13	EARTHING DEVICE & ASSOCIATED ACCESSORIES (50 mm heavy duty GI PERFORATED PIPE 3 mtrs long for treated earth pit)	Nos	50				
13.1	EARTHING DEVICE & ASSOCIATED ACCESSORIES 40mm MS rod 3 mtrs long for non treated earth pit)	Nos	50				
13.2	G.I Cable Trays including support GI angle suitable for different sections along with its accessories as per TS. Details of No. of tiers are indicated in the TS-Civil Section accordingly the requirement can be ascertained.						
14	G.I Cable Trays(size: 450x75x2500mm)	MTRS	1000				
14.1	G.I Cable Trays(size: 300x75x2500mm)	MTRS	1000				
14.2	G.I Cable Trays(size: 150x75x2500mm)	MTRS	1000				
15	SUB STATION SWITCHYARD BMK,AC CONSOLE & OTHER MARSHALLING BOXES						
15.1	BAY MARSHALLING KIOSK (02 Nos. in 220 KV Side,01 Nos. in 132 KV Bay Side, 01 Nos. in 33KV Side )	NOS	4				
15.2	SWITCH YARD AC CONSOLE FOR LIGHTING (01 Nos. in 220 KV bay, 01 No. in 132 kv Bay )	NOS	2				

15.3	SWITCH YARD RECEPTACLE BOARD FOR TFR OIL FILTERATION (01 No. near each 220/132 Auto Transformers, and 01 no. near power transformer )	NOS	3				
15.4	SWITCH YARD RECEPTACLE BOARD FOR WELDING & OTHER EMERGENCY (01 No.)	NOS	1				
16	<b>HDG SWITCH YARD STRUCTURES (INCLUDING FOUNDATION BOLTS) FOR 220KV &amp;132KV CLASS</b>						
16.1	<b>DIFFERENT TYPES OF LATICE TYPE COLUMNS &amp; DIFFERENT TYPE OF BEAMS AND LIGHTING CUM</b>						
16.1.1	TOTAL WEIGHT OF COLUMN & BEAM	MT	33.34				
16.1.2	DIFFERENT TYPE OF SUPPORT STRUCTURES LATICE TYPE FOR ALL 220KV,132KV & 33 KV EQUIPMENT INCLUDING HIGH LEVEL SA NEAR TRANSFORMER.	MT	14.69				
16.2	Erection including foundation for 40 Mtrs heigh Monopole (HDG) Lighting cum Lightning Mast including LED lighting fixtures (240 watts each minimum 8 Nos.) with control gear panel etc suitable for wind zone-VI, with all other accessories like motor for hoisting/lowering the lighting platform & other switchgear and lighting control panel including required cable(copper) & other accessories etc.	SET	2				
17	Laying of Power and Control Cable including fixing of cable with terminal connections both at equipments and control panels with supply of and fixing of lugs, Ferrules, clamps, connectors, glands, fixing of cable trays, including supply of N&B, Link plates, Cable Markers, Plaster of Paris, M-Seal compounds etc for sealing purpose and all necessary arrangements, laying of Earthing Flats, earthing ,laying of Cable trench slabs and chequered plate etc for the cable trench,Cable scheduled and cable diagram to be prepared by the contractor						
17.1	POWER CABLES,1.1KV,XLPE & PVC FRLS ,FLAT STRIP ARMOURED, ALUMINIUM CONDUCTOR (As per Specification)						
17.1.1	XLPE-1CX 300 mm2	Mtrs	1000				
17.1.2	XLPE-3.5 CX185 mm2	Mtrs	1000				
17.1.3	XLPE-3.5 CX120 mm2	Mtrs	1000				
17.1.4	PVC-3.5 CX70 mm2	Mtrs	1200				
17.1.5	PVC-3.5 CX35 mm2	Mtrs	3200				
17.1.6	PVC-4 CX 16 mm2	Mtrs	2200				
17.1.7	PVC-4 CX 6 mm2	Mtrs	5000				
17.1.8	PVC-2CX 6 mm2	Mtrs	5000				
17.2	CONTROL CABLES,1.1 KV,PVC FRLS , COPPER STRANDED ARMOURED STRANDED(As per specification).						
17.2.1	2 CX 2.5 mm2	Mtrs	8000				

17.2.2	4 CX 2.5 mm2	Mtrs	15000				
17.2.3	5 CX 2.5 mm2	Mtrs	7500				
17.2.4	7CX 2.5 mm2	Mtrs	8500				
17.2.5	10 CX 2.5 mm2	Mtrs	15000				
17.2.6	12 CX 2.5 mm2	Mtrs	14500				
17.2.7	16 CX 2.5 mm2	Mtrs	7000				
17.2.8	19 CX 2.5 mm2	Mtrs	3000				
17.2.9	1CX 120 mm2 BAT TO BAT CHARGER & CHARGER TO DCDB	Mtrs	1200				
17.3	HARD CONDUIT INCLUDING of adequate tensile strength minimum 7kg/sqmm or better & ITS ACCESSORIES LIKE ALL TYPE OF SOCKETS & BENDS FOR TAKING CABLE FROM TRENCH TO EQUIPMENT MB etc	LOT	1				
18	<b>ACCESSORIES FOR PLCC SYSTEM With OPGW cable</b>						
18.1	48 Fibre Optic Approach cable along with HDPE Pipes	KM	0.50				
18.2	Optical line Terminal Equipment(OLTE) -STM4 type SDH equipment with integrated MUX & tributary cards for speech & data ports for interfacing of Speech & data which should be compatible with existing OPTCL system	No	1				
18.3	Digital Teleprotection Equipment and accessories to be suitable for interfacing with SDHMUX	No	1				
18.4	Supply of FODP(Fibre Optic Distribution Panel)48 F: Indoor type,rack mounted with FCPC coupling and pig tails(DWSm Fibre)	No	1				
18.5	48 V, 300 AH, maintenance free VRLA Battery set.	Set	1				
18.6	SMPS based Battery Charger of 75A suitable for 48V VRLA Battery set	No	1				
18.7	2.5 sq. mm muti strand 2 core control cable(power supply,Transducer/MFT PT supply)	Metre	300				
18.8	2.5 sq. mm multi strand 4 core control cable(Transducer/MFT CT supply)	Metre	300				
18.9	1.5 sq. mm multi strand 10 core control cable(Digital Input)	Metre	200				
18.10	10 sq. mm 2 core multi strand control cable(Battery)	Metre	100				
18.11	48V DCDB,	Set	1				
18.12	Earth Flat, Cable Tray, Telephone cable, Foundation rail, Junction Box,.	Set	1				
19	<b>ERECTION OF STATION TRANSFORMER &amp; OTHER MATERIALS FOR MEETING THE AUXILIARY SUPPLY OF THE SUB-STATION AS PER TECHNICAL SPECIFICATION</b>						
19.1	STATION TRANSFORMER 33KV/0.43 V,500 KVA (Confirming to Energy Efficiency Level 2 -AS PER SPECIFICATION & relevant IS)	NOS	2				



19.2	<p><b>One no. 4 pole structure (HDG Type) alongwith other equipment &amp; materials for two nos station transformers:</b></p> <p>1.4 Pole structure (using 200X100 mm RS Joist)</p> <p>2. Channel &amp; Angle FOR BRACING OF, CHANNEL for the SA &amp; Isolator &amp; HG fuse etc.</p> <p>3. 90 KN Disc/composite long rod Insulators for 33 KV (48 nos./12 sets) for bus, Bus stringing using ACSR moose conductor &amp; tension hardwares,other clamps &amp; connectors etc as per requirement.</p> <p>4. 2sets of 33 KV Isolator (800 AMP) for 33 KV side of station trafo.</p> <p>5. 2sets of 33 KV HG FUSE.</p> <p>6. 100 Sq mm AAAC conductor suitable for connection between HG fuse &amp; station transformer bushing.</p> <p>7. 2 sets of LT OUT DOOR KIOSK MADE OUT OF 3mm CRCA sheet GI MARSHALLING BOX suitable for outdoor mounting. The bus bar suitable for 1000 AMP shall be arranged in the out door kiosk and other Facility like two sets of 400 Amps MCCB for incoming &amp; outgoing with required sizes of terminal studs for power cable termination &amp; any other accessories required.</p> <p>All materials shall be As per relevant latest IS &amp; as per the direction of Engg. in charge</p>	SETS	2				
20	SUB STATION LIGHTING (AS PER SPECIFICATION AND APPROVED DRAWINGS )(Switch yard and other street area)(Including provision of the fittings on the LM)						
20.1	<p><b>SUB-STATION SWITCH YARD LIGHTING :</b> IT INCLUDES SUPPLY OF FIXTURES &amp; LAMPS (LED) of reputed make (Philips/CGL/Bajaj/other approved make of OPTCL) with switch gear,GI Conduit etc.(Lighting fixtures are to be fixed rigidly on the Column at a suitable height so that the required lux can be achieved).(150 watt each). (* REMARKS : FOR SUPPLY OF ALL THE CABLES AS INDICATED ARE COVERED IN THE CABLE ITEMS AS INDICATED ABOVE )</p>	SET	60				
20.2	<p><b>STREET LIGHTING:</b> GI Tubular Pole: (410-SP-24: IS 2713-Part-II-1980 or latest) Length of pole 8.5 mtrs(minimum weight 158 Kgs). &amp; LED light fittings etc.</p> <p>(ALL THE STREET LIGHT POLE SHALL BE OF GI TUBULAR POLE AND PROVISION OF A GI JUNCTION BOX WITH SUITABLE COVERS AT A HEIGHT OF 1 METRE FROM THE GROUND. THE JUNCTION BOX SHALL HAVE PROVISION OF FUSES, BUSES, CONNECTORS FOR CABLE IN AND OUT. ( IT INCLUDES SUPPLY OF LED LIGHTING FIXTURES WITH LAMPS of 100 Watts of reputed make (Philips/CGL/Bajaj/other approved make of OPTCL) &amp; as per technical specification. (* REMARKS : FOR SUPPLY OF ALL THE CABLES AS INDICATED ARE COVERED IN THE CABLE ITEMS AS INDICATED ABOVE )</p>	SET	25				

20.3	<b>OUTDOOR KIOSK (HDG type) FOR STREET LIGHTING PURPOSE</b> HAVING 2 NOS 200 AMP SWITCH FUSE UNITS AND , 6 NOS.OUT LETS OF 32 AMP MCB FOR STREET LIGHTING. (SUITABLE FOR XLPE CABLES(3.5 CORE 120 SQMM) FROM MAIN ACDB FROM CONTROL ROOM TO THE OUT DOOR KIOSK. XLPE CABLE OF 4C X 16 SQMM FROM OUTDOOR KIOSK TO THE STREET LIGHT POLES AND 4CX6 SQMM FROM POLE TO POLE AND 2CX6 SQMM FROM POLE TO LIGHTING FIXTURES. > 1 NO. OUTDOOR KIOSK FOR COLONY SUPPLY PURPOSE HAVING (* REMARKS : FOR SUPPLY OF ALL THE CABLES AS INDICATED ARE COVERED IN THE CABLE ITEMS AS INDICATED ABOVE )	SET	2				
21	2 TR CAPACITY SPLIT AIR CONDITIONING UNITS (Dual Inverter, five star type latest model) with copper condensor having remote temperature & operation control facility with required voltage stabiliser. Receptical indoor Control Board having suitable outgoing (one outgoing for one AC & with overload control gear) & wiring materials with 32 amp socket & plug for each unit of AC etc to complete (AS PER SPECIFICATION) FOR CONTROL ROOM, CARRIER ROOM & CONFERENCE ROOM.,OFFICE ROOM etc which includes all type of cables & wires and a main control switch gear kiosk having sufficient outlet for each air conditioner unit.	LOT	1				
22	FIRE FIGHTING SYSTEM(PORTABLE /TROLLEY/ WHEEL MOUNTEDFIRE EXTINGUISHERS SETS FOR CONTROL ROOM,EQUIPMENT LIKE TRANSFORMER AND OTHER AREAS AS PER TECH SPEC(REFER TS-VOL-IIA-SCOPE OF WORKAT SL NO. 15-ANNEXURE - I)						
22.1	FOAM TYPE-9 LTRS	NOS	5				
22.2	DRY CHEMICAL POWDER(TROLLEY MOUNTED)- 22.5 KGS	NOS	6				
22.3	DRY POWDER TYPE - 5 KGS	NOS	6				
22.4	CO2 - 4.5 KGS	NOS	6				
22.5	CO2 - 9 KGS	NOS	6				
22.6	CO2 (TROLLY MOUNTED)- 22.5 KGS	NOS	4				
22.7	9 litre water type	Nos.	4				
22.8	50 Litres Mechanical Foam type	Nos.	2				
22.9	FIRE BUCKET (6 NOS IN EACH STAND) WITH STAND	SET	5				

23	<p><b>SUBSTATION AUTOMATION SYSTEM</b> FOR 220/132/33 KV SUBSTATION ON PRP MODE: Design , engineering , drawing, supervision, installation , testing &amp; commissioning of Substation Automation system alongwith Supply of the following 220, 132 and 33 kV level of protection panels consisting of Bay control Units &amp; numerical protection relays and other auxiliary relays suitable for SAS as per technical specification.</p> <p><b>(220KV side: COMPRISING OF 04 Nos. FEEDER BAYS + 02 TRANSFORMER BAYS + 01 Nos BUS COUPLER BAY, 132 KV side: COMPRISING OF 02 Nos. FEEDER SAYS + 04 Nos TRANSFORMER BAYS(auto &amp; power trf.) + 01 No. BUS COUPLER BAY) &amp; 33 KV side: COMPRISING OF 02 Nos. FEEDER SAYS + 05 Nos TRANSFORMER BAYS + 01 No. BUS COUPLER BAY)</b></p> <p><b>NOTE:</b> All protective relays &amp; BCU shall be numerical type.</p>						
23.1	Yard AC Kiosk :6000 mm (L)x5000mm (W)x 4500mm (H) with AC, <b>as per the Specification;</b>	Nos.	3				
23.2	Gate way panel for Sub-Station Automation (in PRP as per the specification & indicative drg ) system (for All 220, 132 & 33 KV side bays including the future bays),other accessories (comprising servers,	SET	1				
23.3	<b>BCU for Substation Auxilliary</b> System (Datas for monitoring of Station AC, Station DC, Lighting, Fire fighting, Air conditioning, Diesel generator	SET	1				
23.4	GPS System with PTP, IRIG-B, SNTP	SET	1				
23.2	<b>220 KV SIDE PROTECTION &amp; OTHER PANELS</b>						
23.2.1	<b>FEEDER PROTECTION PANEL</b> (MAIN-I , MAIN-II & BACK-UP PROTECTION WITH AUTO RECLOSURE DISTANCE PROTECTION with Bay control unit (BCU) with all other relays & component required for complete prtecton,control etc as per TS and also suitable for substation automation system.	NOS	4				
23.2.2	<b>TRANSFORMER PROTECTION PANEL</b> (DIFFERENTIAL I , REF I & BACK-UP PROTECTION & BCU for 220 KV side) & (Bay control unit-BCU andBACK-UP PROTECTION for 132 KV side) CONSIDERING HV & LV side of 220/132 KV, 160 MVA Auto transformer with all other relays & component required for complete prtecton,control etc as per TS and also suitable for substation automation system.	NOS	2				
23.2.3	<b>BUS COUPLER PROTECTION PANEL</b> with Bay control unit (BCU) & Back-up protection relay with with all other relays & component required for complete prtecton,control etc as per TS and also suitable for substation automation system.	NOS	1				
23.2.4	<b>BUS-BAR PROTECTION PANEL</b> ( Provision of bus bar modules for the future bays(two nos) and with with all other relays & component	SET	1				
23.3	<b>132 KV SIDE PROTECTION PANELS</b>						
23.3.1	<b>FEEDER PROTECTION PANEL</b> (MAIN-I & BACK-UP PROTECTION DISTANCE PROTECTION with Bay control unit	NOS	2				

23.3.2	TRANSFORMER PROTECTION PANEL (DIFFERENTIAL,REF & BACK-UP ,PROTECTION CONSIDERING HV side for 40 MVA 132/33 KV Power Transformer) with Bay control unit (BCU) for substation automation system.	NOS	2				
23.3.3	BUS COUPLER PROTECTION PANEL with Bay control unit (BCU) for substation automation system.	NOS	1				
<b>23.4</b>	<b>33 KV SIDE PROTECTION PANEL</b>						
23.4.1	FEEDER PROTECTION PANEL with Bay control & protection unit (BCPU) along with additional BACK-UP PROTECTION for substation automation system for 33KV feeders [ 2nos. Feeder bays in one panel].	SET	3				
23.4.2	TRANSFORMER PROTECTION PANEL (REF & BACK-UP ,PROTECTION CONSIDERING LV side for 2x40 MVA 132/33 KV Power Transformer) with Bay control & protection unit (BCPU) for	SET	1				
23.4.3	STATION TRANSFORMER PROTECTION PANEL(2X 33/0.43 KV, 250 KVA) with Bay control & protection unit (BCPU) for substation	NOS	1				
23.4.4	BUS COUPLER PROTECTION PANEL with Bay control & protection unit (BCPU) for substation automation system.	NOS	1				
<b>24</b>	<b>AC &amp; DC SYSTEM</b>						
<b>24.1</b>	<b>AC SYSTEM</b>						
24.1.1	MAIN AC DB,(HAVING A 1600 A,50KA,DRAWOUT TYPE ACB WITH 3 O/C,E/F,U/V RELAYING FACILITY and MECH& ELECT INTERLOCK FACILITY CONSIDERING Main-1,2 & DG INDOOR TYPE AS PER SPECIFICATION.(MAIN DB-1,MAIN DB-2 WITH B/C & PROVISION FOR D.G INCOMING)	SET	1				
24.1.2	ACDB (HAVING 800A MCCB) AS PER SPECIFICATION (AC DB-1,AC DB-2 WITH B/C)	SET	1				
24.1.3	MAIN LIGHTING DISTRIBUTION BOARD (HAVING 250A MCCB AS INCOMER)AS PER SPECIFICATION (WITH DB-1,DB-2 & B/C)	SET	1				
24.1.4	INDOOR LIGHTING DISTRIBUTION BOARD AS PER SPECIFICATION. (WITH DB-1,DB-2 & B/C)	SET	1				
24.1.5	EMERGENCY LIGHTING DISTRIBUTION BOARD	SET	1				
24.1.6	INDOOR RECEPTACLE BOARD	SET	1				
<b>24.2</b>	<b>DC SYSTEM</b>						
24.2.1	220 V DC BOARD (HAVING 100A DC MCCB AS INCOMER, E/F (EARTH LEAKAGE), UNDER & OVER VOLTAGE AS PER SPECIFICATION (DC DB-1,DC DB-2 & B/C). Consider separate source(DC1 & DC 2) to each panels & accordingly sufficient nos. of DC output from DB-1 & 2 to be considered.	SET	2				
24.2.2	220 V DC EMERGENCY DISTRIBUTION BOARD	SET	1				
24.2.3	BATTERY (645 AH PLANTE TYPE) for 220 V DC	SET	2				

24.2.4	BATTERY CHARGER FOR 645 AH, 220 V DC (FLOAT & FLOAT CUM BOOST) (including provision of series dropper diodes with heat sinks & other protection facility at the DC Load terminal end in order to feed 220 V to the load).	SET	2				
25	DE MINERALISED PLANT of 30 L/Hr FOR MAKING DISTILLED WATER FOR BATTERY BANKS	SET	1				
26	PORTABLE ALUMINIUM LADDER EXTENDABLE TYPE OF ADEQUATE HEIGHT TO BE USED FOR MAINTENANCE OF EQUIPMENT INSIDE SWITCH YARD.(REFER TS-VOL-IIA-SCOPE OF WORKAT SL NO. 19)	NOS	2				
27	CARTWHEEL MOUNTED ALUMINIUM LADDER OF ADEQUATE HEIGHT TO BE USED FOR MAINTENANCE OF EQUIPMENT .	NOS	1				
28	WATER COOLER WITH WATER PURIFIER (with R.O & ultra violet purification system of ISI mark) SYSTEM	NOS	2				
29	MAINTENANCE & TESTING EQUIPMENT (REFER TS-VOL-IIA-16. Maintenance & Testing Equipment (ANNEXURE-II & ANNEXURE-III) INDICATED IN -SCHEDULE OF REQUIREMENTS OF MAINTENANCE EQUIPMENT).	LOT	1				
30	OFFICE FURNITURE (REFER TS-VOL-IIA-SCOPE OF WORKAT SL NO. 18 ANNEXURE - IV ,INDICATED IN SCHEDULE OF REQUIREMENTS OFFICE FURNITURE) & PLACING IN CONTROL ROOM,CONFERENCE ROOM,OFFICE ROOMS,LIBRARY,TESTING LAB,etc.	LOT	1				
31	BEST QUALITY &APPROVED MAKE INSULATING MAT (Confirming to IS:15652:2006) TO BE KEPT INFRONT OF ALL PANELS,BOARDS ETC.(2000X1000X3)mm Size	Nos	50				
32	250 KVA outdoor type silent Generator with contro panel having adequate mechanical & electrical protection as per latest IS with Automatic Mains Failure feature as per Technical spec.	NOS	1				

33	ERECTION OF THE TRANSFORMERS AND ITS ACCESSORIES ON THE PLINTH AND PLACING IN POSITION, ERECTION OF ACCESSORIES OF THE TRANSFORMERS, EART-HING AS PER STANDARD(INCLUDING SUPPLY OF MATERIALS),VACUUM TREATMENT OF THE TANK AND WINDING,OIL FILTRATION(INCLUDING SUPPLY OF VACUUM CUM OIL FILTER MACHINE),SUPPLY & LAYING OF ALL TYPES OF CONTROL & POWER CABLES PERTAINING TO TRANSFORMERS ,TESTING AND COMMISSIONING INCLUDING ALL TESTS OF THE OILS AS PER STIPULATION IN THE STANDARD APPROVED TESTING LABORATORY AND AS PER THE INSTRUCTION OF THE ENGINEER IN CHARGE.THIS INCLUDE ALL RELATED WORKS FOR ERECTION,TESTING AND COMMISSIONING OF THE POWER TRANSFORMERS.(CONTRACTOR TO ARRANGE POWER SUPPLY FOR FILTRATION AND VACUUM TREATMENT WORKS).IT ALSO INCLUDES SUPPLY OF ALL MATERIALS FOR ERECTION INCLUDING T&P's.						
33.1	220/132KV, 160 MVA AUTO TRANSFORMER	Nos	2				
33.2	40 MVA, 132/33kV Power Transformer	Nos	2				
34	FIRE FIGHTING EQUIPMENT: (Main Pump, Jockey Pump, DG Set cum Pump, Control Panel for Fire Fighting System (HIGH PRESSURE : Hydrant and Mulsifire system) to take care of 2 Nos 160 MVA ICT, Power Transformer, switcyard equipment and buildings. HVW system & hydrant sytsem, complete with all piping, valves, fittings etc inside pump house for Fire protection sytem of substation) as per the technical spec.	LOT	1				
35	Hydrant sytsem, complete U/G piping of different sizes,vaves and accessories etc outside the Pump House for Fire protection sytem of 2 Nos 160 MVA Aoto transformers, Power transformers, switcyard equipment and buildings as per the technical spec.	LOT	1				
<b>TOTAL OF ELECTRICAL WORKS (PART-B)</b>							
<b>TOTAL OF ERECTION OF SUBSTATION (Electrical Work), (Civil Work) &amp; Other Serviced-Schedule-4-ss (to Schedule No. 6 Grand Summary)</b>							
1 Specify currency in accordance with specifications in Bid Data Sheet under ITB 19.1 in Single-Stage Bid, or ITB 34.1 in Two-							

**ODISHA POWER TRANSMISSION CORPORATION LIMITED**

**NAME OF THE WORK:-Design, Supply and Installation of 2X160MVA Auto Transformer & 2X40 MVA Power Transformer,for 220/132/33 KV Out Door Type GIS Grid Sub-station at ,Kuakhia in Odisha State of India under PACKAGE-3A Under Japan International Cooperation Agency (JICA)'s ODA Loan.**

**Loan Agreement No: [ID-P245] - FB No: [CPC/JICA/ICB/03A /19-20]- Reference Identification No: [OPTCL/JICA/PKG-3]**

**Schedule No. 6. Grand Summary**

NAME OF THE BIDDER		Total Price <sup>1</sup>	
Item	Description	Foreign	Local
1	Total Schedule No. 1. Plant, Supplied from Abroad (Substation)		
2	Total Schedule No. 2. Plant, Supplied from Within the Employer's Country (substation)		
3	Total Schedule No. 3. Design Services (Not Applicable)		
4	Total Schedule No. 4. Installation and Other Services (substation)		
5	Total Schedule No. 5. Provisional Sums (Not to be considered for Evaluation)		
Total( to Bid Form)			

Name of Bidder: \_\_\_\_\_

Signature of Bidder: \_\_\_\_\_

<sup>1</sup> Specify currency in accordance with specifications in Bid Data Sheet under ITB 19.1 in Single-Stage Bidding, or ITB 34.1 in Two-Stage Bidding. Create and use as many columns for Foreign





**ODISHA POWER TRANSMISSION CORPORATION LIMITED**

**NAME OF THE WORK:-Design, Supply and Installation of 2X160MVA Auto Transformer & 2X40 MVA Power Transformer,for 220/132/33 KV Out Door Type GIS Grid Sub-station at ,Kuakhia in Odisha State of India under PACKAGE-3A Under Japan International Cooperation Agency (JICA)'s ODA Loan.**

**Loan Agreement No: [ID-P245] - FB No: [CPC/JICA/ICB/03A/19-20]- Reference Identification No: [OPTCL/JICA/PKG-3]**

**Schedule No. 8. Details of Taxes & Duties**

**NAME OF THE BIDDER**

Sl No	Description of Applicable Tax/Levy		Tax @ __%	Total Amount of Taxes /Duty/ Levies
<b>1</b>	Details of Taxes and levies on the direct / bought out transactions between Bidder and ODISHA POWER TRANSMISSION CORPORATION LTD included in the Bid			
(i)	TOTAL IGST			
(ii)	TOTAL CGST			
(III)	TOTAL OGST			
(iv)	TOTAL Any other tax			
	TOTAL OF TAXES AND DUTIES [Sum (i) to (iv)]			
<b>2</b>	Details of Taxes and levies on the direct / bought out transactions between Bidder and ODISHA POWER TRANSMISSION CORPORATION LTD included in the Bid Price above but as may be payable by ODISHA POWER TRANSMISSION CORPORATION LTD (Schedule- 4)			
(i)	TOTAL IGST			
(ii)	TOTAL CGST			
(III)	TOTAL OGST			
(iv)	TOTAL Any other tax			
	TOTAL OF TAXES AND DUTIES [Sum (i) to (iv)]			
<b>4</b>	<b>F. Total Bid Price: (including Taxes &amp; Duties and other</b>			

Name of Bidder:\_\_\_\_\_

Signature of Bidder:\_\_\_\_\_