


ଓଡିଶା ବିଦ୍ୟୁତ ଶକ୍ତି ସଂଚାରଣ ନିଗମ ଲିଡ.
ODISHA POWER TRANSMISSION CORPORATION LIMITED



(A Government of Odisha Undertaking)

CIN: U40102OR2004SGC007553

Office of the Deputy General Manager (Electrical)
E.H.T. (O&M) Division, Laltikra, Bolangir – 767002,

E-Mail: ehtm.div.blm@optcl.co.in .

ANNEXURE – I

TENDER CALL NOTICE-07/2021-22

Sealed Tenders in Double copy of tender papers in single envelope are invited by the undersigned from Electrical contractor having valid HT/EHT License with 3 years Civil work experience in any HV/EHV S/S(33Kv & above) having Valid PAN card, G.S.T certificate & Contractor License for 'Repair of earth Retaining wall inside 132/33Kv Grid s/s,Laltikra, Bolangir' .

Sl No	Description of work	Total cost of work including GST.	EMD Cost Rs.	Tender Paper Cost Rs.
1	Repair of earth Retaining wall inside 132/33Kv Grid s/s,Laltikra, Bolangir	Rs.6,34,334.00	NIL	Rs.4000.00+12 %GST=Rs.4480.00(Non Refundable)

The tender document can be made available in the office of the undersigned on payment of requisite amount **Rs.4000.00+12%GST=Rs.4480.00** towards cost of tender paper cost by Bank draft drawn in favour of DGM, E.H.T. (O&M) Division, OPTCL, Bolangir, payable at Bolangir. The bid should have accompanied with two sets of tender papers & self attested Photocopy of PAN, GST, and Electrical contractor License. The Tender will be opened in presence of Tenderers or their authorised representatives possessing original authorisation letter. Incomplete Tender shall be rejected.

Date of Sale of Tender Paper: From dt.22.12.2021 to dt.06.01.2022 (During Office Hours)

Last Date of receipt of Tender Paper: dt.07.01.2022 up to 01.30 PM.

Date of Opening of Tender Paper: dt.07.01.2022 at 4.00 PM.

If the last date of receipt/opening of Tender falls on a Holiday, then the tender paper will be received/ opened in the next working days.

The undersigned reserves the right to accept or reject any or all tenders without assigning any reason thereof.

**Deputy General Manager
EHT (O&M) Division Bolangir.**

SCOPE OF WORK:

Name of work:- Repair of earth Retaining wall inside 132/33Kv Grid s/s,Laltikra, Bolangir

<u>Sl No.</u>	<u>Description of Items.</u>	<u>Quantity</u>	<u>Unit</u>
1	Earth Work in excavation in foundation trenches in ordinary soil within 50m, initial lead and 1.5m, initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per direction of the Engineer-in-charge	28.19	Cum
2	Filling in Foundation and plinth with sand watered and rammed, including cost of sand, all labours, T&P reqd. etc. complete.	3.52	Cum
3	Cement Concrete (1:4:8) with 4cm size hard granite metal including cost of all materials, labours T&P reqd. etc. complete.	5.5	Cum
4	Cement concrete (1:11/2:3) with 12mm size broken hard granite chips for R.C.C. works including hoisting and lying including cost of all materials, labours, T&P reqd. etc. complete. (In Foundation & Plinth)	8.22	Cum
5	<i>Rigid and smooth centering and shuttering for R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc</i>	58.29	Sqm.
6	Cement concrete (1:11/2:3) with 12mm size broken hard granite chips for R.C.C. works including hoisting and lying including cost of all materials, labours, T&P reqd. etc. complete. (In Column, wall & Beam)	11.69	Cum
7	<i>Rigid and smooth centering and shuttering for R.C.C. beams, column, girder and bressmer, etc.</i>	228.96	Sqm.
8	Supplying, fitting and placing uncoated HYSD bar reinforcement complete as drawing and technical specification, including cost of all materials, labours, T&P required etc. complete.	24.6	Qntl
9	12mm. Thick cement plaster (1:6) with cement mortar over brick work, including cost of all materials, labours, T&P required etc. complete.	203.04	Sqm
10	Priming 1 coat with any approved Primer, including cost of all materials, labours, T&P required etc. complete. Data for 9.30 Sqm.	203.04	Sqm
11	Supplying & Painting two coats of weather coats over wall surfaces, including cost of all materials, labours, T&P required etc. complete.	203.04	Sqm
12	Cement Concrete with proportion (1:2:4) with using 12mm size hard crusher broken granite chips including cost of all materials and of all labours with T&P as required for the work etc. complete.	0.78	Cum
13	Filling in Foundation and plinth with excavated earth watered and rammed, including cost of sand, all labours, T&P reqd. etc. complete.	28.19	Cum


Deputy General Manager,
E.H.T. (O&M) Division
OPTC, TD Balangir