



(A Government of Odisha Undertaking) CIN – U40102OR2004SGC007553

OFFICE OF THE GENERAL MANAGER, (Elect)

EHT (O&M) Circle, Cuttack.

At: Madhusudan Nagar, P.O: Tulsipur, Cuttack-753008. Tel-(0671)-2970227, E-mail: ehtm.cle.ctc@optcl.co.in

No. EHTM/GM/ETCN/07/CTC/23-24/

383

/Dated, 24.07.2023

E-Tender Call Notice Nos. 07/CTC/2023-24

ADDENDUM NO -1

- The Schedule of Quantity and Technical Specification at Section III & Section IV respectively, of Part I of the tender specification for E-Tender Call Notice number 07/CTC/2023-24 regarding "Supply of 220kV, 132kV & 33kV switchyard Bay Marshalling Kiosks for SAS Project Work (Under PSDF) of 220/132/33kV Grid Substation, Bidanasi", has been revised at parts as per the serial number detailed below and are highlighted / written in red font.
- As the technical specification has been modified, the price bid has been revised and reuploaded accordingly. The tenderers who have already submitted their price, are requested
 to re-submit their price bids.
- All other terms & conditions remain unaltered.

N.B: All subsequent addendums/corrigendum to the tender shall be hosted in the OPTCL's official web site http://www.optcl.co.in and www.tenderwizard.com/OPTCL only.

General Manager (Elec) EHT (O&M) Circle, Cuttack

PART - I SECTION-III

SCHEDULE OF QUANTITY ALONG WITH DELIVERY SCHEDULE

Sl. No	Description of materials.		Total Quantity		
	Description of materials.	Unit	220kV	132kV	33kV
1	Supply of Switchyard Bay Marshalling Kiosks	Nos	4	4	4

PART-I (SECTION-IV)

TECHNICAL SPECIFICATION FOR 220kV, 132kV & 33kV SWITCHYARD BAY MARSHALLING KIOSKS FOR SAS PROJECT WORK (UNDER PSDF) OF 220/132/33kV GRID SUBSTATION, BIDANASI

BAY MARSHALLING KIOSKS

132kV S/Y BMK

Sl. No	Type of Feeder	No. of Feeders	Voltage & Phase	Current rating	Controlled by	Pole & Neutral
5.	Outgoing	6	240V, 1Ø	16A, 10kA	MCB	DP

33kV S/Y BMK

Sl. No	Type of Feeder	No. of Feeders	Voltage & Phase	Current rating	Controlled by	Pole & Neutral
3.	Outgoing	15	415V, 3Ø	32A, 10kA	MCB	TPN (4P)
4.	Outgoing	6	240V, 1Ø	16A, 10kA	MCB	DP

Bill of Quantity

SL. NO.	the tracking the second	TOTAL QTY.			
	DESCRIPTION	220kV BMK	132kV BMK	33kV BMK	MAKE
9	MCB-32A-3P-10KA-C CURVE	18	15	15	L&T/ Legrande / ABB
12	MCB-16A-DP-10KA-C CURVE	5	6	6	L&T/ Legrande / ABB
21	POWER - TERMINAL - BLOCK CONNECTOR - 32A (CATM4)	80	70	70	ELMEX/CON.WELL
22	POWER - TERMINAL - BLOCK CONNECTOR-16A (CATM3)	15	15	15	ELMEX/CON.WELL

General Manager (Elec) EHT (O&M) Circle, Cuttack