

TENDER SUMMARY SHEET

Name of the Work: Construction of common cement structure grid marking pillar with display of name of the Grid Sub-Station pertaining to 132/33KV GSS, Jagatsinghpur, 220/33KV GSS, Godisahi, 132/33KV GSS, Phulnakhara, 132/33KV GSS, Brajabiharipur & 132/33KV GSS, SCBMCH under EHT (O&M) Division Cuttack.

Sl. No.	Particulars	Details
1	NIT No.	07/CTC/2026-27
2	Type of Tender Limited/Open/E-Tender	Open Tender
3	Scope of Work (Pl. furnish the detail/ broad scope of work)	As Annexed
4	Location of Work: Sub-Station/ EHT Line (Particular Location)	1. 132/33KV GSS, Jagatsinghpur. 2. 220/33KV GSS, Godisahi. 3. 132/33KV Phulnakhara. 4. 132/33KV GSS, Brajabiharipur. 5. 132/33KV GSS, SCBMCH.
5	Scope of supply of materials: OPTCL/ Executing Agency (Detail to be furnished)	Executing Agency has to supply all the materials as required.
6	Bid Validity Period (Days)	180 days from the date of opening of the tender
7	Submission of work order towards execution of similar works in Power Utilities for preceeding three years (as applicable)	Nil
8	Requirement of EHT/HT/Civil License/(Class/Type) for executing the work(Specify)	IT PAN, GSTIN Registration Certificate & Civil License (D& above).
9	Brief Summary of Eligibility Criteria (Technical & Financial)	The contractor should have Civil License (D& above).
10	Estimated Cost (Amount in Rs.)	Rs. 4,93,197.00
11	Work Completion Period (Months/Days)	45 Days w.e.f. the issuance of Work Order
12	Basis of Estimate: Rate Contract/Schedule of Rate (Optional)	Schedule of Rate.
13	Tender Cost(Amount in Rs.)	Tender Cost = Rs. 4,93,197.00 only/ Tender Paper Cost = Rs. 2,360.00 only (Incl. of GST). The tender paper cost should be through DDs only in favour of EHT (O&M) Circle, OPTCL, Cuttack payable at Cuttack.
14	Mode of Payment of Tender Cost(Demand Draft/NEFT)	Demand Draft
15	Tender Processing Fees (Incl. of GST) Amount in Rs.	Tender Paper Cost = Rs. 2,360.00 only(Incl. of GST) through DDs only in favour of EHT (O&M) Circle, OPTCL, Cuttack payable at Cuttack.

Ms



16	Tender (Opening & Closing) Period (from DD/MM/YYYY to DD/MM/YYYY)	From 21.10.2026-12:00 Hrs- to 03.11.2026 - 14:30Hrs
17	Date of Pre-Bid meeting (at the request of Bidders) --- Days before closing date	NA
18	Issue of Offline/Online Tender Documents (Bid Sheet/Tender documents) in complete shape (from DD/MM/YYYY to DD/MM/YYYY)	From 21.10.2026-12:00 Hrs- to 03.11.2026 - 14:30Hrs
19	Last date of submission of bid (Upto DD/MM/YYYY.... Hrs.)	Upto 03.11.2026/17:00Hrs.
20	Date & time of opening of Techno-Commercial Bid of Tender(DD/MM/YYYY, ...Hrs.)	04.11.2026/ 16:00 Hrs.
21	Date of opening of price bid of Tender(DD/MM/YYYY, ...Hrs.)	04.11.2026/ 17:00 Hrs.
22	Bid Security or EMD Details/ Exemption Clause (if any)	Rs. 5000.00 only through DDs only in favour of EHT (O&M) Circle, OPTCL, Cuttack payable at Cuttack.
23	Performance Security requirement(...% & period of validity), if applicable	10% of Contract Value & validity for a period of 14 months from the date of completion of the work
24	Payment Terms : After completion / RA Bill based on JMC	1.90% of the value-After completion of work in all respect. 2.Balance 10%- On submission of performance Bank guarantee(Validity of two months more than the guarantee period). 3.The Bill payment along with full taxes & duties (if any) shall be made after successful completion of the work in all respect as per JMC and verification thereof subject to approval of guarantee certificate & performance BG.
25	Guarantee Period (in months)	12(Twelve) months from the date of completion.
26	Liquidated damages /Penalty:	In case the contractor fails to execute by the stipulated completion date, penalty is chargeable @ a sum of half percent (i.e. 0.5 percent) of the contract price for each calendar week or part thereof of limited to maximum of 5% of cost (exclusive of GST) of contract value.
27	MSME related exemptions/ relaxations (if any):	EMD-50% of Actual EMD Value. CPBG-5% of contract value instead of 10%.
28	Contact Person details: Email id and Mobile No.)	Er. Monalisa Sarangi, ehtm.div.ctc@optcl.co.in and 9438908397
NB:	Corrigendum/Addendum to the Tender shall be uploaded in the website of OPTCL. Bidders are requested to view the website (www.optcl.co.in) regularly for updates.	

21/10/2026
Estimator (Elect.)
EHT (O&M) Division

Dy. General Manager (Elect.)
EHT (O&M) Division
OPTCL, Cuttack

NIT No. 07/DIV/2026-27

Name of the Work: Construction of common cement structure grid marking pillar with display of name of the Grid Sub-Station pertaining to 132/33KV GSS, Jagatsinghpur, 220/33KV GSS, Godisahi, 132/33KV GSS, Phulnakhara, 132/33KV GSS, Brajabiharipur & 132/33KV GSS, SCBMCH under EHT (O&M) Division Cuttack.

SCOPE OF WORK

Sl No.	Description	Unit	Quantity
1	Excavation & back filling in hard soil for foundation of equipment & column including supply of all material ,labour,T&P as per instruction of Engineer-in-charge, first depth upto 1 mtr	CUM	6.25
2	Supplying all labour with T&P for filling foundation and plinth with good quality River sand including watering ,ramming etc ,in complete shape including cost ,conveyance, royalties and taxes of all materials and cost of labour .	CUM	3.75
3	Providing P.C.C in the ratio 1:3:6 with supply of 40 mm size black hard crosser broken granite with supply of good quality river sand, cement etc in the dimension.	CUM	2.5
4	Providing .C.C in the ratio 1:2:4 with supply of 20 mm size black hard crosser broken granite with supply of good quality river sand, cement etc in the dimension.	CUM	1.25
5	BRICK MASONRY WORK in first class FA bricks of 25 cm X 12 cm X 8 cm size having crushing strength not less than 75 kg/cm ² with dimension tolerance +/- 2% in cement and sand mortar 1:6 ratio in FP using ,including splays cutting , circular molding & corbelling ,chamfering & similar such type of works ,watering & curing etc, complete including ,cost ,conveyance . royalties & taxes of all materials and cost of all labour with T&P required for the work etc, complete	CUM	19.8
6	PLASTERING (1:6) 16mm thick	CUM	39.6
7	Supply of Black Color JET BLACK 14MM Granite of size 130 sq Ft size and 10 sqft wastage (Granite size More than 1.5 SQM)	SQFT	700
8	Granite laying charges including half-rounding groove ,Border work , splays cutting , circular molding & corbelling ,chamfering & similar such type of works ,watering & curing etc, complete including ,cost of all materials required for the above work ,like Cement ,Marble Paste , M-SEAL, adhesive ,conveyance . royalties & taxes of all materials and cost of all labour with T&P required for the work etc complete, as per the direction of the engineer in-charge .	SQFT	625
9	Supply of stainless steel (304) Grade letter of size 8 inches Each+ OPTCL Logo of Size 15" height .	Inch	715
10	Fitting charges for numbers of Stainless Steel Letter complete including ,cost ,conveyance . Royalties & taxes of all materials and cost of all labour with T&P required for the work etc complete, as per the direction of the engineer in charge	No	80

21/10/26